



BUREAU OF CUSTOMS

MAKABAGONG ADUANA, MATATAG NA EKONOMIYA



PROFESSIONALISM

INTEGRITY

ACCOUNTABILITY

REQUEST FOR QUOTATION

The Bureau of Customs (BOC), through its Administration Office (AO), will undertake a Small Value Procurement for **"Repair and Re-roofing of the Office of XIP and Collection Division of Port of Manila"** in accordance with the Revised Implementing Rules and Regulations of Republic Act No. 9184. The details of the project are as follows:

Name of Project: **Repair and Re-roofing of the Office of XIP and Collection Division of Port of Manila**

Location: **Bureau of Customs Port Area Manila**

Approved Budget for the Contract: **Nine Hundred Ninety-Seven Thousand Seven Hundred Ninety-One Pesos and 20/100 (PHP997,791.20) - inclusive of tax**

Specifications

QTY.	DESCRIPTION
1 LOT	<p>1. Mobilization</p> <ul style="list-style-type: none"> a. Preparation of logistics of contractor's equipment. b. Setting up of Temporary Facilities within the site. c. Setting up of necessary water and power lines required for the Project. <p>2. Demolition Works</p> <ul style="list-style-type: none"> a. Dismantling and subsequent hauling of existing roofing sheet including framing and its accessories. b. Dismantling and subsequent hauling of existing drywalls and all ceiling as indicated on the proposed plan. c. Dismantling and subsequent hauling of existing electrical wiring and auxiliary system affected of demolition works. <p>3. Carpentry Works</p> <ul style="list-style-type: none"> a. Supply and installation of fiber cement board with complete standard metal furring support on all ceiling. b. Supply and Installation of fiber cement board with complete standard metal stud support on all dry wall partition as shown on the plans. c. Fabrication of all architectural finishes and built-in furniture (cabinet and shelves) as shown on the plans.



4. Tile and Flooring Works

- a. Dismantling and subsequent replace of all dilapidated floor tiles.

5. Painting Works

- a. Painting of all interior and exterior walls, partitions and ceiling as per plan.
- b. Painting of all existing doors, windows and cabinets.
- c. Repainting of existing concrete canopy as shown on the plan.

6. Doors and Windows

- a. Supply and installation of all new panel doors with door jamb as shown on the plans including of its accessories.
- b. Supply and installation of transaction windows as shown on the plan.

7. Roofing Works

- a. Dismantling and subsequent replace of all roofing sheet including of its framing and accessories.
- b. Supply and installation of roof canopy on the existing electrical panelboard system located at outside of the concrete walls of the building.

8. Electrical Works

- a. Supply and installation of complete electrical system as shown on the plan.
- b. Supply and installation of wiring devices, switches and outlets, wall receptacles, plates and accessories.
- c. Restoration of other electrical system not shown on the drawings such as power outlets, switches, data and other control wirings.
- d. Complete testing and commissioning of all electrical lighting, power systems.

9. Demobilization

- a. Site clean-up
- b. Hauling of debris materials from project site to appropriate disposal area.
- c. Removal and hauling of tools and equipment from project site.

Work duration: 60 calendar days



BUREAU OF CUSTOMS

MAKABAGONG ADUANA, MATATAG NA EKONOMIYA



PROFESSIONALISM

INTEGRITY

ACCOUNTABILITY

Interested suppliers are required to submit their valid and current Mayor's Permit, DTI/SEC Registration (for partnerships/corporations, General Information Sheet & Articles of Incorporation shall also submit), PHILGEPS Registration Certificate, Omnibus Sworn Statement, Latest Income/Business Tax Return, PCAB License and duly signed price quotation form (Annex "A").

Submission of quotation and eligibility documents in hard copy is on or before **May 10, 2021, 10:00 a.m., at General Services Division (GSD)**, Ground Floor, OCOM Building, Port Area, Manila.

Award of contract shall be made to the lowest quotation, which complies with the minimum description as stated above and other terms and conditions stated in the price quotation form.

Any interlineations, erasures or overwriting shall be valid only if they are signed or initialed by the bidder or his/her duly authorized representative/s.

The BOC reserves the right to accept or reject any or all quotations and to impose additional terms and conditions as it may deem proper.

For inquiry, you may contact us at Telefax no. 527-9757 or email us at bacsecretariat@customs.gov.ph.

Very truly yours,

RAQUEL G. DE JESUS

Acting Chief, General Services Division



BUREAU OF CUSTOMS

MAKABAGONG ADUANA, MATATAG NA EKONOMIYA



PROFESSIONALISM

INTEGRITY

ACCOUNTABILITY

Annex "A"

PRICE QUOTATION FORM

Date:

The Bids and Awards Committee
Bureau of Customs
Port Area, Manila

Project Name: **Repair and Re-roofing of the Office of XIP and Collection Division of Port of Manila**

Sir/Madam:

After having carefully read and accepted the terms and conditions in the Request for Quotation, hereunder is our quotation/s for the items as follows:

DESCRIPTION	QTY		MATERIAL COST		LABOR COST	TOTAL
	#Units	UM	P/Unit	Total		
1. Mobilization /Demobilization	1.00	lot				
2. Demolition Works Dismantling and hauling of all dilapidated dry wall partitions, ceiling, flooring, roofing, electrical system.	1.00	Lot				
3. Carpentry Works <u>Ceiling Works</u>						
a. Wall Angle	25.00	lgth				
b. Main Tee	30.00	lgth				
c. Cross Tee 4'	45.00	lgth				
d. Cross Tee 2'	45.00	lgth				
e. Steel Angle	15.00	lgth				
f. Drive Pin 1"	25.00	pcs				
g. Cartridge .27	25.00	pcs				
h. Suspension Rod 3/8	55.00	lgth				
i. Metal Furring	65.00	lgth				
j. Carrying Channel	50.00	lgth				
k. Blind Rivet	8.00	box				



BUREAU OF CUSTOMS

MAKABAGONG ADUANA, MATATAG NA EKONOMIYA



PROFESSIONALISM

INTEGRITY

ACCOUNTABILITY

l. Black Screw	10.00	box				
m. Fiber Cement Board 6mm	35.00	sht/s				
<u>Dry Walls and Interior Wall Partitions</u>						
a. Metal Studs	45.00	lgth				
b. Metal Tracks	15.00	lgth				
c. Gypsum Board 9mm	15.00	sht/s				
d. Blind Rivet	5.00	box/s				
e. Black Screw	5.00	box/s				
f. Masonry Drill Bit 1/8	10.00	pcs				
g. Metal Drill Bit 1/8	10.00	pcs				
<u>Fabricated Built-in Cabinet, Shelves, Table/Countertop and Design Walls</u>						
a. 3/4" Plyboard	5.00	shts				
b. Cabinet Accessories	1.00	lot				
c. Contact Cement	10.00	bags				
d. Black Screw	500.00	pcs				
e. Common Nail	1.00	lot				
f. Concrete Nail	1.00	lot				
g. Stickwell	2.00	gals				
h. Rugby	1.00	gals				
i. Miscellaneous	1.00	lot				

Subtotal: _____

4. Tiling and Flooring Works						
a. Ceramic floor tiles 60cmx60cm	170.00	Pcs				
b. Adhesive	20.00	bag/s				
c. Grout	15.00	bag/s				
d. Portland Cement	20.00	bags				

Subtotal: _____



BUREAU OF CUSTOMS

MAKABAGONG ADUANA, MATATAG NA EKONOMIYA



PROFESSIONALISM

INTEGRITY

ACCOUNTABILITY

5. Painting Works						
a. Flat Latex	6.00	tins				
b. Semi-Gloss Latex	6.00	tins				
c. QDE	3.00	tins				
d. Flat Wall Enamel	3.00	tins				
e. Laquer Primer	4.00	gals				
f. Paint Thinner	2.00	gals				
g. Paint Roller	1.00	lot				
h. Pollituff	4.00	gals				
i. A/C Paint	1.00	lot				
j. Skim Coat	15.00	bag				
k. Brush	10.00	pcs				
l. Rug	20.00	kgs				
m. Waterproofing	4.00	gal				
n. Miscellaneous	1.00	lot				

Subtotal: _____

6. Doors and Windows						
a. Transaction Window	1.00	set				
b. Wood Panel door with wood jamb (70x185cm)	2.00	set				

Subtotal: _____

7. Roofing and Trusses Works						
a. 20ft Pre-painted Color Roof	60.00	Pcs				
b. Pre-painted gutter	25.00	lm				
c. Ridge Roll	5.00	pcs				
d. Teckscrew	10.00	box				
e. Vulcaseal	2.00	gal				
f. Sealant	5.00	pcs				
g. Angular Bar 3x3x6m	20.00	pcs				
h. Angular Bar 2x2x6m	15.00	pcs				
i. C-Channel 2x5x6m	10.00	pcs				
j. C-Furlin 3x8m	50.00	pcs				
k. Machine Bolt 1x3 w/ knot	10.00	pcs				



BUREAU OF CUSTOMS

MAKABAGONG ADUANA, MATATAG NA EKONOMIYA



PROFESSIONALISM

INTEGRITY

ACCOUNTABILITY

l. Cross Bracing	8.00	pcs				
m. Turn Buckle	4.00	pcs				
n. Welding Rod	4.00	box				
o. Gusset Plate	5.00	pcs				
p. Base Plate	5.00	pcs				

Subtotal: _____

8. Electrical Works

Power, Lightning and Auxiliary System

a. 15mm dia. PVC	45.00	length				
b. 15mm dia. PVC Adaptor with Locknut	35.00	pcs				
c. 15mm dia. Mica Tube	50.00	lm				
d. Junction Box	30.00	pcs				
e. Utility Box	21.00	pcs				
f. Square Box	5.00	pcs				
g. Pullbox	2.00	pcs				

Wires and Cables

a. 3.5mm ² THHN Copper Wire	3.00	box				
b. Cat 5E UTP Cable	100.00	lm				

Wires Devices

a. Two gang Switch	5.00	set				
b. Duplex Convenience Outlet	20.00	set				

Lightning Fixtures

a. LED round panel light	30.00	set				
--------------------------	-------	-----	--	--	--	--

Subtotal: _____



BUREAU OF CUSTOMS

MAKABAGONG ADUANA, MATATAG NA EKONOMIYA



PROFESSIONALISM

INTEGRITY

ACCOUNTABILITY

Work Duration: 60 Calendar Days

Total amount in words:

The above-quoted prices are inclusive of all costs and applicable taxes.

Very truly yours,

Name/ Signature of Representative

Name of Company

Mayor's Permit No. _____

PhilGEPS Registration No. _____

(Please submit the photocopies of the above documents upon submission of quotation)

Direct Cost	
Material Cost	
Labor Cost	
Mobilization	
Total Direct Cost	_____
Indirect Cost	
OCM (15% of DC)	
Contractors Profit (10% of DC)	
Total Indirect Cost	
Tax (5% of DC + IC)	_____
TOTAL PROJECT COST	_____