



Republic of the Philippines
Department of Finance
Bureau of Customs
1099 Manila

REQUEST FOR QUOTATION

The Bureau of Customs (BOC), through its Administration Office (AO), will undertake a Small Value Procurement for "**Repair and Renovation of Customs Clearance Area (CCA) Office at Tipo Gate, Port of Subic**" in accordance with the Revised Implementing Rules and Regulations of Republic Act No. 9184. The details of the project are as follows:

Name of Project : **Repair and Renovation of Customs Clearance Area (CCA) Office at Tipo Gate, Port of Subic**
Location : **Port of Subic**
Approved Budget for the Contract: **Nine Hundred Ninety-three Thousand Seven Hundred Forty-six Pesos and 77/100 (Php 993,746.77) – inclusive of tax**

Specifications

QTY.	DESCRIPTION
1 LOT	<ol style="list-style-type: none">1. Mobilization<ol style="list-style-type: none">a. Preparation of logistics of contractor's equipment.b. Setting up of Temporary Facilities within the site.c. Setting up of necessary water and power lines required for the Project's repair and renovation.2. Demolition Works<ol style="list-style-type: none">a. Dismantling and subsequent hauling of existing drywall, ceiling, windows, roof and roof framingb. Dismantling and subsequent hauling of existing plumbing fixture, piping and accessories.3. Excavation Works<ol style="list-style-type: none">a. Excavation of sewerage pipeline to existing septic tank.4. Masonry and Concreting Works<ol style="list-style-type: none">a. Supply and installation of CHB wall and subsequent plastering of interior and exterior wall on the proposed pantry and quarter room.5. Steel Works<ol style="list-style-type: none">a. Supply and installations of roof framing, roof trusses and rafters.6. Doors and Windows Works<ol style="list-style-type: none">a. Supply and installation of doors and windows as shown on the plans and door and windows schedule<ol style="list-style-type: none">i. Transaction windowii. Sliding windows for Pantry and Quarter Roomiii. Panel Door on Main Entrance, Storage and Quarters room7. Roofing Works

- a. Supply and installation of roofing sheets and its accessories

8. Electrical Works

- a. Dismantling of existing lighting fixture, wiring devices, roughing-ins/raceways and accessories.
- b. Restoration of any unforeseen auxiliary and electrical wiring system of other circuit home run affected during demolition works
- c. Supply and installation of complete electrical system as indicated on the plans
- d. Supply and installation of wiring devices, switches and outlets, wall receptacles, plates and accessories
- e. Restoration of other electrical system not shown on the drawings such as power outlets, switches, data and other control wirings.
- f. Complete testing and commissioning of all electrical lighting, power systems

9. Plumbing Works

- a. Dismantling of malfunctioning plumbing fixtures such as water, closet, lavatory, urinal, soap, holder, tissue holder and all fittings and accessories
- b. Supply and installation of new plumbing fixture and accessories as indicated on the plans.
- c. Re-piping of water distribution and sanitary system.

10. Carpentry Works

- a. Supply and installation of fiber cement board with complete standard metal furring support on all ceiling and dry wall partition as shown on the plans.

11. Tile Works

- a. Supply and installation of floor tiles on the proposed pantry and quarter's room.
- b. Supply and installation of floor and wall tiles on the comfort room.

12. Painting Works

- a. Painting of all newly installed ceiling
- b. Repainting of all interior and exterior walls.
- c. Painting of new roofing and subsequent the application of roof sealant.

13. Canopy Works

- a. Supply and installation of 3m x 5.2 Steel Canopy on the transaction area including of its roofing system with downspout and electrical system.

14. Demobilization

- a. Site clean-up
- b. Hauling debris materials from project site to appropriate disposal area.
- c. Removal and hauling of tools and equipment from project site.

Work Duration: 65 Calendar Days
--

Interested suppliers are required to submit their valid and current Mayor's Permit, DTI/SEC Registration (for partnerships/corporations, General Information Sheet & Articles of Incorporation shall also be submitted), PHILGEPS Registration Certificate, Omnibus Sworn Statement, Latest Income/Business Tax Return, and duly signed price quotation form (Annex "A").

Submission of quotation and eligibility documents is on or before October 15, 2019, 10:00 a.m., at General Services Division (GSD), Ground Floor, OCOM Building, Port Area, Manila.

Award of contract shall be made to the lowest quotation, which complies with the minimum description as stated above and other terms and conditions stated in the price quotation form.

Any interlineations, erasures or overwriting shall be valid only if they are signed or initialed by the bidder or his/her duly authorized representative/s.

The BOC reserves the right to accept or reject any or all quotations and to impose additional terms and conditions as it may deem proper.

For inquiry, you may contact us at Telefax no. 527-9757 or email us at bacsecretariat@customs.gov.ph.

Very truly yours,



RAQUEL G. DE JESUS

Acting Chief, General Services Division

Annex "A"

PRICE QUOTATION FORM

Date:

The Bids and Awards Committee
Bureau of Customs
Port Area, Manila

Sir/Madam:

After having carefully read and accepted the terms and conditions in the Request for Quotation, hereunder is our quotation/s for the items as follows:

DESCRIPTION	QTY		MATERIAL COST	
	#Units	UM	P/Unit	Total
A. Mobilization/Demobilization	1.00	lot		
B. Demolition Works <ul style="list-style-type: none">Dismantling and hauling of existing dry wall, ceiling, windows, roofing and framingDismantling and hauling of existing plumbing fixture, pipings and accessories	1.00 1.00	lot lot		
C. Excavation Works <ul style="list-style-type: none">Excavation of sewerage pipeline to existing septic tank	1.00	lot		
D. Masonry and Concreting Works <ul style="list-style-type: none">CementSandGravel $\frac{3}{4}$Gravel $\frac{1}{2}$ (Gravita)CHB 5"CHB 4"10 mm Deformed Bars9 mm Deformed Bars	68.00 7.00 3.70 1.30 626.00 30.00 69.00 28.00	bags cu.m. cu.m. cu.m. pcs pcs pcs pcs		

<ul style="list-style-type: none"> • Tie wire # 16 	20.00	kls		
E. Steel Works <ul style="list-style-type: none"> • 2x2 angle bar • 1 1/2 angle bar • 2x3 C-purlins • 2x6 C-purlins • Sag rod 10mm round bar • Welding rod 	15.00 14.00 35.00 11.00 6.00 30.00	pcs pcs pcs pcs pcs kls		
F. Doors and Windows Works <ul style="list-style-type: none"> • 1.2x1.2 Aluminum Sliding Window • Panel door with door jambs • Door knobs 	3.00 3.00 3.00	unit unit sets		
G. Roofing Works <ul style="list-style-type: none"> • GA # 24 corrugated GI roofing sheet 3.66m • GA # 24 end flushing • Tek screw • blind rivets • vulcaseal 400cc 	44.00 26.00 800.00 4.00 2.00	pcs pcs pcs box can		
H. Electrical Works <ul style="list-style-type: none"> • Led lighting with housing • Wires and Cables • Roughing ins • Gang switches • AC outlets • Electrical tape 	44.00 26.00 800.00 4.00 2.00	pcs pcs pcs box can		
I. Plumbing Works <ul style="list-style-type: none"> • Gate valve 1/2" • Gate Valve 3/4" 	2.00 1.00	pcs. pcs.		

<ul style="list-style-type: none"> • PVC Pipe 1/2" • PVC Pipe 3/4" • PVC Adaptor 1/2" • PVC Adaptor 3/4" • Lavatory Faucet • PVC Coupling 1/2" • PVC Couling 3/4" • 3" PVC Sanitary pipes • 3" PVC Elbow 90deg • 3" PVC Elbow 45deg • 3"x3"PVC Wye • 2" PVC Sanitary pipes • 2" PVC Elbow 90deg • 2" PVC Elbow 45deg • 2"x2"PVC Wye • PVC Solvent Cement • Floor drain • Water Closet W/ accessories • Lavatory • Face Mirror • consumables 	<p>4.00 2.00 12.00 14.00 3.00 14.00 12.00 4.00 3.00 5.00 3.00 4.00 4.00 3.00 2.00 2.00 1.00 1.00 1.00 1.00 1.00</p>	<p>length length pcs pcs pcs pcs length pcs pcs pcs pcs pcs pcs can pcs set set pcs. Lot</p>		
<p>J. Carpentry Works</p> <ul style="list-style-type: none"> • 1"x1" shelf angle • wall angle 10' • Metal furrings • Metal Studs • Furring clip • tie wire # 16 • 4.5mm thk. fiber cement board • Rivets • Black screw • Drill bit 	<p>80.00 58.00 149.00 35.00 250.00 1.50 45.00 12.00 3,000.00 35.00</p>	<p>pcs pcs pcs pcs pcs kls pcs box pcs pcs</p>		
<p>K. Tiles Work</p> <ul style="list-style-type: none"> • 40x40 Ceramic tiles • 20x20 floor tiles • 20x30 wall tiles • Tile adhesive • Tile grout 	<p>170.00 95.00 350.00 45.00 25.00</p>	<p>pcs pcs pcs bags kls</p>		

<p>L. Painting Works</p> <ul style="list-style-type: none"> • Latex paint flat • Latex paint gloss • Enamel paint flat • Enamel paint gloss • Red oxide • Paint thinner • Paint brush # 1 • Paint brush # 2 • Paint brush # 2 	<p>3.00 3.00 4.00 3.00 3.00 3.00 12.00 12.00 16.00</p>	<p>tins tins gal gal gal gal pcs pcs pcs</p>		
<p>M. Canopy Works</p> <ul style="list-style-type: none"> • 3mx5.2m Canopy 	<p>1.00</p>	<p>lot</p>		

Work Duration: 65 Calendar Days

Total amount in words:

The above-quoted prices are inclusive of all costs and applicable taxes.

Very truly yours,

Name/ Signature of Representative

Name of Company

Mayor's Permit No. _____

PhilGEPS Registration No. _____

(Please submit the photocopies of the above documents upon submission of quotation)