



REQUEST FOR QUOTATION

The Bureau of Customs (BOC), through its Administration Office (AO), will undertake a Small Value Procurement for Renovation of Comfort Room and Pantry of BOC Media Lounge, in accordance with the Revised Implementing Rules and Regulations of Republic Act No. 9184. The details of the project are as follows:

Name of Project: Renovation of Comfort Room and Pantry of BOC Media Lounge
Location: BOC Media Lounge
Approved Budget for the Contract: One Hundred Twenty Thousand Pesos (120,000.00)-inclusive of tax

Specifications :

QTY.	SCOPE OF WORKS
1 lot	<p>A. CIVIL, ARCHITECTURAL, ELECTRICAL AND MECHANICAL WORKS >DISMANTLING, DEMOLITION AND HAULING-OUT WORKS</p> <ul style="list-style-type: none">I. Dismantling of existing wall and floor tiles at CRII. Dismantling of water closet and accessories at CRIII. Dismantling of ceiling board at CR and pantry including cornice and coveIV. Dismantling of door at CRV. Dismantling of wall hung lavatoryVI. Dismantling of soap holderVII. Dismantling of tissue holderVIII. Dismantling of metma floor drainIX. Cleaning of site and hauling-out of debris/wastes <p>B. FINISHES >Ceiling Finishes -4.5mm THK cement fiber ceiling on .40mm THK x 19mm x 25mm metal furring channel and 1.00mm THK x 12mm THK x 38mm carrying channel spaced @ 1.20m O.C (pantry, CRs,)</p> <p>> Tiles finishes - 600mm x 600mm homogeneous tiles (polish finish; color: beige (HE604); louie valentino porcelato) at pantry - 300mm x 300mm granite floor tiles</p> <p>> Wall Finishes - 300mm x 300mm granite wall tiles</p> <p>C. DOORS/DOOR JAMBS - PVC hollow core flush-type door/door jamb with louver vent for CRs</p> <p>D. PAINTING WORKS -Flat latex paint finish a.) Ficemboard ceiling at hallway, pantry,CRs, and supply/ records rooms)</p> <p>E. PLUMBING WORKS - Water closet-white, New Esedra 2819 3/4.5 L Dual flush button-including fittings/accessories American Standard - New Codie 450mm round wall-hung lavatory by American standard w/ 1501 saga lavatory faucet incl. fitting and acc. - Tissue holder - 4"x4" metma floor drain - Soap holder -1/4" thk x 1.1mH mirror w/ aluminum frame at CRs</p>

Delivery Term: Fifteen (15) calendar days from signing of Purchase Order

ll

Interested suppliers are required to submit their valid and current Mayor's Permit and PHILGEPS Registration Certificate and DTI/Sec Registration, Bill of Quantity/Detailed Estimate and duly signed price quotation form (Annex "A").

Submission of quotation and eligibility documents is on or December 10, 2015 10:00 a.m., at General Services Division (GSD), Ground Floor, OCOM Building, Port Area, Manila.


Award of contract shall be made to the lowest quotation, which complies with the minimum description as stated above and other terms and conditions stated in the price quotation form.

Any interlineations, erasures or overwriting shall be valid only if they are signed or initialled by the bidder or his/her duly authorized representative/s.

The BOC reserves the right to accept or reject any or all quotations and to impose additional terms and conditions as it may deem proper.

For inquiry, you may contact us at Telefax no. 527-9757 or email us at bocbacsecretariat2014@gmail.com

Very truly yours,


DIMPNA O. LEJOS
OIC-Director, Administration Office

Annex "A"

PRICE QUOTATION FORM

Date

The Bids and Awards Committee
Bureau of Customs
Port Area, Manila

Sir/Madam:

After having carefully read and accepted the terms and conditions in the Request for Quotation, hereunder is our quotation/s for the items as follows:

Quantity	Description	Unit Price	Total Price
1 lot	<p>E. CIVIL, ARCHITECTURAL, ELECTRICAL AND MECHANICAL WORKS >DISMANTLING, DEMOLITION AND HAULING-OUT WORKS</p> <p>X. Dismantling of existing wall and floor tiles at CR XI. Dismantling of water closet and accessories at CR XII. Dismantling of ceiling board at CR and pantry including cornice and cove XIII. Dismantling of door at CR XIV. Dismantling of wall hung lavatory XV. Dismantling of soap holder XVI. Dismantling of tissue holder XVII. Dismantling of metma floor drain XVIII. Cleaning of site and hauling-out of debris/wastes</p> <p>F. FINISHES >Ceiling Finishes -4.5mm THK cement fiber ceiling on .40mm THK x 19mm x 25mm metal furring channel and 1.00mm THK x 12mm THK x 38mm carrying channel spaced @ 1.20m O.C (pantry, CRs,) > Tiles finishes - 600mm x 600mm homogeneous tiles (polish finish; color: beige (HE604); louie valentino porcelato) at pantry - 300mm x 300mm granite floor tiles > Wall Finishes - 300mm x 300mm granite wall tiles</p> <p>G. DOORS/DOOR JAMBS - PVC hollow core flush-type door/door jamb with louver vent for CRs</p> <p>H. PAINTING WORKS -Flat latex paint finish -Ficemboard ceiling at hallway, pantry,CRs, and</p>		

	<p style="text-align: center;">supply/ records rooms)</p> <p>E. PLUMBING WORKS</p> <ul style="list-style-type: none"> - Water closet-white, New Esedra 2819 3/4.5 L <p>Dual flush button-including fittings/accessories American Standard</p> <ul style="list-style-type: none"> - New Codie 450mm round wall-hung lavatory by American standard w/ 1501 saga lavatory faucet incl. fitting and acc. - Tissue holder - 4"x4" metma floor drain - Soap holder -1/4" thk x 1.1mH mirror w/ aluminum frame at CRs 		
--	---	--	--

Total amount in words:

The above-quoted prices are inclusive of all costs and applicable taxes.
Very truly yours,

Name/ Signature of Representative

Name of Company

Mayor's Permit No. _____

PhilGEPS Registration No. _____

(Please submit the photocopies of the above documents upon submission of quotation)