



Republic of the Philippines  
Department of Finance  
**Bureau of Customs**  
1099 Manila

## REQUEST FOR QUOTATION

The Bureau of Customs (BOC), through its Administration Office (AO), will undertake a second Small Value Procurement for "**Improvement of Pathway and Repair and Rehabilitation of Main Sewer Line of IAS Building**" in accordance with the Revised Implementing Rules and Regulations of Republic Act No. 9184. The details of the project are as follows:

Name of Project : **Improvement of Pathway and Repair and Rehabilitation of Main Sewer Line of IAS Building**  
Location : **Bureau of Customs Port Area Manila**  
Approved Budget for the Contract: **Nine Hundred Forty Nine Thousand One Hundred Eighty Eight Pesos and Fifty Five Centavos (Php 949,188.55) inclusive of tax**

### Specifications

<b>QTY.</b>	<b>DESCRIPTION</b>
LOT	<ul style="list-style-type: none"><li><b>1. Mobilization</b><ul style="list-style-type: none"><li>a. Preparation of logistics of contractor's equipment.</li><li>b. Setting up of Temporary Facilities within the site.</li><li>c. Setting up of necessary water and power lines required for the Project's repair and renovation.</li></ul></li> <li><b>2. Demolition Works</b><ul style="list-style-type: none"><li>d. Dismantling and subsequent hauling of existing main sewer line and pavement.</li></ul></li> <li><b>2. Relocation of Existing ACU</b><ul style="list-style-type: none"><li>a. Dismantling and subsequent the relocation of existing air-conditioning condensing unit located at beside BOC Gymnasium.</li></ul></li> <li><b>3. Painting Works</b><ul style="list-style-type: none"><li>a. Painting of all newly installed ceiling.</li><li>b. Repainting of all interior and exterior walls.</li><li>c. Painting of new roofing and subsequent the application of roof sealant.</li></ul></li> <li><b>4. Steel Works</b></li></ul>

Omnibus Sworn Statement, Latest Income/Business Tax Return, PCAB License and duly signed price quotation form (Annex "A").

Submission of quotation and eligibility documents is on or before December 2, 2019, 10:00 a.m., at General Services Division (GSD), Ground Floor, OCOM Building, Port Area, Manila.

Award of contract shall be made to the lowest quotation, which complies with the minimum description as stated above and other terms and conditions stated in the price quotation form.

Any interlineations, erasures or overwriting shall be valid only if they are signed or initialed by the bidder or his/her duly authorized representative/s.

The BOC reserves the right to accept or reject any or all quotations and to impose additional terms and conditions as it may deem proper.

For inquiry, you may contact us at Telefax no. 527-9757 or email us at [bacsecretariat@customs.gov.ph](mailto:bacsecretariat@customs.gov.ph).

Very truly yours,



**RAQUEL G. DE JESUS**

Acting Chief, General Services Division

	<p>a. Supply and installation of steel roof framing and its accessories as per plan.</p> <p><b>5. Roofing Works</b></p> <p>a. Supply and installation roofing and its accessories as per plan.</p> <p><b>6. Electrical Works</b></p> <p>a. Supply and installation of complete electrical system.</p> <p>b. Supply and installation of wiring devices, switches and outlets, wall receptacles, plates and accessories.</p> <p>c. Restoration of other electrical system not shown on the drawings such as power outlets, switches, data and other control wirings.</p> <p>d. Complete testing and commissioning of all electrical lighting, power systems.</p> <p><b>7. Plumbing Works</b></p> <p>a. Supply and installation of downspout and storm drainage system.</p> <p>b. Re-piping of existing main sanitary line.</p> <p><b>8. Masonry Works</b></p> <p>a. Concrete pavement as per plan.</p> <p><b>9. Tiling Works</b></p> <p>a. Supply and installation of floor tiles as per plan.</p> <p><b>10. Aluminum Works</b></p> <p>a. Supply and installation of glass door and window with aluminum framing as shown on the plan.</p> <p><b>11. Carpentry Works</b></p> <p>a. Supply and Installation of fiber cement board with complete standard metal furring support on all ceiling.</p> <p><b>12. Demobilization</b></p> <p>a. Site clean-up</p> <p>b. Hauling of debris materials from project site to appropriate disposal area.</p> <p>c. Removal and hauling of tools and equipment from project site.</p>
--	--

Interested suppliers are required to submit their valid and current Mayor's Permit, DTI/SEC Registration (for partnerships/corporations, General Information Sheet & Articles of Incorporation shall also submitted), PHILGEPS Registration Certificate,

Annex "A"

### PRICE QUOTATION FORM

Date:

The Bids and Awards Committee  
Bureau of Customs  
Port Area, Manila

Sir/Madam:

After having carefully read and accepted the terms and conditions in the Request for Quotation, hereunder is our quotation/s for the items as follows:

DESCRIPTION	QTY		MATERIAL COST	
	#Units	UM	P/Unit	Total
<b>1. Mobilization</b>	1.00	lot		
<b>2. Demolition Works</b> <ul style="list-style-type: none"><li>• Dismantling of existing sewer line and pavement</li></ul>	54.00	sq.m.		
<b>3. Relocation of Existing ACU</b>	1.00	lot		
<b>4. Painting Works</b> <ul style="list-style-type: none"><li>• Semi-Gloss Latex</li><li>• Flat Latex</li><li>• Gypsum Putty</li><li>• Masonry Putty</li><li>• Concrete Neutralizer</li><li>• Patching Compound</li><li>• Consumables</li></ul>	12.00 9.00 6.00 3.00 8.00 24.00 1.00	gals gals gals gals gals kgs lot		

<b>5. Steel Works</b> <ul style="list-style-type: none"> <li>• C-Channel 2x5x6m</li> <li>• C-Purlins 2x5x6m</li> <li>• Zag Rod 5/8</li> <li>• I-Beam 4x6x6m</li> <li>• Welding Rod</li> <li>• Flat Bar</li> <li>• Deformed bar 10mmx6m</li> <li>• Steel Stiffener</li> <li>• Miscellaneous</li> </ul>	15.00 18.00 10.00 6.00 3.00 6.00 90.00 9.00 1.00	pcs pcs pcs pcs box pcs sets length lot		
<b>6. Roofing Works</b> <ul style="list-style-type: none"> <li>• Pre-Painted Roofing</li> <li>• Ridge Roll</li> <li>• End Wall Flushing</li> <li>• Gutter</li> <li>• Text Screw</li> <li>• Blind Rivets 1/8x2</li> <li>• Silicon Rubber Sealant</li> <li>• Touch-up Paint</li> <li>• Concrete Nail 2"</li> <li>• PVC Pipe 2 1/2x6m</li> </ul>	26.00 61.00 40.00 30.00 300.00 1500.00 10.00 4.00 8.00 6.00	pcs lm lm lm pcs pcs pcs ltr kgs pcs		
<b>7. Electrical Works</b> <ul style="list-style-type: none"> <li>• Panel Board</li> <li>• Leg Light</li> <li>• One single switch in one plate cover</li> <li>• Two single switch in one plate cover</li> <li>• Duplex universal convenience outlet</li> <li>• 15mm dia. PVC flexible conduit pipe</li> </ul>	1.00 20.00 12.00 12.00 12.00 4.00	set pcs sets sets sets rols		

<ul style="list-style-type: none"> <li>• 15mm dia. Rigid conduit pipe</li> <li>• 15mm. dia. PVC elbow</li> <li>• 15mm dia. PVC adapter</li> <li>• 15mm dia. Locknut</li> <li>• 15mm dia. PVC bushing</li> <li>• 1" PVC Plastic Molding</li> <li>• 3.5mm<sup>2</sup> THHN copper wire stranded</li> <li>• Junction Box</li> <li>• Utility Box</li> <li>• Square Box</li> </ul>	<p>8.00</p> <p>22.00</p> <p>22.00</p> <p>22.00</p> <p>22.00</p> <p>18.00</p> <p>1.00</p> <p>13.00</p> <p>8.00</p> <p>3.00</p>	<p>length</p> <p>pcs</p> <p>pcs</p> <p>pcs</p> <p>pcs</p> <p>length</p> <p>box</p> <p>pcs</p> <p>pcs</p> <p>pcs</p>		
<p><b>8. Plumbing Works</b></p> <ul style="list-style-type: none"> <li>• 6" PVC Sanitary pipes</li> <li>• 6" PVC Elbow 90deg</li> <li>• 6" PVC Elbow 45deg</li> <li>• 6"x6"PVC Wye</li> <li>• 4" PVC Sanitary pipes</li> <li>• 4" PVC Elbow 90deg</li> <li>• 4" PVC Elbow 45deg</li> <li>• 4"x4" PVC Wye</li> <li>• PVC Solvent Cement</li> </ul>	<p>5.00</p> <p>6.00</p> <p>6.00</p> <p>3.00</p> <p>10.00</p> <p>5.00</p> <p>7.00</p> <p>4.00</p> <p>4.00</p>	<p>length</p> <p>pcs</p> <p>pcs</p> <p>pcs</p> <p>pcs</p> <p>pcs</p> <p>pcs</p> <p>pcs</p> <p>pcs</p>		
<p><b>9. Masonry Works</b></p> <ul style="list-style-type: none"> <li>• Portland Cement</li> <li>• Gravel</li> <li>• Sand</li> <li>• Plastering Sand</li> <li>• CHB</li> </ul>	<p>120.00</p> <p>3.00</p> <p>6.00</p> <p>300.00</p> <p>200.00</p>	<p>bags</p> <p>cu.m.</p> <p>cu.m.</p> <p>bags</p> <p>pcs</p>		
<p><b>10. Tiling Works</b></p> <ul style="list-style-type: none"> <li>• Ceramic Floor Tiles 60x60</li> <li>• Tile grout</li> </ul>	<p>100.00</p> <p>4.00</p>	<p>pcs</p> <p>bags</p>		
<p><b>11. Glass Works</b></p> <ul style="list-style-type: none"> <li>• 1.00x100x2.10 tempered glass door with aluminum frame</li> <li>• 1.20x120 tempered glass window with aluminum frame</li> </ul>	<p>1.00</p> <p>2.00</p>	<p>set</p> <p>sets</p>		
<p><b>12. Carpentry Works</b></p> <ul style="list-style-type: none"> <li>• Finishing nail</li> <li>• Concrete nail</li> <li>• Rugby</li> <li>• Ficem screw 7x25</li> <li>• Stikwell</li> </ul>	<p>4.00</p> <p>3.00</p> <p>3.00</p> <p>780.00</p> <p>3.00</p>	<p>kgs</p> <p>kgs</p> <p>gals</p> <p>pcs</p> <p>ltr</p>		

• ½"x1"x10" S4S KD	12.00	pcs		
• Soft Closing concealed hinges #2	16.00	pairs		
• Dual lock	8.00	pairs		
• ¼ thk Cement Fiber Board	30.00	shts		
• Consumables	1.00	lot		

**Work Duration: 45 Calendar Days**

Total amount in words:

The above-quoted prices are inclusive of all costs and applicable taxes.

Very truly yours,

\_\_\_\_\_  
Name/ Signature of Representative

\_\_\_\_\_  
Name of Company

Mayor's Permit No. \_\_\_\_\_

PhilGEPS Registration No. \_\_\_\_\_

(Please submit the photocopies of the above documents upon submission of quotation)

**BUREAU OF CUSTOMS**  
**GENERAL SERVICES DIVISION**  
 BUILDING AND MAINTENANCE SECTION  
 OCOM Bldg. Port Area, Manila

**BILL OF QUANTITIES**

**Project Title : Improvement of Pathway and Repair and Rehabilitation of Main Sewer Line of IAS Building**

Sheet No.: 2 of 2

**Location : VCD Compound, Gate 3, South Harbor, Port Area, Manila**

Date: 10/17/2019

DESCRIPTION	QTY		MATERIAL COST		LABOR COST	TOTAL
	# Units	UM	P/Unit	Total		
<b>A. Mobilization/Demobilization</b>						
	1.00	lot				
<b>B. Demolition Works</b>						
Dismantling of existing sewer line and pavement	54.00	sq.m.				
<b>C. Relocation of Existing ACU</b>						
	1.00	lot				
<b>D. Painting Works</b>						
Semi-Gloss Latex	12.00	gals				
Flat Latex	9.00	gals				
Gypsum Putty	6.00	gals				
Masonry Putty	3.00	gals				
Concrete Neutralizer	8.00	gals				
Patching Compound	24.00	kgs				
Consumables	1.00	lot				
<b>E. Steel Works</b>						
C-Channel 2x5x6m	15.00	pcs				
C-Purlins 2x5x6m	18.00	pcs				
Zag Rod 5/8	10.00	pcs				
I-Beam 4x6x6m	6.00	pcs				
Welding Rod	3.00	box				
Flat Bar	6.00	pcs				
Deformed Bar 10mmx6m	90.00	sets				
Steel Stiffener	9.00	length				
Miscellaneous	1.00	lot				
<b>Roofing Works</b>						
Pre-Painted Roofing	26.00	pcs				
Ridge Roll 0.40mmx0.60mmxLS	61.00	lm				
End Wall Flushing 0.40mmx0.60mmxLS	40.00	lm				
Gutter 0.40mmx0.60mmxLS	30.00	lm				
Text Screw	300.00	pcs				
Blind Rivets 1/8x2	1,500.00	pcs				
Silicon Rubber Sealant	10.00	pcs				
Touch-up Paint	4.00	ltr				
Concrete Nail 2"	8.00	kgs				
PVC Pipe 2 1/2x6m	6.00	pcs				
<b>Electrical Works</b>						
Panel Board	1.00	set				
ed light	20.00	pcs				



DESCRIPTION	QTY		MATERIAL COST		LABOR COST	TOTAL
	# Units	UM		Total		
One single switch in one plate cover	12.00	sets				
Two single switch in one plate cover	12.00	sets				
Duplex universal convenience outlet	12.00	sets				
15mm dia. PVC flexible conduit pipe	4.00	rolls				
15mm dia. PVC rigid conduit pipe	8.00	length				
15mm dia. PVC elbow	22.00	pcs				
15mm dia. PVC adapter	22.00	pcs				
15mm dia. PVC locknut	22.00	pcs				
15mm dia. PVC bushing	22.00	pcs				
1"PVC Plastic molding	18.00	length				
3.5mm2 THHN copper wire stranded	1.00	box				
Junction Box	13.00	pcs				
Utility Box	8.00	pcs				
Square Box	3.00	pcs				
<b>H. Plumbing Works</b>						
6" PVC Sanitary pipes	5.00	length				
6" PVC Elbow 90deg	6.00	pcs				
6" PVC Elbow 45deg	6.00	pcs				
6"x6"PVC Wye	3.00	pcs				
4" PVC Sanitary pipes	10.00	pcs				
4" PVC Elbow 90deg	5.00	pcs				
4" PVC Elbow 45deg	7.00	pcs				
4"x4"PVC Wye	4.00	pcs				
PVC Solvent Cement	4.00	pcs				
<b>I. Masonry Works</b>						
Portland Cement	120.00	bags				
Gravel	3.00	cu. m.				
Sand	6.00	cu. m.				
Plastering Sand	300.00	bags				
CHB	200.00	pcs				
<b>Tiling Works</b>						
Ceramic Floor Tiles 60x60	100.00	pcs				
Tile grout	4.00	bags				
<b>Glass Works</b>						
1.00x100x2.10 tempered glass door with aluminum frame	1.00	set				
1.20x120 Tempered glass window with aluminum frame	2.00	sets				
<b>Carpentry Works</b>						
Finishing Nail	4.00	kgs				
Concrete Nail	3.00	kgs				
Rugby	3.00	gals				
Ficem screw 7x25	780.00	pcs				
Stikwell	3.00	ltr				
1/2"x1"x10" S4S KD	12.00	pcs				
Soft closing concealed hinges #2	16.00	pairs				
Dual lock	8.00	pairs				

DESCRIPTION	QTY		MATERIAL COST		LABOR COST	TOTAL
	# Units	UM	P/Unit	Total		
1/4 thk Cement Fiber Board	30.00	shts				
Consumables	1.00	lot				

Prepared by:

  
**GARY E. AGUILAR**  
 Technical Staff  
 General Services Division

  
**GENBERT S. GUSAGO**  
 Technical Assistant  
 General Services Division


**Direct Cost**  
 Material Cost  
 Labor Cost  
 Mobilization  
**Total Direct Cost**

**Indirect Cost**  
 OCM (15% of DC)  
 Contractors Profit (10% of DC)  
**Total Indirect Cost**

Tax (5% of DC + IC)

**TOTAL PROJECT COST**

Reviewed by:

  
**ENGR. CECIL G. FABIAN**  
 Administrative Officer IV  
 General Services Division

Noted by:

  
**RAQUEL G. DE JESUS**  
 Acting Chief  
 General Services Division

Recommending approval:

  
**DONATO B. SAN JUAN**  
 Deputy Commissioner  
 Internal Administration Group

Approved by:

  
**REY LEONARDO B. GUERRERO**  
 Commissioner  
 Bureau of Customs