



REQUEST FOR QUOTATION

The Bureau of Customs (BOC), through its Administration Office (AO), will undertake a Small Value Procurement for **“Repainting of BOC Entrance Gate and Perimeter Fence and Front Façade of OCOM Building”** in accordance with the Revised Implementing Rules and Regulations of Republic Act No. 9184. The details of the project are as follows:

Name of Project: **Repainting of BOC Entrance Gate and Perimeter Fence and Front Façade of OCOM Building**

Location: **General Services Division, OCOM Building, Gate 3, South Harbor, Port Area, Manila**

Approved Budget for the Contract: **Nine Hundred Eighty - Nine Thousand Eight Hundred Six and Sixty - Two Centavos (PHP989,806.62) inclusive of tax**

Specifications:

QTY.	DESCRIPTION
1 LOT	<p>SCOPE OF WORKS</p> <p>A. Mobilization</p> <ul style="list-style-type: none"> a. Preparation of logistics of contractor’s equipment. b. Setting up of necessary water and power lines required for the Project. <p>B. Painting Works</p> <ul style="list-style-type: none"> a. Repainting of the walls of the OCOM Building. b. Repainting of interior lobby including its walls and ceilings. c. Supply and installation of scaffoldings and platforms to be used in the works. <p>C. Foyer Change Ceiling</p> <ul style="list-style-type: none"> a. Dismantling of existing ceiling of the foyer. b. Proper hauling and subsequent disposal of construction debris produced by the dismantling of the existing foyer ceiling.



- c. Supply and installation of replacement foyer ceiling along with all of its accessories.
- d. Painting of replaced ceiling as specified.

D. Demolition of Walkway

- a. Demolition of existing walkway and canopy.
- b. Proper hauling and subsequent disposal of construction debris produced by the dismantling of the walkway and canopy.

E. Replacement of Tiles at Flagpole

- a. Dismantling of existing tiles located at the base of the flagpole.
- b. Proper hauling and subsequent disposal of construction debris produced by the dismantling of existing tiles.
- c. Supply and installation of replacement tiles (60x60cm ceramic tiles).

F. Removal of Window Grill

- a. Dismantling of existing window grills.
- b. Retouch of masonry affected by the removal of window grills.
- c. Hauling and set-up of scaffolding that will be used.

G. Demobilization

- a. Site clean-up.
- b. Hauling of debris materials from project site to appropriate disposal area.
- c. Removal and hauling of tools and equipment from project site.

Work Duration: 60 Calendar Days

Interested suppliers are required to submit **original/certified true copy** of the following: valid and current Mayor's Permit, DTI/SEC Registration (for partnerships/corporations, General Information Sheet & Articles of Incorporation shall also submit), PHILGEPS Registration Certificate, Omnibus Sworn Statement, Latest



BUREAU OF CUSTOMS

MAKABAGONG ADUANA, MATATAG NA EKONOMIYA



PROFESSIONALISM

INTEGRITY

ACCOUNTABILITY

Income/Business Tax Return, PCAB License and duly signed price quotation form (Annex "A"). All must be properly sealed.

Submission of quotation and eligibility documents in hard copy is on or before **April 29, 2022, 10:00 a.m., at General Services Division (GSD)**, Ground Floor, OCOM Building, Port Area, Manila.

Award of contract shall be made to the lowest quotation, which complies with the minimum description as stated above and other terms and conditions stated in the price quotation form.

Awarded Bidder must secure Performance Security/Performance Bond 30% of Contract Price upon receipt of Notice of Award.

Any interlineations, erasures or overwriting shall be valid only if they are signed or initialed by the bidder or his/her duly authorized representative/s.

The BOC reserves the right to accept or reject any or all quotations and to impose additional terms and conditions as it may deem proper.

For inquiry, you may contact us at Telefax no. 527-9757 or email us at bacsecretariat@customs.gov.ph.

Very truly yours,


ISAGANI D. GALSIM
Chief Administrative Officer
General Services Division

A Modernized and Credible Customs Administration That is Among the World's Best

South Harbor, Gate 3, Port Area, Manila 1099
8527-4537, 8527-1935 | www.customs.gov.ph | boc.cares@customs.gov.ph



Annex "A"

PRICE QUOTATION FORM

Date:

The Bids and Awards Committee
Bureau of Customs
Port Area, Manila

Project Name: **Repainting of BOC Entrance Gate and Perimeter Fence and Front Façade of OCOM Building**

Sir/Madam:

After having carefully read and accepted the terms and conditions in the Request for Quotation, hereunder is our quotation/s for the items as follows:

DESCRIPTION	QTY		MATERIAL COST		LABOR COST	TOTAL
	#Units	UM	P/Unit	Total		
A. Mobilization /Demobilization	1.00	lot				
B. Painting Works OCOM Building Repainting						
• Latex 701	110.00	gal				
• Semi Gloss Latex Paint	40.00	gal				
• Roller brush #7	15.00	pcs				
• Roller brush #4	10.00	pcs				
• Paint brush #4	15.00	pcs				
• Thinner	7.00	tin				
• Skim coat ABC 25kg	1.00	bags				
• Boral	5.00	bags				
• Palete	30.00	pcs				
• Sand paper#180	300.00	pcs				
• Sand paper#200	300.00	pcs				
• Consumables	1.00	lot				
• Labor	1.00	lot				
Interior Lobby Repainting (Wall and Ceiling)						

A Modernized and Credible Customs Administration That is Among the World's Best

South Harbor, Gate 3, Port Area, Manila 1099

8527-4537, 8527-1935 | www.customs.gov.ph | boc.cares@customs.gov.ph



BUREAU OF CUSTOMS

MAKABAGONG ADUANA, MATATAG NA EKONOMIYA



PROFESSIONALISM

INTEGRITY

ACCOUNTABILITY

<ul style="list-style-type: none"> • Latex 701 • Semi Gloss Latex Paint • Roller brush #7 • Roller brush #4 • Paint brush #4 • Thinner • Skim coat ABC 25kg • Boral • Palete • Sand paper#180 • Sand paper#200 • Consumables • Labor 	10.00 10.00 5.00 5.00 5.00 2.00 2.00 2.00 15.00 50.00 50.00 1.00 1.00	gal gal pcs pcs pcs tin bags bags pcs pcs pcs lot lot					
Scaffoldings, Platforms and Consumables <ul style="list-style-type: none"> • Scaffoldings and Platforms • Labor 			8.00 1.00	set lot			
Subtotal:							
C. Foyer Change Ceiling <ul style="list-style-type: none"> • Dismantling of existing ceiling • Hauling of construction debris Ceiling Works <ul style="list-style-type: none"> • 12mm Moisture Resistant Gypsum Board • Carrying Channel 0.65mm • Double Furring 0.6mm • 10mm Full Threaded Rod • Consumables • Labor Painting Works <ul style="list-style-type: none"> • Latex 701 • Roller brush #7 • Roller brush #4 • Paint brush #4 • Thinner • Skim coat ABC 25kg • Boral • Palete • Sand paper#180 • Sand paper#200 	55.03 3.00 42.00 30.00 90.00 15.00 1.00 1.00 4.00 3.00 2.00 2.00 1.00 2.00 2.00 2.00 5.00 10.00	sqm trips boards pcs pcs pcs lot lot gal pcs pcs pcs tin bags bags pcs pcs pcs					

A Modernized and Credible Customs Administration That is Among the World's Best

South Harbor, Gate 3, Port Area, Manila 1099

8527-4537, 8527-1935 | www.customs.gov.ph | boc.cares@customs.gov.ph



BUREAU OF CUSTOMS

MAKABAGONG ADUANA, MATATAG NA EKONOMIYA



PROFESSIONALISM

INTEGRITY

ACCOUNTABILITY

<ul style="list-style-type: none"> • Consumables • Labor 	1.00 1.00	lot lot				
Subtotal:						

C. Demolition of Walkway <ul style="list-style-type: none"> • Demolition of Walkway • Hauling of construction debris 	150.00 5.00	sqm trips				
---	----------------	--------------	--	--	--	--

Subtotal:						
------------------	--	--	--	--	--	--

E. Replacement of Tiles at Flag Pole <ul style="list-style-type: none"> • Dismantling of existing tiles • Hauling of construction debris Supply and Installation of Tiles (22.23 sqm) <ul style="list-style-type: none"> • 25kg ABC Tile Adhesive • Ceramic Tiles (60x60) • White Sand (Bistay) • Portland Cement • Consumables • Labor 	22.23 1.00 15.00 70.00 60.00 12.00 1.00 1.00	sqm trips bags pcs bags bags lot lot				
---	---	---	--	--	--	--

Subtotal:						
------------------	--	--	--	--	--	--

F. Removal of Window Grill <ul style="list-style-type: none"> • Dismantling of Window Grill • Masonry retouch • Hauling and set up of scaffolding 	1.00 1.00 1.00	lot lot set up				
---	----------------------	----------------------	--	--	--	--

Subtotal:						
------------------	--	--	--	--	--	--

Total:						
---------------	--	--	--	--	--	--

A Modernized and Credible Customs Administration That is Among the World's Best

South Harbor, Gate 3, Port Area, Manila 1099

8527-4537, 8527-1935 | www.customs.gov.ph | bcc.cares@customs.gov.ph



BUREAU OF CUSTOMS

MAKABAGONG ADUANA, MATATAG NA EKONOMIYA



PROFESSIONALISM

INTEGRITY

ACCOUNTABILITY

Work Duration: 90 Calendar Days

Total amount in words:

The above-quoted prices are inclusive of all costs and applicable taxes.

Very truly yours,

Name/ Signature of Representative

Name of Company

Mayor's Permit No. _____

PhilGEPS Registration No. _____

(Please submit the photocopies of the above documents upon submission of quotation)

Direct Cost	
Material Cost	
Labor Cost	
Mobilization	
Total Direct Cost	_____
Indirect Cost	
OCM (15% of DC)	
Contractors Profit (10% of DC)	
Total Indirect Cost	
Tax (5% of DC + IC)	_____
TOTAL PROJECT COST	



PROJECT : OCOM BUILDING PROPOSED COLOR

DESIGN BY : BUILDING AND MAINTENANCE DIVISION-GSD

LOCATION : BUREAU OF CUSTOMS, PORT OF MANILA



[Handwritten signature]