



Republic of the Philippines
Department of Finance
Bureau of Customs
1099 Manila

REQUEST FOR QUOTATION

The Bureau of Customs (BOC), through its Administration Office (AO), will undertake a Small Value Procurement for "**Repair and Reroofing of IAS Extension**" in accordance with the Revised Implementing Rules and Regulations of Republic Act No. 9184. The details of the project are as follows:

Name of Project : **Repair and Reroofing of IAS Extension**
Location : **Bureau of Customs**
Approved Budget for the Contract: **Eight Hundred Eighty Five Thousand and Eighty Five Pesos and Eighty Nine Centavos (885,085.89)**

Specifications

QTY.	DESCRIPTION
1 LOT	<ul style="list-style-type: none">1. Mobilization<ul style="list-style-type: none">a. Preparation of logistics of contractor's equipment.b. Setting up of Temporary Facilities within the site.c. Setting up of necessary water and power lines required for the Project's repair and renovation.2. Demolition Works<ul style="list-style-type: none">a. Dismantling and subsequent hauling of existing roof and roof framing.b. Dismantling and subsequent hauling of existing ceiling and framing.3. Roofing Works<ul style="list-style-type: none">a. Dismantling and subsequent replace of existing roofing and its accessories.4. Steel Works<ul style="list-style-type: none">a. Dismantling and subsequent replace of existing roof framing and its accessories.5. Carpentry Works<ul style="list-style-type: none">a. Supply and Installation of fiber cement board with complete standard metal furring support on all ceiling.6. Painting Works<ul style="list-style-type: none">a. Painting of all newly installed ceiling.b. Repainting of all interior and exterior walls.c. Painting of new roofing and subsequent the application of roof sealant.7. Electrical Works<ul style="list-style-type: none">a. Dismantling of existing lighting fixture, wiring devices, roughing-ins/raceways and accessories.b. Restoration of any unforeseen auxiliary and electrical wiring system of other circuit home run affected during demolition works.

	<ul style="list-style-type: none"> c. Supply and installation of complete electrical system as indicated on the plans d. Supply and installation of wiring devices, switches and outlets, wall receptacles, plates and accessories e. Restoration of other electrical system not shown on the drawings such as power outlets, switches, data and other control wirings. f. Complete testing and commissioning of all electrical lighting, power system <p>8. Demobilization</p> <ul style="list-style-type: none"> a. Site clean-up b. Hauling of debris materials from project site to appropriate disposal area. c. Removal and hauling of tools and equipment from project site.
--	---

Interested suppliers are required to submit their valid and current Mayor's Permit, DTI/SEC Registration (for partnerships/corporations, General Information Sheet & Articles of Incorporation shall also be submitted), PHILGEPS Registration Certificate, Omnibus Sworn Statement, Latest Income/Business Tax Return, and duly signed price quotation form (Annex "A").

Submission of quotation and eligibility documents is on or before July 29, 2019, 10:00 a.m., at General Services Division (GSD), Ground Floor, OCOM Building, Port Area, Manila.

Award of contract shall be made to the lowest quotation, which complies with the minimum description as stated above and other terms and conditions stated in the price quotation form.

Any interlineations, erasures or overwriting shall be valid only if they are signed or initialed by the bidder or his/her duly authorized representative/s.

The BOC reserves the right to accept or reject any or all quotations and to impose additional terms and conditions as it may deem proper.

For inquiry, you may contact us at Telefax no. 527-9757 or email us at bacsecretariat@customs.gov.ph.

Very truly yours,



RAQUEL G. DE JESUS

Acting Chief, General Services Division

Annex "A"

PRICE QUOTATION FORM

Date:

The Bids and Awards Committee
Bureau of Customs
Port Area, Manila

Sir/Madam:

After having carefully read and accepted the terms and conditions in the Request for Quotation, hereunder is our quotation/s for the items as follows:

DESCRIPTION	QTY		MATERIAL COST	
	#Units	UM	P/Unit	Total
A. Mobilization	1.00	lot		
B. Demolition Works <ul style="list-style-type: none">• Ceiling and Hauling• Roofing and Hauling	140.50 140.00	Sq.m. Sq.m.		
C. Painting Works Interior Walls <ul style="list-style-type: none">• Permacoat Latex Paint• Permacoat Latex• Gypsum Putty• Masonry Putty• Concrete Neutralizer• Patching Compound• Permacoat Latex topcoat• Black Latex Paint• White Semi Gloss Duco paint Finish• Beige Duco Paint Finish• Consumables (Roller with tray, Brush, Sand paper, rugs, tinting color etc	12.00 9.00 6.00 3.00 8.00 24.00 16.00 8.00 16.00 16.00 1.00	Gals Gals Gals Gals Kls Gals Gals Gals Gals lot		

<p>D. Steel Works</p> <ul style="list-style-type: none"> • C-channel 2x5x6m • C-purlins 2x4x6m • Zag rod 5/8 • Welding Rod • Flat bar • Deformed Bar 10mm x 6m • Steel Stiffeners • Miscellaneous 	<p>25.00 18.00 10.00 3.00 6.00 5.00 9.00 1.00</p>	<p>Pcs Pcs Pcs Box Pcs Set Length Lot</p>		
<p>E. Carpentry Works Cabinet and Shelves</p> <ul style="list-style-type: none"> • 1/2 thk Plywood • 3/4 thk Plywood • 1/2 thk Marine Plywood • Finishing nails • Concrete Nails • Rugby/Cement Adhesive • Ficem screw 7x25 • Stikwell wood glue • 1/2"x1"x10'4S4 KD • Soft closing concealed Hinges #2 • Dual lock • Consumables <p>Ceiling</p> <ul style="list-style-type: none"> • 1/4 thk Cement Fiber Board • Metal studs, u-track metal, etc • Consumables(Rivets, Fasteners, hinges etc.) <p>Accessories</p> <ul style="list-style-type: none"> • Wooden Baseboard • Wooden Cornices 	<p>7.00 14.00 11.00 4.00 3.00 3.00 780.00 3.00 12.00 16.00 8.00 1.00 51.00 16.00 1.00 36.00 14.00</p>	<p>Shts Shts Shts Kgs Kgs Gal Pcs Lits Pcs Pairs Pairs Lot Shts Length Length Lot Length Length</p>		

<p>F. Roofing Works</p> <ul style="list-style-type: none"> • Super V crimp (0.40mmx1.05mxLS) • Ridge roll (0.40mmx0.60mxLS) • End wall flashing (0.40mmx0.60mxLS) • Gutter (0.40mmx0.60mxLS) • Teks 12-24x55mm w/ neo washer • Blind revit 5/32x3/8 • Silicon rubber sealant • Touchup paint • Concrete nails 25mm 	<p>44.00</p> <p>70.40</p> <p>47.00</p> <p>35.00</p> <p>352.00</p> <p>1,584.00</p> <p>10.00</p> <p>4.00</p> <p>8.00</p>	<p>Lm</p> <p>Lm</p> <p>Lm</p> <p>Lm</p> <p>Pcs</p> <p>Pcs</p> <p>ctgs</p> <p>Lts</p> <p>kgs.</p>		
<p>G. Electrical</p> <p>Lighting Fixture and Accessories</p> <ul style="list-style-type: none"> • Panel Board • 100mmx100mm 6W recessed white LED Ceiling Downlight, Warm White w/ diffuser • T8 Fluorescent Lamp Flat Panel Cover daylight <p>Wiring devices and accessories</p> <ul style="list-style-type: none"> • One single pole switch in one plate cover • Two single pole switch in one plate cover • Duplex universal convenience outlet <p>Roughing-ins and accessories</p> <ul style="list-style-type: none"> • 15mm dia. PVC flexible conduit pipe • 15mm dia. PVC rigid conduit pipe • 15mm dia. PVC Elbow • 15mm dia. PVC adaptor • 15mm dia. PVC locknut • 15mm dia. PVC bushing • 1"uPVC plastic molding <p>Wires and cables</p> <ul style="list-style-type: none"> • 3.5 mm sq. THHN copper wire stranded <p>Boxes</p> <ul style="list-style-type: none"> • Junction box 	<p>1.00</p> <p>73.00</p> <p>4.00</p> <p>12.00</p> <p>12.00</p> <p>12.00</p> <p>4.00</p> <p>8.00</p> <p>22.00</p> <p>22.00</p> <p>22.00</p> <p>22.00</p> <p>18.00</p> <p>1.00</p> <p>13.00</p>	<p>Set</p> <p>Pcs.</p> <p>Pcs.</p> <p>Set</p> <p>Set</p> <p>Set</p> <p>Roll</p> <p>Length</p> <p>Pcs.</p> <p>Pcs.</p> <p>Pcs.</p> <p>Pcs.</p> <p>Length</p> <p>Box</p> <p>Pcs.</p>		

<ul style="list-style-type: none"> • Utility box • Square box 	<p style="text-align: center;">8.00 3.00</p>	<p style="text-align: center;">Pcs. Pcs.</p>		
---	--	--	--	--

Total amount in words:

The above-quoted prices are inclusive of all costs and applicable taxes.

Very truly yours,

Name/ Signature of Representative

Name of Company

Mayor's Permit No. _____

PhilGEPS Registration No. _____

(Please submit the photocopies of the above documents upon submission of quotation)

BUREAU OF CUSTOMS
GENERAL SERVICES DIVISION
BUILDING AND MAINTENANCE SECTION
 OCOM Bldg. Port Area, Manila

Project Title : Repair and Reroofing of IAS Extension
 Location : VCD Compound, Gate 3, Port Area, Manila

Sheet No.: 2 of 2
 Date: 6/10/2019

DESCRIPTION	QTY		MATERIAL COST		LABOR COST	TOTAL
	# Units	UM	P/Unit	Total		
A Mobilization	1.00	lot				
B Demolition Works						
Ceiling and Hauling	140.50	sq.m.				
Roofing and Hauling	140.00	sq.m.				
C Painting Works						
Interior Walls						
Permacoat Latex Paint	12.00	gals				
Permacoat Latex	9.00	gals				
Gypsum Putty	6.00	gals				
Masonry Putty	3.00	gals				
Concrete Neutralizer	8.00	gals				
Patching Compound	24.00	kls				
Permacoat Latex topcoat	16.00	gals				
Black Latex Paint	8.00	gals				
White Semi Gloss Duco paint Finish	16.00	gals				
Beige Duco Paint Finish	16.00	gals				
consumables (Roller with tray, Brush, Sand paper, rugs, tinting color etc)	1.00	lot				
D Steel Works						
C-Channel 2 x 5 x 6m	25.00	pcs				
C-Purlins 2 x 4 x 6m	18.00	pcs				
Zag Rod 5/8	10.00	pcs				
Welding rod	3.00	box				
Flat bar	6.00	pcs				
Deformed Bar 10mm x 6m	5.00	set				
Steel Stiffeners	9.00	length				
miscellaneous	1.00	lot				
E Carpentry Works						
Cabinet and Shelves						
1/2 thk Plywood	7.00	shts				
3/4 thk Plywood	14.00	shts				
1/2 thk Marine Plywood	11.00	shts				
finishing nails	4.00	kgs.				
Concrete Nails	3.00	kgs.				
Rugby/Cement Adhesive	3.00	gal				


DESCRIPTION	QTY		MATERIAL COST		LABOR COST	TOTAL
	# Units	UM	P/Unit	Total		
ficem screw 7x25	780.00	pcs				
stikwell wood glue	3.00	lits				
1/2" x1" x10' 4S4 KD	12.00	pcs				
soft closing concealed Hinges #2	16.00	pairs				
dual lock	8.00	pairs				
consumables	1.00	lot				
Ceiling						
1/4 thk Cement Fiber Board	51.00	shts				
metal studs, u-track metal, etc	16.00	length				
Consumables (Rivets, Fasteners, hinges etc.)	1.00	lot				
Accessories						
Wooden Baseboard	36.00	length				
Wooden Cornices	14.00	length				
F Roofing Works						
Super V crimp (0.40mmx1.05mxLS)	44.00	lm				
ridge roll (0.40mmx0.60mxLS)	70.40	lm				
End wall flashing (0.40mmx0.60mxLS)	47.00	lm				
Gutter (0.40mmx0.60mxLS)	35.00	lm				
teks 12-24x55mm w/ neo washer	352.00	pcs				
blind revit 5/32x3/8	1,584.00	pcs				
silicon rubber sealant	10.00	ctgs				
touchup paint	4.00	lts				
Concrete nails 25mm	8.00	kgs.				
G Electrical						
Lighting Fixture and Accessories						
Panel Board	1.00	set				
100mm x 100mm 6W recessed white LED Ceiling Downlight, Warm White w/ diffuser	73.00	pcs.				
t8 Flourescent Lamp Flat Panel Cover, daylight	4.00	pcs.				
Wiring devices and accessories						
One single pole switch in one plate cover	12.00	set				
two single pole switch in one plate cover	12.00	set				
dulplex universal convenience outlet	12.00	set				
Roughing-ins and accessories						
15mm dia. PVC flexible conduit pipe	4.00	roll				
15mm dia. PVC rigid conduit pipe	8.00	length				
15mm dia. PVC Elbow	22.00	pcs.				
15mm dia. PVC adaptor	22.00	pcs.				

DESCRIPTION	QTY		MATERIAL COST		LABOR COST	TOTAL
	# Units	UM	P/Unit	Total		
15mm dia. PVC locknut	22.00	pcs.				
15mm dia. PVC bushing	22.00	pcs.				
1" uPVC plastic molding	18.00	length				
Wires and cables						
3.5 mm sq. THHN copper wire stranded	1.00	box				
Boxes						
Junction box	13.00	pcs.				
Utility box	8.00	pcs.				
square box	3.00	pcs.				


Prepared by:


GARY E. AGUILAR
 Technical Staff
 General Services division


Noted by:


ATTY. FRANCIS T. TOLIBAS
 Acting Chief
 General Services division

Recommending approval:


DONATO B. SAN JUAN
 Deputy Commissioner
 Internal Administration Group

Approved by:


REY LEONARDO B. GUERRERO
 Commissioner
 Bureau of Customs