



Republic of the Philippines  
Department of Finance  
**Bureau of Customs**  
1099 Manila

## REQUEST FOR QUOTATION

The Bureau of Customs (BOC), through its Administration Office (AO), will undertake a Small Value Procurement for "**Rehabilitation of Electrical System of Export Division at Port of NAIA**" in accordance with the Revised Implementing Rules and Regulations of Republic Act No. 9184. The details of the project are as follows:

Name of Project: **Rehabilitation of Electrical System of Export Division at Port of NAIA**  
Location: **Bureau of Customs Port Area Manila**  
Approved Budget for the Contract: **Six Hundred Forty-Three Thousand Five Hundred Fifteen Pesos and 47/100 (Php643,515.47) inclusive of tax**

### Specifications

QTY.	DESCRIPTION
1 LOT	<p><b>1. Mobilization</b></p> <ul style="list-style-type: none"><li>a. Preparation of logistics of contractor's equipment.</li><li>b. Setting up of Temporary Facilities within the site.</li><li>c. Setting up of necessary water and power lines required for the Project.</li></ul> <p><b>2. Electrical Works</b></p> <ul style="list-style-type: none"><li>a. Supply and installation of complete electrical system as indicated on the plans such as lighting and power system.</li><li>b. Supply and installation of wiring devices, switches and outlets, wall receptacles, plates and accessories.</li><li>c. Restoration of other electrical system not shown on the drawings such as power outlets, switches, data and other control wirings.</li><li>d. Submit as-built plan with signed and sealed by the Professional Electrical Engineer.</li><li>e. Complete testing and commissioning of all electrical lighting, power systems.</li></ul> <p><b>3. Demobilization</b></p> <ul style="list-style-type: none"><li>a. Site clean-up</li><li>b. Hauling of debris materials from project site to appropriate disposal area.</li><li>c. Removal and hauling of tools and equipment from project site.</li></ul> <p><b>Work Duration: 45 Calendar Days</b></p>

Interested suppliers are required to submit their valid and current Mayor's Permit, DTI/SEC Registration (for partnerships/corporations, General Information Sheet & Articles of Incorporation shall also submitted), PHILGEPS Registration Certificate, Omnibus Sworn Statement, Latest Income/Business Tax Return, PCAB License and duly signed price quotation form (Annex "A").

Submission of quotation and eligibility documents is on or before December 16, 2019, 10:00 a.m., at General Services Division (GSD), Ground Floor, OCOM Building, Port Area, Manila.


Award of contract shall be made to the lowest quotation, which complies with the minimum description as stated above and other terms and conditions stated in the price quotation form.

Any interlineations, erasures or overwriting shall be valid only if they are signed or initialed by the bidder or his/her duly authorized representative/s.

The BOC reserves the right to accept or reject any or all quotations and to impose additional terms and conditions as it may deem proper.

For inquiry, you may contact us at Telefax no. 527-9757 or email us at [bacsecretariat@customs.gov.ph](mailto:bacsecretariat@customs.gov.ph).

Very truly yours,

  
**RAQUEL G. DE JESUS**  
Acting Chief, General Services Division

Annex "A"

### PRICE QUOTATION FORM

Date:

The Bids and Awards Committee  
Bureau of Customs  
Port Area, Manila

Sir/Madam:

After having carefully read and accepted the terms and conditions in the Request for Quotation, hereunder is our quotation/s for the items as follows:

DESCRIPTION	QTY		MATERIAL COST	
	#Units	UM	P/Unit	Total
<b>A. Mobilization/Demobilization</b>	1.00	lot		
<b>B. Dismantling Works</b>	1.00	lot		
<b>C. Electrical Works</b>				
<b>Pipes and Fittings</b>				
• EMT Pipe 1/2"	180.00	length		
• EMT Pipe 3/4"	40.00	length		
• EMT Pipe 1"	20.00	length		
• EMT Adapter 1/2"	160.00	pcs		
• EMT Adapter 3/4"	80.00	pcs		
• EMT Adapter 1"	40.00	pcs		
• EMT Coupling 1/2"	180.00	pcs		
• EMT Coupling 3/4"	80.00	pcs		
• EMT Coupling 1"	40.00	pcs		
• RSC Clamp 1/2"	120.00	pcs		
• RSC Clamp 3/4"	80.00	pcs		
• RSC Clamp 1"	4.00	pcs		
• EMT Elbow 1/2"	26.00	pcs		
• EMT Elbow 3/4"	10.00	pcs		
• EMT Elbow 1"	10.00	pcs		
• Octagonal Box 4x4	26.00	pcs		
• Utility Box 2x4	15.00	pcs		
• Square Box witch cover 4x4	10.00	pcs		
• PVC Pipe 1/2"	40.00	pcs		
• PVC Pipe 3/4"	20.00	pcs		

<ul style="list-style-type: none"> <li>• 1" uPVC Moldings</li> <li>• Miscelenoues</li> </ul>	95.00 1.00	pcs lot		
<b>D. Wires and Cables</b> <ul style="list-style-type: none"> <li>• 3.5mm2 THHN CU wire stranded</li> <li>• 5.5mm2 THHN CU wire stranded</li> <li>• 14mm2 THHN CU wire stranded</li> <li>• 60mm2 THHN CU wire stranded</li> <li>• Plastic Tape (Big)</li> </ul>	14.00 4.00 30.00 60.00 50.00	box box mtrs mtrs roll		
<b>E. Lighting Fixture and Lamps</b> <ul style="list-style-type: none"> <li>• 2x40 W. Fluorescent Fixture (LED)</li> <li>• Porcelain Receptacle</li> <li>• Male and Female Plug</li> <li>• Pinlight</li> <li>• Emergency Light</li> </ul>	33.00 33.00 33.00 5.00 8.00	sets sets sets sets sets		
<b>F. Panelboard and Circuit Breaker</b> <ul style="list-style-type: none"> <li>• Main: 150 Amps, 2P, 240V MCCB</li> <li>• Branches: 6-40 Amps, 2P, 240V MCB 6-20 Amps, 2P, 240V MCB</li> </ul>	1.00	set		
<b>G. Wiring Device and Accessories</b> <ul style="list-style-type: none"> <li>• A/C Outlet</li> <li>• Universal Convenience Outlet</li> <li>• Three Gang Switch</li> <li>• Two Gang Switch</li> <li>• Single Gang Switch</li> </ul>	6.00 14.00 3.00 4.00 4.00	sets sets sets sets sets		

**Work Duration: 45 Calendar Days**

Total amount in words:

The above-quoted prices are inclusive of all costs and applicable taxes.

Very truly yours,

\_\_\_\_\_  
Name/ Signature of Representative

\_\_\_\_\_  
Name of Company

Mayor's Permit No. \_\_\_\_\_

PhilGEPS Registration No. \_\_\_\_\_

(Please submit the photocopies of the above documents upon submission of quotation)

<b>Direct Cost</b>	
Material Cost	
Labor Cost	
Mobilization	
<b>Total Direct Cost</b>	_____
<b>Indirect Cost</b>	
OCM (15% of DC)	
Contractors Profit (10% of DC)	
Total Indirect Cost	
<b>Tax (5% of DC + IC)</b>	_____
<b>TOTAL PROJECT COST</b>	

**BUREAU OF CUSTOMS**  
**GENERAL SERVICES DIVISION**  
BUILDING AND MAINTENANCE SECTION  
OCOM Bldg. Port Area, Manila

**BILL OF QUANTITIES**

Project Title : Rehabilitation of Electrical System of Export Division at Port of NAIA

Sheet No.: 2 of 2

Location : Port of NAIA

Date: 11/6/2019


DESCRIPTION	QTY		MATERIAL COST		LABOR COST	TOTAL
	# Units	UM	P/Unit	Total		
<b>A. Mobilization</b>						
	1.00	lot				
<b>B. Dismantling Works</b>						
	1.00	lot				
<b>C. Electrical Works</b>						
<b>Pipes and Fittings</b>						
EMT Pipe 1/2"	180.00	length				
EMT Pipe 3/4"	40.00	length				
EMT Pipe 1"	20.00	length				
EMT Adapter 1/2"	160.00	pcs				
EMT Adapter 3/4"	80.00	pcs				
EMT Adapter 1"	40.00	pcs				
EMT Coupling 1/2"	180.00	pcs				
EMT Coupling 3/4"	80.00	pcs				
EMT Coupling 1"	40.00	pcs				
RSC Clamp 1/2"	120.00	pcs				
RSC Clamp 3/4"	80.00	pcs				
RSC Clamp 1"	4.00	pcs				
EMT Elbow 1/2"	26.00	pcs				
EMT Elbow 3/4"	10.00	pcs				
EMT Elbow 1"	10.00	pcs				
Octagonal Box 4x4	26.00	pcs				
Utility Box 2x4	15.00	pcs				
Square Box witch cover 4x4	10.00	pcs				
PVC Pipe 1/2"	40.00	pcs				
PVC Pipe 3/4"	20.00	pcs				
1" uPVC Moldings	95.00	pcs				
Miscelenoues	1.00	lot				
<b>Wires and Cables</b>						
3.5mm2 THHN CU wire stranded	14.00	box				
5.5mm2 THHN CU wire stranded	4.00	box				
14mm2 THHN CU wire stranded	30.00	mtrs				
60mm2 THHN CU wire stranded	60.00	mtrs				
Plastic Tape (Big)	50.00	roll				
<b>Lighting Fixture and Lamps</b>						
2x40 W. Fluorescent Fixture (LED)	33.00	sets				
Porcelain Receptacle	33.00	sets				
Male and Female Plug	33.00	sets				
Pinlight	5.00	sets				
Emergency Light	8.00	sets				
<b>Panelboard and Circuit Breaker</b>						
Main: 150 Amps, 2P, 240V MCCB	1.00	set				
Branches: 6-40 Amps, 2P, 240V MCB						
6-20 Amps, 2P, 240V MCB						
<b>Wiring Device and Accessories</b>						

DESCRIPTION	QTY		MATERIAL COST		LABOR COST	TOTAL
	# Units	UM	P/Unit	Total		
A/C Outlet	6.00	sets				
Universal Convenience Outlet	14.00	sets				
Three Gang Switch	3.00	sets				
Two Gang Switch	4.00	sets				
Single Gang Switch	4.00	sets				

Prepared by:



**ENGR. GARY E. AGUILAR**  
 Technical Staff  
 General Services Division



**GENBERT S. GUSAGO**  
 Technical Assistant  
 General Services Division

**Direct Cost**

Material Cost  
 Labor Cost  
 Mobilization

**Total Direct Cost**

**Indirect Cost**


OCM (15% of DC)  
 Contractors Profit (10% of DC)

**Total Indirect Cost**

**Tax (5% of DC + IC)**

**TOTAL PROJECT COST**

Reviewed by:



**ENGR. CECILIA G. FABIAN**  
 Administrative Officer IV  
 General Services Division

Noted by:




**RACQUEL G. DE JESUS**  
 Acting Chief  
 General Services Division

Recommending approval:



**DONATO B. SAN JUAN**  
 Deputy Commissioner  
 Internal Administration Group

Approved by:



**REY LEONARDO B. GUERRERO**  
 Commissioner  
 Bureau of Customs