



Republic of the Philippines
Department of Finance
Bureau of Customs
1099 Manila

REQUEST FOR QUOTATION

The Bureau of Customs (BOC), through its Administration Office (AO), will undertake a Small Value Procurement for "**Repair and Rehabilitation of JICA Comport Room**" in accordance with the Revised Implementing Rules and Regulations of Republic Act No. 9184. The details of the project are as follows:

Name of Project : **Repair and Rehabilitation of JICA Comport Room**
Location : **Bureau of Customs**
Approved Budget for the Contract: **One Hundred Twenty Seven Thousand Five Hundred Thirty Five Pesos and 96/100 (Php127,535.96)– inclusive of tax**

Specifications

QTY.	DESCRIPTION
1 LOT	<ul style="list-style-type: none">1. Mobilization2. Carpentry Works<ul style="list-style-type: none">a. Dismantling of ceiling boards and frame.b. Installation of fiber cement board with complete standard metal furring support on ceilingc. Dismantling and subsequent replace of existing PVC flush door3. Painting Works<ul style="list-style-type: none">a. Painting of newly installed ceiling.b. Waterproof comfort room flooring.4. Tiling Works<ul style="list-style-type: none">a. Chipping off of existing floor and wall tiles located at comfort room.b. Installation of floor and wall tiles at comport room.5. Plumbing Works<ul style="list-style-type: none">a. Dismantling and subsequent replace of existing plumbing fixtures, fittings and accessoriesb. Dismantling and subsequent replace of existing water distribution and sanitary piping system<ul style="list-style-type: none">i. Supply and installation of new PPR pipes with complete standard fittings and accessoriesii. Supply and installation of PVC sanitary pipes fittings and accessories.c. Supply and installation of PVC sanitary pipes fittings and accessories.6. Electrical Works<ul style="list-style-type: none">a. Dismantling of existing lighting fixture, wiring devices, roughing-ins/raceways and accessoriesb. Supply and installation of complete electrical system as indicated on the plans.

	<ul style="list-style-type: none"> c. Supply and installation of wiring devices, switches and outlets, wall receptacles, plates and accessories d. Restoration of other electrical system not shown on the drawings such as power outlets, switches, data and other control wirings e. Complete testing and commissioning of all electrical lighting power systems <p>7. Demobilization</p> <ul style="list-style-type: none"> a. Site clean-up b. Hauling of debris materials from projects site to appropriate disposal area. c. Removal and hauling of tools and equipment from project site. <p>8. Canopy Works</p> <ul style="list-style-type: none"> a. Supply and installation of 3m x 5.2 Steel Canopy on the transaction area including of its roofing system with downspout and electrical system. <p>9. Demobilization</p> <ul style="list-style-type: none"> a. Site clean-up b. Hauling debris materials from project site to appropriate disposal area. c. Removal and hauling of tools and equipment from project site.
--	-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------

Work duration: 25 Calendar Days

Interested suppliers are required to submit their valid and current Mayor's Permit, DTI/SEC Registration (for partnerships/corporations, General Information Sheet & Articles of Incorporation shall also submitted), PHILGEPS Registration Certificate, Omnibus Sworn Statement, Latest Income/Business Tax Return, PCAB License, and duly signed price quotation form (Annex "A").

Submission of quotation and eligibility documents is on or before November 8, 2019, 10:00 a.m., at General Services Division (GSD), Ground Floor, OCOM Building, Port Area, Manila.

Award of contract shall be made to the lowest quotation, which complies with the minimum description as stated above and other terms and conditions stated in the price quotation form.

Any interlineations, erasures or overwriting shall be valid only if they are signed or initialed by the bidder or his/her duly authorized representative/s.

The BOC reserves the right to accept or reject any or all quotations and to impose additional terms and conditions as it may deem proper.

For inquiry, you may contact us at Telefax no. 527-9757 or email us at bacsecretariat@customs.gov.ph.

Very truly yours,



RAQUEL G. DE JESUS

Acting Chief, General Services Division

Annex "A"

PRICE QUOTATION FORM

Date:

The Bids and Awards Committee
 Bureau of Customs
 Port Area, Manila

Sir/Madam:

After having carefully read and accepted the terms and conditions in the Request for Quotation, hereunder is our quotation/s for the items as follows:

DESCRIPTION	QTY		MATERIAL COST	
	#Units	UM	P/Unit	Total
A. Mobilization/Demobilization	1.00	lot		
B. Demolition / Chipping Works	1.00	lot		
C. Carpentry Works				
Ceiling				
• 4.5mm thk x 4' x 8' flexboard	2.00	Lot		
• 0.40 mm thk x 19 mm x 25 mm x 5 m furring channel	4.00	Lot		
• 1.00 mm thk x 12 mm x 38 mm x 5 m carrying channel	4.00	shts		
• Wall ange (12' G.I.)	2.00	pcs		
• Steel angle	2.00	pcs		
• W-clips	45.00	pcs		
• Suspension clip & rod joiner	4.00	set		
• Concrete nails	1.00	kgs		
• Blind rivets 1/8" x 1/2"	120.00	pcs		
• Ficem screw 7x25	50.00	pcs		
• Pvc flush door with jam	1.00	set		
• consumables	1.00	lot		

<p>D. Tiling Works</p> <ul style="list-style-type: none"> • 300mm x 300mm ceramic floor tiles • 300mm x 200mm ceramic wall tiles • Tile adhesive, 25kgs • Tile grout, 5kgs • Tile trim consumables 	<p>45.00 125.00 4.00 3.00 20.00 1.00</p>	<p>Pcs Pcs Bags Bags Pcs lot</p>		
<p>E. Plumbing Works</p> <ul style="list-style-type: none"> • Water closet, 2 button type w/ complete accessories • Lavatory, counter top mounted • Lavatory faucet, cold water • Face Mirror • Gate valve 1/2 " • Gate valve 3/4 " • PPR Pipe 1/2 " • PPR Pipe 3/4 " • Union Patente 1/2 " • Union Patente 3/4 " • PPR Adaptor 1/2 " • PPR Adaptor 3/4 " • PPR Coupling 1/2 " • PPR Coupling 3/4 " • 75mm PVC Sanitary pipes • 75mm PVC Elbow 90deg • 75mm PVC Elbow 45deg • 75mm x 75mm PVC Wye • PVC Solvent Cement • Floor Drain • consumables <p>F. Painting Works</p> <ul style="list-style-type: none"> • Flat Latex • Semi-gloss latex • Rugs • Paint and roller brush • Sand paper • Paint thinner • Lacquer thinner • Mesh tape • Polituff • Lacquer putty • consumables 	<p>1.00 1.00 1.00 1.00 1.00 2.00 2.00 2.00 2.00 2.00 5.00 5.00 6.00 6.00 1.00 2.00 2.00 2.00 2.00 2.00 1.00 1.00 1.00 3 1 1 1 1 5 1 1 1</p>	<p>Set Set Set Pcs Pcs Pcs Length Length Pcs Pcs Pcs Pcs Pcs Pcs Length Pcs Pcs Pcs Pcs Pcs Pcs lot gals gals kls lot lot gals gals gals gals gals gals lot</p>		

G. Electrical Works			
• Plastic Flexible 1/2 "	1	rolls	
• PVC Pipe 1/2 "	1	pcs	
• THHN Wire #12	1	rolls	
• Utility Box	2	pcs	
• Octagonal box	2	pcs	
• Lighting Fixture	1	pcs	
• Electrical tape	2	rolls	
• Wiring devices	1	lot	
• consumables	1	lot	

Total amount in words:

The above-quoted prices are inclusive of all costs and applicable taxes.

Very truly yours,

Name/ Signature of Representative

Name of Company

Mayor's Permit No. _____

PhilGEPS Registration No. _____

(Please submit the photocopies of the above documents upon submission of quotation)

BUREAU OF CUSTOMS
GENERAL SERVICES DIVISION
 BUILDING AND MAINTENANCE SECTION
 OCOM Bldg. Port Area, Manila

BILL OF QUANTITIES

Project Title : Repair and Rehabilitation of Comfort Room and Plumbing System of JICA Customs Expert Office

Location : 2nd Floor CRIC Building


Sheet No.: 2 of 2

Date: 9/25/2019

DESCRIPTION	QTY		MATERIAL COST		LABOR COST	TOTAL
	# Units	UM	P/Unit	Total		
A Mobilization						
B Demolition/Chipping Works	1.00	lot				
C Carpentry Works	1.00	lot				
Ceiling						
4.5mm thk x 4' x 8' flexboard	2.00	shts				
0.40 mm thk x 19 mm x 25 mm x 5 m furring channel	4.00	pcs				
1.00 mm thk x 12 mm x 38 mm x 5 m carrying channel	4.00	pcs				
wall angle (12' G.I.)	2.00	pcs				
steel angle	2.00	pcs				
w-clips	45.00	pcs				
suspension clip & rod joiner	4.00	set				
concrete nails	1.00	kgs.				
blind rivets 1/8" x 1/2"	120.00	pcs				
ficem screw 7x25	50.00	pcs				
PVC flush door with jam	1.00	set				
consumables	1.00	lot				
D Tiling Works						
300mm x 300mm ceramic floor tiles	45.00	pcs.				
300mm x 200mm ceramic wall tiles	125.00	pcs.				
Tile adhesive, 25kgs.	4.00	bags				
Tile grout, 5kgs.	3.00	bags				
Tile trim	20.00	pcs				
consumables	1.00	lot				
E Plumbing Works						
Water closet, 2 button type w/ complete accessories	1.00	set				
Lavatory, counter top mounted	1.00	set				
Lavatory faucet, cold water	1.00	set				
Face Mirror	1.00	pcs.				
Gate valve 1/2"	1.00	pcs.				
Gate Valve 3/4"	1.00	pcs.				
PPR Pipe 1/2"	2.00	length				
PPR Pipe 3/4"	2.00	length				
Union Patente 1/2"	2.00	pcs				
Union Patente 3/4"	2.00	pcs				
PPR Adaptor 1/2"	5.00	pcs				
PPR Adaptor 3/4"	5.00	pcs.				

DESCRIPTION	QTY		MATERIAL COST		LABOR COST	TOTAL
	# Units	UM	P/Unit	Total		
PPR Coupling 1/2"	6.00	pcs.				
PPR Coupling 3/4"	6.00	pcs.				
75mm PVC Sanitary pipes	1.00	length				
75mm PVC Elbow 90deg	2.00	pcs				
75mm PVC Elbow 45deg	2.00	pcs				
75mm x 75mm PVC Wye	2.00	pcs				
PVC Solvent Cement	2.00	pcs.				
Floor Drain	1.00	pcs.				
consumables	1.00	lot				
F Painting Works						
Flat Latex	1	gals				
Semi-Gloss Latex	1	gals				
Rugs	3	kls				
Paint and Roller Brush	1	lot				
Sand Paper	1	lot				
Paint Thinner	1	gals				
Lacquer Thinner	1	gals				
Mesh Tape	5	rolls				
Polituff	1	gals				
Lacquer Putty	1	gals				
consumables	1	lot				
G Electrical Works						
Plastic Flexible 1/2"	1	rolls				
PVC Pipe 1/2"	1	pcs				
THHN Wire #12	1	rolls				
Utility Box	2	pcs				
Octagonal Box	2	pcs				
Lighting Fixture	1	pcs				
Electrical Tape	2	rolls				
Wiring Devices	1	lot				
consumables	1	lot				


Prepared by:


GARY E. AGUILAR
 Technical Staff
 General Services Division

Noted by:


RAQUEL G. DE JESUS
 Acting Chief
 General Services Division

Recommending approval:


DONATO B. SAN JUAN
 Deputy Commissioner
 Internal Administration Group

Approval by:


REY LEONARDO B. GUERRERO
 Commissioner
 Bureau of Customs

Direct Cost

Material Cost

Labor Cost

Mobilization

Total Direct Cost

Indirect Cost

OCM (15% of DC)

Contractors Profit (10% of DC)

Total Indirect Cost

Tax (5% of DC + IC)

TOTAL PROJECT COST