



Republic of the Philippines  
Department of Finance  
**Bureau of Customs**  
1099 Manila

## REQUEST FOR QUOTATION

The Bureau of Customs (BOC), through its Administration Office (AO), will undertake Third Small Value Procurement for **Repainting of IAS Building, Re-piping of Water Source Distribution System, and Repair and Renovation of Comfort Rooms and Directors Office**, in accordance with the Revised Implementing Rules and Regulations of Republic Act No. 9184. The details of the project are as follows:

Name of Project : **Repainting of IAS Building, Re-piping of Water Source Distribution System, and Repair and Renovation of Comfort Rooms and Directors Office**

Location : **IAS Building, Gate 3, South Harbor, Port Area, Manila**

Approved Budget for the Contract: **Nine Hundred Eighty Thousand Three Hundred Forty Nine Pesos & 61/100 (Php980,349.61), inclusive of tax**

Specifications:

QTY.	UNIT	DESCRIPTION
1	LOT	<b>1. MOBILIZATION</b>
1	LOT	<b>2. CONCRETE WORKS</b>
		c) Provision of concrete water pump enclosure (as per plan)
1	LOT	<b>3. Plumbing Works</b>
		<b>a) C.R. NEAR THE MAIN ENTRANCE</b>
		<b>I.</b> Dismantling of all fixtures
		<b>II.</b> Re-piping of water lines and sanitary lines
		<b>III.</b> Supply and installation of toilet fixtures
		1. Water closets with bidets
		2. Lavatories with faucets
		3. Urinals
		4. Soap dispensers and holders
		5. Tissue paper holders
		<b>b) C.R. AT SECOND FLOOR</b>
		<b>I.</b> Dismantling of all fixtures
		<b>II.</b> Re-piping of water lines and sanitary lines
		<b>III.</b> Supply and installation of toilet fixtures
		1. Water closets with bidets
		2. Lavatories with faucets
		3. Urinals
		4. Soap dispensers and holders
		5. Tissue paper holders
		<b>c) WATER SOURCE DISTRIBUTION SYSTEM</b>
		<b>I.</b> Supply and Installation of two(2) sets 5hp Centrifugal pump located at near cistern tank of OCOM Building
		<b>II.</b> Supply and installation of new PPR pipes with complete standard fittings and accessories(as per plan)

12-20-17-10093

		<ol style="list-style-type: none"> <li>1. Use standard size of PPR pipe for up-feed pipe connecting from 5hp centrifugal pump through gravity tank</li> </ol>
		<ol style="list-style-type: none"> <li>2. Provide foot valve at the suction pipe</li> </ol>
		<ol style="list-style-type: none"> <li>3. Provide gate valve on each side of the pump</li> </ol>
		<ol style="list-style-type: none"> <li>4. Two(2) pumps must be equipped with a by-pass, by inserting Tees of the same diameter at the suction and feed side</li> </ol>
		<ol style="list-style-type: none"> <li>5. In case of pump trouble, the control valve on either side of the pump must be closed and the by-pass control valve on the alternate pump must be open</li> </ol>
1	LOT	<b>4. PAINTING WORKS</b>
		<b>a) PAINTING OF BUILDING (EXTERIOR)</b>
		<b>I.</b> Latex paint on concrete surfaces
		<b>II.</b> Enamel paint on wood surfaces
		<b>III.</b> Elastomeric paint on roof
		<b>IV.</b> Spot putty whenever required
		<b>V.</b> Preparation and application must be according to the brand's instructions
		<b>b)</b> Painting of new ceiling board and walls at Ground floor and Second floor common comfort rooms and for the Director's office at ground floor
1	LOT	<b>5. CARPENTRY WORKS</b>
		<b>a) C.R. NEAR THE MAIN ENTRANCE</b>
		<b>I.</b> Dismantling of dilapidated ceiling boards and frames
		<b>II.</b> Water proofing of ceiling slab
		<b>III.</b> Supply and Installation of new ceiling frames and boards
		<b>IV.</b> Fiber board cement on metal furring spaced at 0.60 m. o.c. and carrying channel spaced at 1.20 m. o.c.
		<b>b) DIRECTOR'S OFFICE AT GROUND FLOOR (AS PER PLAN/DESIGN)</b>
		<b>II.</b> Repair of one way mirror
1	LOT	<b>6. ELECTRICAL WORKS</b>
		<b>a) C.R. NEAR THE MAIN ENTRANCE</b>
		<b>I.</b> Dismantling of existing lighting fixture, wiring devices and roughing-ins
		<b>II.</b> Supply and Installation of standard lighting fixture as specified by engineer and /or owner's representative.
		<b>III.</b> Supply and installation of wiring devices, roughing-ins, switches and outlets.
		<b>IV.</b> Supply and installation of new 2sets 8inch exhaust fan
		<b>b) ELECTRICAL WIRING SYSTEM FOR WATER PUMP</b>
		<b>I.</b> Supply and Installation of motor controller with nema enclosure and complete required circuit breakers, contactors and overload relays

		<b>II.</b> Supply and Installation of automatic floater switch which control automatically on and off the pump depending upon the volume demand of gravity tank
		<b>III.</b> Supply and Installation of THHN/THWN copper wire stranded of complete electrical system and control wiring of centrifugal pump,
		<b>IV.</b> Termination of Electrical System from the main source power or panelboard
		<b>V.</b> Complete testing and commissioning of electrical system
		<b>c)</b> All exposed existing electrical wirings, data cable and telephone line inside the building shall be covered using uPVC moldings, use appropriate size to accommodate the wires and cables with proper insulation, do not combine the electrical wire, data cable and telephone line on the same raceways
1	LOT	<b>7. DEMOBILIZATION</b>

Delivery Term: Fifty Five (55) calendar days from signing of PO

Interested suppliers are required to submit their valid and current Mayor's Permit, DTI/SEC Registration, PHILGEPS Registration Certificate, Omnibus Sworn Statement, Income/ Business Tax Return, NFCC,PCAB License and duly signed price quotation form (Annex "A").

Submission of quotation and eligibility documents is on or before December 27, 2017, 10:00 a.m., at General Services Division (GSD), Ground Floor, OCOM Building, Port Area, Manila.



Award of contract shall be made to the lowest quotation, which complies with the minimum description as stated above and other terms and conditions stated in the price quotation form.

Any interlineations, erasures or overwriting shall be valid only if they are signed or initialed by the bidder or his/her duly authorized representative/s.

The BOC reserves the right to accept or reject any or all quotations and to impose additional terms and conditions as it may deem proper.

For inquiry, you may contact us at Telefax no. 527-9757 or email us at [bacsecretariat@customs.gov.ph](mailto:bacsecretariat@customs.gov.ph).

Very truly yours,

  
**GLADYS F. ROSALES, MPA, CESE**  
 OIC, Deputy Commissioner  
 Internal Administration Group 

Annex "A"

### PRICE QUOTATION FORM

Date \_\_\_\_\_

The Bids and Awards Committee  
Bureau of Customs  
Port Area, Manila

Sir/Madam:

After having carefully read and accepted the terms and conditions in the Request for Quotation, hereunder is our quotation/s for the items as follows:

QTY.	UNIT	DESCRIPTION	UNIT PRICE	TOTAL PRICE
1	LOT	<b>1. MOBILIZATION</b>		
1	LOT	<b>2. CONCRETE WORKS</b>		
		a) Provision of concrete water pump enclosure (as per plan)		
1	LOT	<b>3. Plumbing Works</b>		
		<b>a) C.R. NEAR THE MAIN ENTRANCE</b>		
		I. Dismantling of all fixtures		
		II. Re-piping of water lines and sanitary lines		
		III. Supply and installation of toilet fixtures		
		1. Water closets with bidets		
		2. Lavatories with faucets		
		3. Urinals		
		4. Soap dispensers and holders		
		5. Tissue paper holders		
		<b>b) C.R. AT SECOND FLOOR</b>		
		I. Dismantling of all fixtures		
		II. Re-piping of water lines and sanitary lines		
		III. Supply and installation of toilet fixtures		
		1. Water closets with bidets		
		2. Lavatories with faucets		
		3. Urinals		
		4. Soap dispensers and holders		
		5. Tissue paper holders		
		<b>c) WATER SOURCE DISTRIBUTION SYSTEM</b>		
		I. Supply and Installation of two(2) sets 5hp Centrifugal pump located		

		at near cistern tank of OCOM Building		
		<b>II.</b> Supply and installation of new PPR pipes with complete standard fittings and accessories(as per plan)		
		1. Use standard size of PPR pipe for up-feed pipe connecting from 5hp centrifugal pump through gravity tank		
		2. Provide foot valve at the suction pipe		
		3. Provide gate valve on each side of the pump		
		4. Two(2) pumps must be equipped with a by-pass, by inserting Tees of the same diameter at the suction and feed side		
		5. In case of pump trouble, the control valve on either side of the pump must be closed and the by-pass control valve on the alternate pump must be open		
1	LOT	<b>4. PAINTING WORKS</b>		
		<b>a) PAINTING OF BUILDING (EXTERIOR)</b>		
		<b>I.</b> Latex paint on concrete surfaces		
		<b>II.</b> Enamel paint on wood surfaces		
		<b>III.</b> Elastomeric paint on roof		
		<b>IV.</b> Spot putty whenever required		
		<b>V.</b> Preparation and application must be according to the brand's instructions		
		<b>b.</b> Painting of new ceiling board and walls at Ground floor and Second floor common comfort rooms and for the Director's office at ground floor		
1	LOT	<b>5. CARPENTRY WORKS</b>		
		<b>a) C.R. NEAR THE MAIN ENTRANCE</b>		
		<b>I.</b> Dismantling of dilapidated ceiling boards and frames		
		<b>II.</b> Water proofing of ceiling slab		
		<b>III.</b> Supply and Installation of new ceiling frames and boards		
		<b>1.</b> Fiber board cement on metal furring spaced at 0.60 m. o.c.		

		and carrying channel spaced at 1.20 m. o.c.		
		<b>b) DIRECTOR'S OFFICE AT GROUND FLOOR (AS PER PLAN/DESIGN)</b>		
		<b>II.</b> Repair of one way mirror		
1	LOT	<b>6. ELECTRICAL WORKS</b>		
		<b>a) C.R. NEAR THE MAIN ENTRANCE</b>		
		<b>I.</b> Dismantling of existing lighting fixture, wiring devices and roughing-ins		
		<b>II.</b> Supply and Installation of standard lighting fixture as specified by engineer and /or owner's representative.		
		<b>III.</b> Supply and installation of wiring devices, roughing-ins, switches and outlets.		
		<b>IV.</b> Supply and installation of new 2sets 8inch exhaust fan		
		<b>b) ELECTRICAL WIRING SYSTEM FOR WATER PUMP</b>		
		<b>I.</b> Supply and Installation of motor controller with nema enclosure and complete required circuit breakers, contactors and overload relays		
		<b>II.</b> Supply and Installation of automatic floater switch which control automatically on and off the pump depending upon the volume demand of gravity tank		
		<b>III.</b> Supply and Installation of THHN/THWN copper wire stranded of complete electrical system and control wiring of centrifugal pump,		
		<b>IV.</b> Termination of Electrical System from the main source power or panelboard		
		<b>V.</b> Complete testing and commissioning of electrical system		
		<b>c)</b> All exposed existing electrical wirings, data cable and telephone line inside the building shall be covered using uPVC moldings, use appropriate size to accommodate the wires and cables with proper insulation, do not combine the electrical wire, data cable and telephone line on the same raceways		

1	LOT	<b>7. DEMOBILIZATION</b>		
---	-----	--------------------------	--	--

Warranty: \_\_\_\_ months from the date of delivery

Total amount in words:

The above-quoted prices are inclusive of all costs and applicable taxes.  
Very truly yours,

\_\_\_\_\_  
Name/ Signature of Representative

\_\_\_\_\_  
Name of Company

Mayor's Permit No. \_\_\_\_\_

PhilGEPS Registration No. \_\_\_\_\_

(Please submit the photocopies of the above documents upon submission of quotation)