



REQUEST FOR QUOTATION

The Bureau of Customs (BOC), through its Administration Office (AO), will undertake Small Value Procurement for "**Repair/Rehabilitation of X-Ray Inspection Project, Field Office**", in accordance with the Revised Implementing Rules and Regulations of Republic Act No. 9184. The details of the project are as follows:

Name of Project : Repair/Rehabilitation of X-Ray Inspection Project, Field Office
Location : Ground Floor POM Extension Building, Port of Manila
Approved Budget for the Contract: Four Hundred Ninety Five Thousand Four Hundred Fifty Three & 75/100 Pesos (Php 495,453.75)
-inclusive of tax

Specifications:

Qty.	Unit	DESCRIPTION
Dismantling/Restoration and Hauling-Out Works		
1	lot	• Dismantling of floor and wall tiles at comfort room
1	lot	• Provision of door opening at Comfort room
1	lot	• Dismantling of corrugated roofing at CR and Mezzanine including framing
1	lot	• Dismantling of dilapidated ceiling at mezzanine
1	lot	• Dismantling of wood cladding at Mezzanine
1	lot	• Demolition of existing CHB enclosure at CR
1	lot	• Dismantling of electrical rough-ins
1	lot	• Restoration of all affected areas
1	lot	• Cleaning of site and hauling-out of debris/wastes
MASONRY WORKS		
10.02	sq.m	• 4" CHB wall with rebars
20.04	sq.m	• Plain cement plastering
CARPENTRY WORKS		
1	lot	• Dry wall cladding
CEILING WORKS		
42.81	sq.m	• 4.50 mm thk cement fiberboard ceiling on 0.40mm thk x 19mm x 25mm furring channel @ 0.40mm o.c. and 1.00mm thk x 12mm x 38mm carrying channel with 1.20m O.C B.W. with adjustable rod hanger at Pantry, CR's and Mezzanine
63.08	meter	• Wooden cornice
TILE WORKS		
7.30	sq.m	• 300mm x 300mm CERAMIC FLOOR TILES MATTED FINISHED (COLOR:CHANDON SABBIA)
30.72	sq.m	• 300mm x 300mm CERAMIC WALL TILES (MATTED WITH LUSTER), (COLOR: ANAHAW BEIGE) WITH ANAHAW LISTEL TILE OR APPROVED EQUAL
0.60	sq.m	• Granite counter top at CR
ROOFING		
42.81	sq.m	• Prepainted long span, Rib type G.I sheet G.A # 24 pacific blue with complete accessories such as ridge, gutter, flushing, insulation and

		accessories
1	lot	<ul style="list-style-type: none"> • Roof framing
PAINTING		
258.96	sq.m	<ul style="list-style-type: none"> • Semi-gloss latex paint finish for internal wall
126.76	sq. m	<ul style="list-style-type: none"> • Flat wall enamel paint finish for Cement fiber board ceiling
129.48	meter	<ul style="list-style-type: none"> • Semi-gloss enamel paint finish for wooden cornice
PLUMBING WORKS		
1	lot	<ul style="list-style-type: none"> • Sewerlines
1	lot	<ul style="list-style-type: none"> • Waterlines
2	set	<ul style="list-style-type: none"> • Water closet - New Esedra 2819 3/4.5 L Dual flush button (color: white)
1	set	<ul style="list-style-type: none"> • Urinal (New Washbrook 6501, (URINAL) (Color: White) w/ flush valve
1	set	<ul style="list-style-type: none"> • Lavatory counter top-white, Aqualene or concept sphere by American Standard with lavatory faucet 1501 Saga including fittings and accessories
1	set	<ul style="list-style-type: none"> • Stainless steel kitchen sink, single bowl korea or Taiwan with faucet, complete with fittings and accessories
2	set	<ul style="list-style-type: none"> • Tissue holder
2	set	<ul style="list-style-type: none"> • Exhaust fan
1	set	<ul style="list-style-type: none"> • Floor drain
ELECTRICAL WORKS		
		<ul style="list-style-type: none"> • Lighting fixtures and accessories
5	set	<ul style="list-style-type: none"> • 2 x 36 Watts daylight linear flourecent lamp recessed-type lighting fixture with mirrorized reflector and louver
4	set	<ul style="list-style-type: none"> • 1 x 18 Watts daylight PL lamp 6" diameter pinlight diamond design reflector recessed mounted
		<ul style="list-style-type: none"> • Wires
3	box	<ul style="list-style-type: none"> • 3.5 sq. mm THHN copper wire stranded
		<ul style="list-style-type: none"> • Roughing-Ins and accessories
5	roll	<ul style="list-style-type: none"> • 25 mm diameter PVC flexible conduit pipe
10	pc	<ul style="list-style-type: none"> • 25 mm diameter rigid PVC conduit pipe
		<ul style="list-style-type: none"> • Box
14	pc	<ul style="list-style-type: none"> • Junction box
7	pc	<ul style="list-style-type: none"> • Utility box
		<ul style="list-style-type: none"> • Wiring devices and accessories
4	pc	<ul style="list-style-type: none"> • Single pole switch in one plate cover
3	pc	<ul style="list-style-type: none"> • 2 single pole switch in one plate cover

Delivery Term: Thirty (30) calendar days from signing of PO

Interested suppliers are required to submit their valid and current Mayor's Permit, DTI/SEC Registration, PHILGEPS Registration Certificate, Omnibus Sworn Statement, Income/ Business Tax Return, NFCC,PCAB License and duly signed price quotation form (Annex "A").

Submission of quotation and eligibility documents is on or before December 20, 2016, 10:00 a.m., at General Services Division (GSD), Ground Floor, OCOM Building, Port Area, Manila.

Award of contract shall be made to the lowest quotation, which complies with the minimum description as stated above and other terms and conditions stated in the price quotation form.

Any interlineations, erasures or overwriting shall be valid only if they are signed or initialed by the bidder or his/her duly authorized representative/s.

The BOC reserves the right to accept or reject any or all quotations and to impose additional terms and conditions as it may deem proper.

For inquiry, you may contact us at Telefax no. 527-9757 or email us at bacsecretariat@customs.gov.ph.

Very truly yours,



JOSEPH G. ESCASIO
Officer-in-Charge, Administration Office
Internal Administration Group

PRICE QUOTATION FORM

Date _____

The Bids and Awards Committee
Bureau of Customs
Port Area, Manila

Sir/Madam:

After having carefully read and accepted the terms and conditions in the Request for Quotation, hereunder is our quotation/s for the items as follows:

Qty.	DESCRIPTION	Unit Price	Total Price
	Dismantling/Restoration and Hauling-Out Works		
1 lot	<ul style="list-style-type: none"> Dismantling of floor and wall tiles at comfort room 		
1 lot	<ul style="list-style-type: none"> Provision of door opening at Comfort room 		
1 lot	<ul style="list-style-type: none"> Dismantling of corrugated roofing at CR and Mezzanine including framing 		
1lot	<ul style="list-style-type: none"> Dismantling of dilapidated ceiling at mezzanine 		
1lot	<ul style="list-style-type: none"> Dismantling of wood cladding at Mezzanine 		
1lot	<ul style="list-style-type: none"> Demolition of existing CHB enclosure at CR 		
1lot	<ul style="list-style-type: none"> Dismantling of electrical rough-ins 		
1lot	<ul style="list-style-type: none"> Restoration of all affected areas 		
1lot	<ul style="list-style-type: none"> Cleaning of site and hauling-out of debris/wastes 		
	MASONRY WORKS		
10.02 sq.m	<ul style="list-style-type: none"> 4" CHB wall with rebars 		
20.04 sq.m	<ul style="list-style-type: none"> Plain cement plastering 		
	CARPENTRY WORKS		
1lot	<ul style="list-style-type: none"> Dry wall cladding 		
	CEILING WORKS		
42.81 sq.m	<ul style="list-style-type: none"> 4.50 mm thk cement fiberboard ceiling on 0.40mm thk x 19mm x 25mm furring channel @ 0.40mm o.c. and 1.00mm thk x 12mm x 38mm carrying channel with 1.20m O.C B.W. with adjustable rod hanger at Pantry, CR's and Mezzanine 		
63.08 meters	<ul style="list-style-type: none"> Wooden cornice 		
	TILE WORKS		
7.30 sq.m	<ul style="list-style-type: none"> 300mm x 300mm CERAMIC FLOOR TILES MATTED FINISHED (COLOR:CHANDON SABBIA) 		
30.72 sq.m	<ul style="list-style-type: none"> 300mm x 300mm CERAMIC WALL TILES 		

	(MATTED WITH LUSTER), (COLOR: ANAHAW BEIGE) WITH ANAHAW LISTEL TILE OR APPROVED EQUAL		
0.60 sq.m	<ul style="list-style-type: none"> Granite counter top at CR 		
	ROOFING		
42.81 sq.m	<ul style="list-style-type: none"> Prepainted long span, Rib type G.I sheet G.A # 24 pacific blue with complete accessories such as ridge, gutter, flushing, insulation and accessories 		
1 lot	<ul style="list-style-type: none"> Roof framing 		
	PAINTING		
258.96 sq.m	<ul style="list-style-type: none"> Semi-gloss latex paint finish for internal wall 		
126.76 sq. m	<ul style="list-style-type: none"> Flat wall enamel paint finish for Cement fiber board ceiling 		
129.48 meters	<ul style="list-style-type: none"> Semi-gloss enamel paint finish for wooden cornice 		
	PLUMBING WORKS		
1 lot	<ul style="list-style-type: none"> Sewerlines 		
1 lot	<ul style="list-style-type: none"> Waterlines 		
2 sets	<ul style="list-style-type: none"> Water closet - New Esedra 2819 3/4.5 L Dual flush button (color: white) 		
1 set	<ul style="list-style-type: none"> Urinal (New Washbrook 6501, (URINAL) (Color: White) w/ flush valve 		
1 set	<ul style="list-style-type: none"> Lavatory counter top-white, Aqualene or concept sphere by American Standard with lavatory faucet 1501 Saga including fittings and accessories 		
1 set	<ul style="list-style-type: none"> Stainless steel kitchen sink, single bowl korea or Taiwan with faucet, complete with fittings and accessories 		
2 sets	<ul style="list-style-type: none"> Tissue holder 		
2 sets	<ul style="list-style-type: none"> Exhaust fan 		
1 set	<ul style="list-style-type: none"> Floor drain 		
	ELECTRICAL WORKS		
	<ul style="list-style-type: none"> Lighting fixtures and accessories 		
5 sets	<ul style="list-style-type: none"> 2 x 36 Watts daylight linear flourecent lamp recessed-type lighting fixture with mirrorized reflector and louver 		
4 sets	<ul style="list-style-type: none"> 1 x 18 Watts daylight PL lamp 6" diameter pinlight diamond design reflector recessed mounted 		
	<ul style="list-style-type: none"> Wires 		
3 boxes	<ul style="list-style-type: none"> 3.5 sq. mm THHN copper wire stranded 		
	<ul style="list-style-type: none"> Roughing-Ins and accessories 		
5 rolls	<ul style="list-style-type: none"> 25 mm diameter PVC flexible conduit pipe 		
10 pcs	<ul style="list-style-type: none"> 25 mm diameter rigid PVC conduit pipe 		
	<ul style="list-style-type: none"> Box 		
14 pcs	<ul style="list-style-type: none"> Junction box 		
7 pcs	<ul style="list-style-type: none"> Utility box 		

	• Wiring devices and accessories		
4 pcs	• Single pole switch in one plate cover		
3 pcs	• 2 single pole switch in one plate cover		

Warranty : ____ months from the date of delivery

Total amount in words:

The above-quoted prices are inclusive of all costs and applicable taxes.

Very truly yours,

Name/ Signature of Representative

Name of Company

Mayor's Permit No. _____

PhilGEPS Registration No. _____

(Please submit the photocopies of the above documents upon submission of quotation)