

DEPARTMENT OF FINANCE BUREAU OF CUSTOMS

REPUBLIC OF THE PHILIPPINES

A modernized and credible customs administration that upholds good governance and is among the world's best

BIDDING DOCUMENTS FOR THE SUPPLY, DELIVERY, INSTALLATION, TESTING AND COMMISSIONING OF STANDBY GENERATOR SETS WITH ACCESSORIES AND AUTOMATIC TRANSFER SWITCH (ATS) AT MICP, PORT OF CAGAYAN DE ORO, PORT OF DAVAO AND PORT OF SUBIC

Project ID No.: BOC-GOODS-2024-12 November 2024

TABLE OF CONTENTS

Section I. Invitation to Bid	6
Section II. Instructions to Bidders	7
1. Scope of Bid	8
2. Funding Information	8
3. Bidding Requirements	8
4. Corrupt, Fraudulent, Collusive, and Coercive Practices	8
5. Eligible Bidders	9
6. Origin of Goods	9
7. Subcontracts	9
8. Pre-Bid Conference	9
9. Clarification and Amendment of Bidding Documents	10
10. Documents comprising the Bid: Eligibility and Technical Components	10
11. Documents comprising the Bid: Financial Component	13
12. Bid Prices	13
13. Bid and Payment Currencies	14
14. Bid Security	
15. Sealing and Marking of Bids	14
16. Deadline for Submission of Bids	
17. Opening and Preliminary Examination of Bids	15
18. Domestic Preference	
19. Detailed Evaluation and Comparison of Bids	
20. Post-Qualification	14
21. Signing of the Contract	
Section III. Bid Data Sheet	15
Section IV. General Conditions of Contract	17
1. Scope of Contract	18
2. Advance Payment and Terms of Payment	18
3. Performance Security	18
4. Inspection and Tests	18
5. Warranty	19
6. Liability of the Supplier	19
Section V. Special Conditions of Contract	20
Section VI. Schedule of Requirements	22
Section VII. Technical Specifications	
Section VIII. Checklist of Technical and Financial Documents	

Glossary of Acronyms, Terms, and Abbreviations

ABC – Approved Budget for the Contract.

BAC – Bids and Awards Committee.

Bid – A signed offer or proposal to undertake a contract submitted by a bidder in response to and in consonance with the requirements of the bidding documents. Also referred to as *Proposal* and *Tender*. (2016 revised IRR, Section 5[c])

Bidder – Refers to a contractor, manufacturer, supplier, distributor and/or consultant who submits a bid in response to the requirements of the Bidding Documents. (2016 revised IRR, Section 5[d])

Bidding Documents – The documents issued by the Procuring Entity as the bases for bids, furnishing all information necessary for a prospective bidder to prepare a bid for the Goods, Infrastructure Projects, and/or Consulting Services required by the Procuring Entity. (2016 revised IRR, Section 5[e])

BIR – Bureau of Internal Revenue.

BSP – Bangko Sentral ng Pilipinas.

Consulting Services – Refer to services for Infrastructure Projects and other types of projects or activities of the GOP requiring adequate external technical and professional expertise that are beyond the capability and/or capacity of the GOP to undertake such as, but not limited to: (i) advisory and review services; (ii) pre-investment or feasibility studies; (iii) design; (iv) construction supervision; (v) management and related services; and (vi) other technical services or special studies. (2016 revised IRR, Section 5[i])

CDA - Cooperative Development Authority.

Contract – Refers to the agreement entered into between the Procuring Entity and the Supplier or Manufacturer or Distributor or Service Provider for procurement of Goods and Services; Contractor for Procurement of Infrastructure Projects; or Consultant or Consulting Firm for Procurement of Consulting Services; as the case may be, as recorded in the Contract Form signed by the parties, including all attachments and appendices thereto and all documents incorporated by reference therein.

CIF – Cost Insurance and Freight.

CIP – Carriage and Insurance Paid.

CPI – Consumer Price Index.

DDP – Refers to the quoted price of the Goods, which means "delivered duty paid."



DTI – Department of Trade and Industry.

EXW – Ex works.

FCA – "Free Carrier" shipping point.

FOB – "Free on Board" shipping point.

Foreign-funded Procurement or Foreign-Assisted Project– Refers to procurement whose funding source is from a foreign government, foreign or international financing institution as specified in the Treaty or International or Executive Agreement. (2016 revised IRR, Section 5[b]).

Framework Agreement – Refers to a written agreement between a procuring entity and a supplier or service provider that identifies the terms and conditions, under which specific purchases, otherwise known as "Call-Offs," are made for the duration of the agreement. It is in the nature of an option contract between the procuring entity and the bidder(s) granting the procuring entity the option to either place an order for any of the goods or services identified in the Framework Agreement List or not buy at all, within a minimum period of one (1) year to a maximum period of three (3) years. (GPPB Resolution No. 27-2019)

GFI – Government Financial Institution.

GOCC – Government-owned and/or –controlled corporation.

Goods – Refer to all items, supplies, materials and general support services, except Consulting Services and Infrastructure Projects, which may be needed in the transaction of public businesses or in the pursuit of any government undertaking, project or activity, whether in the nature of equipment, furniture, stationery, materials for construction, or personal property of any kind, including non-personal or contractual services such as the repair and maintenance of equipment and furniture, as well as trucking, hauling, janitorial, security, and related or analogous services, as well as procurement of materials and supplies provided by the Procuring Entity for such services. The term "related" or "analogous services" shall include, but is not limited to, lease or purchase of office space, media advertisements, health maintenance services, and other services essential to the operation of the Procuring Entity. (2016 revised IRR, Section 5[r])

GOP – Government of the Philippines.

GPPB – Government Procurement Policy Board.

INCOTERMS – International Commercial Terms.

Infrastructure Projects – Include the construction, improvement, rehabilitation, demolition, repair, restoration or maintenance of roads and bridges, railways, airports, seaports,



communication facilities, civil works components of information technology projects, irrigation, flood control and drainage, water supply, sanitation, sewerage and solid waste management systems, shore protection, energy/power and electrification facilities, national buildings, school buildings, hospital buildings, and other related construction projects of the government. Also referred to as *civil works or works*. (2016 revised IRR, Section 5[u])

LGUs – Local Government Units.

NFCC – Net Financial Contracting Capacity.

NGA – National Government Agency.

PhilGEPS - Philippine Government Electronic Procurement System.

Procurement Project – refers to a specific or identified procurement covering goods, infrastructure project or consulting services. A Procurement Project shall be described, detailed, and scheduled in the Project Procurement Management Plan prepared by the agency which shall be consolidated in the procuring entity's Annual Procurement Plan. (GPPB Circular No. 06-2019 dated 17 July 2019)

PSA – Philippine Statistics Authority.

SEC – Securities and Exchange Commission.

SLCC – Single Largest Completed Contract.

Supplier – refers to a citizen, or any corporate body or commercial company duly organized and registered under the laws where it is established, habitually established in business and engaged in the manufacture or sale of the merchandise or performance of the general services covered by his bid. (Item 3.8 of GPPB Resolution No. 13-2019, dated 23 May 2019). Supplier as used in these Bidding Documents may likewise refer to a distributor, manufacturer, contractor, or consultant.

UN – United Nations.



Section I. Invitation to Bid

SECTION I. INVITATION TO BID

"Supply, Delivery, Installation, Testing and Commissioning of Standby Generator Sets with Accessories and Automatic Transfer Switch (ATS) at MICP, Port of Cagayan De Oro, Port of Davao and Port of Subic"

1. The Bureau of Customs (BOC) through the authorized appropriations under the CY 2024 General Appropriation Act (GAA) intends to apply the sum Thirteen Million Nine Hundred Five Thousand Three Hundred Thirty-Three Pesos and Thirty-Three Centavos (PhP13,905,333.33) being the Approved Budget for the Contract (ABC) to payments under the contract for "Supply, Delivery, Installation, Testing and Commissioning of Standby Generator Sets with Accessories and Automatic Transfer Switch (ATS) at MICP, Port of Cagayan De Oro, Port of Davao and Port of Subic". Bids received in excess of the ABC shall be automatically rejected at the bid opening. Details are as follows:

Lot No.	Project ID No.	Description	Location	ABC
1		Supply, Delivery, Installation, Testing and Commissioning of Standby Generator Sets with	Port of Subic	
	BOC-GOODS- 2024-12A	Accessories and Automatic Transfer Switch (ATS) at MICP, Port of Cagayan De Oro, Port of Davao and Port of Subic	Manila International Container Port	Php9,020,666.67
2	BOC-GOODS-	Supply, Delivery, Installation, Testing and Commissioning of Standby Generator Sets with Accessories and Automatic	Port of Davao	Dhp/1 99/1 666 67
	2024-12B	Transfer Switch (ATS) at MICP, Port of Cagayan De Oro, Port of Davao and Port of Subic	Port of Cagayan De Oro (Sub-port of Tagoloan)	Php4,884,666.67
	То	tal ABC		Php13,905,333.33



- 2. The Bureau of Customs now invites bids of the above Procurement Project. All bidders should have completed, within five (5) years from the date of submission and receipt of bids, a contract similar to the Project. The description of an eligible bidder is contained in the Bidding Documents, particularly, in Section II (Instructions to Bidders).
- 3. Bidding will be conducted through open competitive bidding procedures using a nondiscretionary "*pass/fail*" criterion as specified in the 2016 revised Implementing Rules and Regulations (IRR) of Republic Act (RA) No. 9184.

Bidding is restricted to Filipino citizens/sole proprietorships, partnerships, or organizations with at least sixty percent (60%) interest or outstanding capital stock belonging to citizens of the Philippines, and to citizens or organizations of a country the laws or regulations of which grant similar rights or privileges to Filipino citizens, pursuant to RA No. 5183.

- 4. Prospective bidders may obtain further information from the BOC Bids and Awards Committee (BAC) Secretariat and inspect the Bidding Documents at the address given below during office hours from 8:00 a.m. to 5:00 p.m.
- 5. A complete set of Bidding Documents may be acquired by interested Bidders on November 8, 2024 from the given address and website below and upon payment of the applicable fee for the Bidding Documents, pursuant to the latest guidelines issued by the GPPB, in the amount for the following Lots: Lot 1- Ten Thousand Pesos (P10,000.00) and Lot 2 Five Hundred Pesos (P5,000.00). The Procuring Entity shall allow the bidder to present its proof of payment for the fees to be presented in person.
- 6. The BOC will hold a Pre-Bid Conference¹ on November 15, 2024, 9:00 a.m. at the GSD Conference Room, Ground Floor, OCOM Building, South Harbor, Gate 3, Port Area, Manila, and/or through videoconferencing/webcasting via Microsoft Teams, which shall be open to prospective bidders. The Letter of Intent shall be sent through email, thereafter, confirmation link shall be sent via Microsoft Teams.
- 7. All bids must be duly received by the BAC Secretariat through manual submission at the office address as indicated below on or November 27, 2024, 9:30 a.m. Any late bids shall not be accepted.
- 8. All bids must be accompanied by a bid security in any of the acceptable forms and in the amount stated in **ITB** Clause 14.
- 9. The bid opening shall be conducted on November 27, 2024, 10:00 a.m. at the given address below submitted bids will be opened in the presence of the bidders' representatives who choose to attend the activity.

¹ May be deleted in case the ABC is less than One Million Pesos (PhP1,000,000) where the Procuring Entity may not hold a Pre-Bid Conference.



- 10. The BOC reserves the right to reject any and all bids, declare a failure of bidding, or not award the contract at any time prior to contract award in accordance with Section 41 of RA 9184 and its IRR, without thereby incurring any liability to the affected bidder or bidders.
- 11. For further information, please refer to:

BOC-BAC Secretariat General Services Division OCOM Bldg., South Harbor, Gate 3, Port Area, Manila Telefax No. 526-6571 Email address: <u>bacsecretariat@customs.gov.ph</u>

12. You may visit the following websites:

For downloading of Bidding Documents: https://customs.gov.ph/bid-opportunities/

Date issued: November 08, 2024

ATTY. ERWIN T. MENDOZA Chairperson, BOC-BAC

Section II. Instructions to Bidders

TABLE OF CONTENTS

1.	SCOPE OF BID	9
2.	FUNDING INFORMATION	9
3.	BIDDING REQUIREMENTS	9
4.	CORRUPT, FRAUDULENT, COLLUSIVE, AND COERCIVE PRACTICES	9
5.	ELIGIBLE BIDDERS	9
6.	ORIGIN OF GOODS	10
7.	SUBCONTRACTS	10
8.	PRE-BID CONFERENCE	10
9.	CLARIFICATION AND AMENDMENT OF BIDDING DOCUMENTS	10
10.	DOCUMENTS COMPRISING THE BID: ELIGIBILITY AND TECHNICAL COMPONENTS	11
11.	DOCUMENTS COMPRISING THE BID: FINANCIAL COMPONENT	11
12.	BID PRICES	11
13.	BID AND PAYMENT CURRENCIES	12
14.	BID SECURITY	12
15.	SEALING AND MARKING OF BIDS	13
16.	DEADLINE FOR SUBMISSION OF BIDS	13
	OPENING AND PRELIMINARY EXAMINATION OF BIDS	
18.	DOMESTIC PREFERENCE	14
19.	DETAILED EVALUATION AND COMPARISON OF BIDS	14
20.	Post-Qualification	14
21.	SIGNING OF THE CONTRACT	16

1. Scope of Bid

The Procuring Entity, Bureau of Customs-Bids and Awards Committee (BOC-BAC) wishes to receive Bids for the "Supply, Delivery, Installation, Testing and Commissioning of Standby Generator Sets with Accessories and Automatic Transfer Switch (ATS) at MICP, Port of Cagayan De Oro, Port of Davao and Port of Subic" with identification number BOC-GOODS-2024-12.

The Procurement Project (referred to herein as "Project") is composed of two (2) lots the details of which are described in Section VII (Technical Specifications).

2. Funding Information

- 2.1. The Government of the Philippine (GOP) through the source of funding as indicated below for FY 2024 General Appropriation Act (GAA) in the amount of Thirteen Million Nine Hundred Five Thousand Three Hundred Thirty-Three Pesos and Thirty-Three Centavos (PhP13,905,333.33).
- 2.2. The source of funding is:
 - a. NGA, the General Appropriations Act or Special Appropriations.

3. Bidding Requirements

The Bidding for the Project shall be governed by all the provisions of RA No. 9184 and its 2016 revised IRR, including its Generic Procurement Manuals and associated policies, rules and regulations as the primary source thereof, while the herein clauses shall serve as the secondary source thereof.

Any amendments made to the IRR and other GPPB issuances shall be applicable only to the ongoing posting, advertisement, or **ITB** by the BAC through the issuance of a supplemental or bid bulletin.

The Bidder, by the act of submitting its Bid, shall be deemed to have verified and accepted the general requirements of this Project, including other factors that may affect the cost, duration and execution or implementation of the contract, project, or work and examine all instructions, forms, terms, and project requirements in the Bidding Documents.

4. Corrupt, Fraudulent, Collusive, and Coercive Practices

The Procuring Entity, as well as the Bidders and Suppliers, shall observe the highest standard of ethics during the procurement and execution of the contract. They or through an agent shall not engage in corrupt, fraudulent, collusive, coercive, and obstructive practices defined under Annex "I" of the 2016 revised IRR of RA No. 9184 or other integrity violations in competing for the Project.

5. Eligible Bidders

- 5.1. Only Bids of Bidders found to be legally, technically, and financially capable will be evaluated.
- 5.2. Foreign ownership limited to those allowed under the rules may participate in this Project.
- 5.3. Pursuant to Section 23.4.1.3 of the 2016 revised IRR of RA No.9184, the Bidder shall have an SLCC that is at least one (1) contract similar to the Project the value of which, adjusted to current prices using the PSA's CPI, must be at least equivalent to:
 - a. For the procurement of Non-expendable Supplies and Services: The Bidder must have completed a single contract that is similar to this Project, equivalent to at least fifty percent (50%) of the ABC.
 - b. For the procurement of Expendable Supplies: The Bidder must have completed a single contract that is similar to this Project, equivalent to at least twenty-five percent (25%) of the ABC.
 - c. For procurement where the Procuring Entity has determined, after the conduct of market research, that imposition of either (a) or (b) will likely result to failure of bidding or monopoly that will defeat the purpose of public bidding: the Bidder should comply with the following requirements: [Select either failure or monopoly of bidding based on market research conducted]
 - i. Completed at least two (2) similar contracts, the aggregate amount of which should be equivalent to at least *fifty percent* (50%) in the case of non-expendable supplies and services or twenty-five percent (25%) in the case of expendable supplies] of the ABC for this Project; and
 - ii. The largest of these similar contracts must be equivalent to at least half of the percentage of the ABC as required above.
- 5.4. The Bidders shall comply with the eligibility criteria under Section 23.4.1 of the 2016 IRR of RA No. 9184.

6. Origin of Goods

There is no restriction on the origin of goods other than those prohibited by a decision of the UN Security Council taken under Chapter VII of the Charter of the UN, subject to Domestic Preference requirements under **ITB** Clause 18.

7. Subcontracts

7.1. The Bidder may subcontract portions of the Project to the extent allowed by the Procuring Entity as stated herein, but in no case more than twenty percent (20%) of the Project.

The Procuring Entity has prescribed that:

- a. Subcontracting is not allowed.
- 7.2. Subcontracting of any portion of the Project does not relieve the Supplier of any liability or obligation under the Contract. The Supplier will be responsible for the acts, defaults, and negligence of any subcontractor, its agents, servants, or workmen as fully as if these were the Supplier's own acts, defaults, or negligence, or those of its agents, servants, or workmen.

8. Pre-Bid Conference

The Procuring Entity will hold a pre-bid conference for this Project on the specified date and time and either at its physical address and/or through videoconferencing/webcasting as indicated in paragraph 6 of the **ITB**.

9. Clarification and Amendment of Bidding Documents

Prospective bidders may request for clarification on and/or interpretation of any part of the Bidding Documents. Such requests must be in writing and received by the Procuring Entity, either at its given address or through electronic mail indicated in the **ITB**, at least ten (10) calendar days before the deadline set for the submission and receipt of Bids.

10. Documents comprising the Bid: Eligibility and Technical Components

- 10.1. The first envelope shall contain the eligibility and technical documents of the Bid as specified in Section VIII (Checklist of Technical and Financial Documents).
- 10.2. The Bidder's SLCC as indicated in **ITB** Clause 5.3 should have been completed within five (5) years as provided in paragraph 2 of the **ITB** prior to the deadline for the submission and receipt of bids.
- 10.3. If the eligibility requirements or statements, the bids, and all other documents for submission to the BAC are in foreign language other than English, it must be accompanied by a translation in English, which shall be authenticated by the appropriate Philippine foreign service establishment, post, or the equivalent office having jurisdiction over the foreign bidder's affairs in the Philippines. Similar to the required authentication above, for Contracting Parties to the Apostille Convention, only the translated documents shall be authenticated through an apostille pursuant to GPPB Resolution No. 13-2019 dated 23 May

2019. The English translation shall govern, for purposes of interpretation of the bid.

11. Documents comprising the Bid: Financial Component

- 11.1. The second bid envelope shall contain the financial documents for the Bid as specified in **Section VIII (Checklist of Technical and Financial Documents)**.
- 11.2. If the Bidder claims preference as a Domestic Bidder or Domestic Entity, a certification issued by DTI shall be provided by the Bidder in accordance with Section 43.1.3 of the 2016 revised IRR of RA No. 9184.
- 11.3. Any bid exceeding the ABC indicated in paragraph 1 of the **ITB** shall not be accepted.
- 11.4. For Foreign-funded Procurement, a ceiling may be applied to bid prices provided the conditions are met under Section 31.2 of the 2016 revised IRR of RA No. 9184.

12. Bid Prices

- 12.1. Prices indicated on the Price Schedule shall be entered separately in the following manner:
 - a. For Goods offered from within the Procuring Entity's country:
 - i. The price of the Goods quoted EXW (ex-works, ex-factory, exwarehouse, ex-showroom, or off-the-shelf, as applicable);
 - ii. The cost of all customs duties and sales and other taxes already paid or payable;
 - iii. The cost of transportation, insurance, and other costs incidental to delivery of the Goods to their final destination; and
 - iv. The price of other (incidental) services, if any, listed in e.
 - b. For Goods offered from abroad:
 - i. Unless otherwise stated in the **BDS**, the price of the Goods shall be quoted delivered duty paid (DDP) with the place of destination in the Philippines as specified in the **BDS**. In quoting the price, the Bidder shall be free to use transportation through carriers registered in any eligible country. Similarly, the Bidder may obtain insurance services from any eligible source country.
 - ii. The price of other (incidental) services, if any, as listed in Section VII (Technical Specifications).

13. Bid and Payment Currencies

- 13.1. For Goods that the Bidder will supply from outside the Philippines, the bid prices may be quoted in the local currency or tradeable currency accepted by the BSP at the discretion of the Bidder. However, for purposes of bid evaluation, Bids denominated in foreign currencies, shall be converted to Philippine currency based on the exchange rate as published in the BSP reference rate bulletin on the day of the bid opening.
- 13.2. Payment of the contract price shall be made in:
 - a. Philippine Pesos.

14. Bid Security

- 14.1. The Bidder shall submit a Bid Securing Declaration² or any form of Bid Security in the amount indicated in the **BDS**, which shall be not less than the percentage of the ABC in accordance with the schedule in the **BDS**.
- 14.2. The Bid and bid security shall be valid until March 27, 2025 Any Bid not accompanied by an acceptable bid security shall be rejected by the Procuring Entity as non-responsive.

15. Sealing and Marking of Bids

Each Bidder shall submit one copy of the first and second components of its Bid.

The Procuring Entity may request additional hard copies and/or electronic copies of the Bid. However, failure of the Bidders to comply with the said request shall not be a ground for disqualification.

If the Procuring Entity allows the submission of bids through online submission or any other electronic means, the Bidder shall submit an electronic copy of its Bid, which must be digitally signed. An electronic copy that cannot be opened or is corrupted shall be considered non-responsive and, thus, automatically disqualified.

16. Deadline for Submission of Bids

16.1. The Bidders shall submit on the specified date and time and either at its physical address or through online submission as indicated in paragraph 7 of the **ITB**.

 $^{^{2}}$ In the case of Framework Agreement, the undertaking shall refer to entering into contract with the Procuring Entity and furnishing of the performance security or the performance securing declaration within ten (10) calendar days from receipt of Notice to Execute Framework Agreement.

17. Opening and Preliminary Examination of Bids

17.1. The BAC shall open the Bids in public at the time, on the date, and at the place specified in paragraph 9 of the **ITB**. The Bidders' representatives who are present shall sign a register evidencing their attendance. In case videoconferencing, webcasting or other similar technologies will be used, attendance of participants shall likewise be recorded by the BAC Secretariat.

In case the Bids cannot be opened as scheduled due to justifiable reasons, the rescheduling requirements under Section 29 of the 2016 revised IRR of RA No. 9184 shall prevail.

17.2. The preliminary examination of bids shall be governed by Section 30 of the 2016 revised IRR of RA No. 9184.

18. Domestic Preference

18.1. The Procuring Entity will grant a margin of preference for the purpose of comparison of Bids in accordance with Section 43.1.2 of the 2016 revised IRR of RA No. 9184.

19. Detailed Evaluation and Comparison of Bids

- 19.1. The Procuring BAC shall immediately conduct a detailed evaluation of all Bids rated "*passed*," using non-discretionary pass/fail criteria. The BAC shall consider the conditions in the evaluation of Bids under Section 32.2 of the 2016 revised IRR of RA No. 9184.
- 19.2. If the Project allows partial bids, bidders may submit a proposal on any of the lots or items, and evaluation will be undertaken on a per lot or item basis, as the case maybe. In this case, the Bid Security as required by **ITB** Clause 15 shall be submitted for each lot or item separately.
- 19.3. The descriptions of the lots or items shall be indicated in Section VII (Technical Specifications), although the ABCs of these lots or items are indicated in the BDS for purposes of the NFCC computation pursuant to Section 23.4.2.6 of the 2016 revised IRR of RA No. 9184. The NFCC must be sufficient for the total of the ABCs for all the lots or items participated in by the prospective Bidder.
- 19.4. The Project shall be awarded one Project having several items that shall be awarded as one contract.
- 19.5. Except for bidders submitting a committed Line of Credit from a Universal or Commercial Bank in lieu of its NFCC computation, all Bids must include the NFCC computation pursuant to Section 23.4.1.4 of the 2016 revised IRR of RA No. 9184, which must be sufficient for the total of the ABCs for all the lots or items participated in by the prospective Bidder. For bidders submitting the committed Line of Credit, it must be at least equal to ten percent (10%) of the ABCs for all the lots or items participated in by the prospective Bidder.

20. Post-Qualification

20.1. Within a non-extendible period of five (5) calendar days from receipt by the Bidder of the notice from the BAC that it submitted the Lowest Calculated Bid, that it is one of the eligible bidders who have submitted bids that are found to be technically and financially compliant,}the Bidder shall submit its latest income and business tax returns filed and paid through the BIR Electronic Filing and Payment System (eFPS) and other appropriate licenses and permits required by law and stated in the **BDS**. The LCB shall likewise submit the required documents for final Post Qualification.}

21. Signing of the Contract

21.1. The documents required in Section 37.2 of the 2016 revised IRR of RA No. 9184 shall form part of the Contract. Additional Contract documents are indicated in the **BDS**.

Section III. Bid Data Sheet

ITB Clause						
1	The P	rocuring Ent	ity is the Bureau of	f Customs.		
	Com Tran Port	missioning c sfer Switch (of Subic"	of Standby Generat	or Sets with Acce rt of Cagayan De	stallation, Testing as essories and Automa Oro, Port of Davao as ODS-2024-12.	tic
2		unding Sour				
	The appro of Th	Government priations und irteen Millic	of the Philipp ler the CY 2024 G	eneral Appropriat Five Thousand T	rough the authoriz tions Act in the amou Three Hundred Thirt 33.33).	ınt
2		-	have two (2) lots a number of the Con		ws:	
	Lot No.	Project ID No.	Description	Location	ABC	
	1		Supply, Delivery, Installation, Testing and Commissioning of Standby	Port of Subic		
		BOC- GOODS 2024-12A	Generator Sets with Accessories and Automatic Transfer Switch (ATS) at MICP, Port of Cagayan De Oro, Port of Davao and Port of Subic	Manila International Container Port	Php9,020,666.67	

	2	BOC- GOODS- 2024-12B	Supply, Delivery, Installation, Testing and Commissioning of Standby Generator Sets with Accessories and Automatic Transfer Switch (ATS) at MICP, Port of Cagayan De Oro, Port of Davao and Port of Subic	Port of Davao Port of Cagayan De Oro (Sub-port of Tagoloan)	Php4,884,666.67
		Total	ABC		Php13,905,333.33
3	No fu	rther instruct	ion.		
5	•		lers found to be leg s defined in ITB C	•	and financially capable
5.2	Foreig	gn bidders are	e not allowed.		
5.3	single at leas Bidde Contra Inspec Accep Failur Comp disqua For t Instal	contract that at fifty percer rs must inclu act, Notice of ction and According tance Report e to submit a letion or a f alification of his purpose lation, Tes	t is similar to the p at (50%) of the AB ade in their Bid a p of Award (NOA), ceptance Committed t or equivalent in the copy of Single La ailure against the the bidder for awa , similar contrac	roject at hand an C to be bid. ohotocopy of Sin Notice to Proce e (TIAC) Repor he Private Sector argest Completed veracity of such rd and forfeiture t shall refer to hissioning of (to November 27, 2024, ad whose value must be agle Largest Completed ceed (NTP), Technical t or Certificate of Final c. Contract with proof of a shall be a ground for of the bid security.
5.4		rther instruct	· · · · ·	·	
7.1 (a)	No fu	rther instruct	ion.		
8	the Gate 3	SD Conferen 3, Port Area,	ce Room, Ground	Floor, OCOM E ough videoconfe	er 15, 2024, 9:00 a.m. at Building, South Harbor, rencing/webcasting via bidders.

14.1	The bid security shall be in the form of a Bid Securing Declaration or any of the following forms and amounts:
	Lot 1
	1. The amount of not less than Php180,413.33 , or 2% if bid security is in cash, cashier's/manager's check, bank draft/guarantee or irrevocable letter of credit;
	2. The amount of not less than Php451,033.33 , or 5% if bid security is in Surety Bond.
	Lot 2
	1. The amount of not less than Php97,693.33 or 2% if bid security is in cash, cashier's/manager's check, bank draft/guarantee or irrevocable letter of credit;
	2. The amount of not less than Php244,233.33 , or 5% if bid security is in Surety Bond.
15	Each Bidder shall submit one (1) original and two (2) copies of the first and second components of its bid with proper tabs.
	All documents within the Original Bid, along with any accompanying attachments like brochures etc., must be originally signed and certified as true copies by the bidder and/or authorized representative. The BAC may require submission of the original documents for the purposes of verification, validation, and ascertaining its authenticity.
19.3	attachments like brochures etc., must be originally signed and certified as true copies by the bidder and/or authorized representative.
19.3	attachments like brochures etc., must be originally signed and certified as true copies by the bidder and/or authorized representative.The BAC may require submission of the original documents for the purposes of verification, validation, and ascertaining its authenticity.Partial bids are allowed. All Goods are grouped in lots listed below. Bidders shall have the option of submitting a proposal on any or all lots and evaluation and contract award will be undertaken on a per lot basis. Lots shall not be divided further into sub-lots for the purpose of bidding, evaluation, and
	attachments like brochures etc., must be originally signed and certified as true copies by the bidder and/or authorized representative.The BAC may require submission of the original documents for the purposes of verification, validation, and ascertaining its authenticity.Partial bids are allowed. All Goods are grouped in lots listed below. Bidders shall have the option of submitting a proposal on any or all lots and evaluation and contract award will be undertaken on a per lot basis. Lots shall not be divided further into sub-lots for the purpose of bidding, evaluation, and contract award.Within a non-extendible period of five (5) calendar days from receipt by the Bidder and/or authorized representative of the notice from the BAC that it submitted the Single/Lowest Calculated Bid, the Bidder shall submit the
	attachments like brochures etc., must be originally signed and certified as true copies by the bidder and/or authorized representative.The BAC may require submission of the original documents for the purposes of verification, validation, and ascertaining its authenticity.Partial bids are allowed. All Goods are grouped in lots listed below. Bidders shall have the option of submitting a proposal on any or all lots and evaluation and contract award will be undertaken on a per lot basis. Lots shall not be divided further into sub-lots for the purpose of bidding, evaluation, and contract award.Within a non-extendible period of five (5) calendar days from receipt by the Bidder and/or authorized representative of the notice from the BAC that it submitted the Single/Lowest Calculated Bid, the Bidder shall submit the following documents:1. Certificate of Site Inspection issued by Ports;

21.1	No further instruction
	 payment (filed and paid through Bureau of Internal Revenue (BIR) Electronic Filing and Payment System (eFS); 7. VAT Returns (Form 2550M and 2550Q) or Percentage Tax Returns (2551M) with proof of payment covering the last 6 months; 8. Latest Audited Financial Statement duly received by Security and Exchange Commission (SEC) and BIR; and 9. Updated Mayor's Permit, Tax Clearance and Department of Trade and Industry or SEC Registration.
	6. Latest Income Tax Return and business Tax Return with proof of

Section IV. General Conditions of Contract

TABLE OF CONTENTS

1.	SCOPE OF CONTRACT	21
2.	Advance Payment and Terms of Payment	21
3.	Performance Security	21
4.	INSPECTION AND TESTS	21
5.	WARRANTY	22
6.	LIABILITY OF THE SUPPLIER	22

1. Scope of Contract

This Contract shall include all such items, although not specifically mentioned, that can be reasonably inferred as being required for its completion as if such items were expressly mentioned herein. All the provisions of RA No. 9184 and its 2016 revised IRR, including the Generic Procurement Manual, and associated issuances, constitute the primary source for the terms and conditions of the Contract, and thus, applicable in contract implementation. Herein clauses shall serve as the secondary source for the terms and conditions of the Contract.

This is without prejudice to Sections 74.1 and 74.2 of the 2016 revised IRR of RA No. 9184 allowing the GPPB to amend the IRR, which shall be applied to all procurement activities, the advertisement, posting, or invitation of which were issued after the effectivity of the said amendment.

Additional requirements for the completion of this Contract shall be provided in the **Special Conditions of Contract (SCC).**

2. Advance Payment and Terms of Payment

- 2.1. Advance payment of the contract amount is provided under Annex "D" of the revised 2016 IRR of RA No. 9184.
- 2.2. The Procuring Entity is allowed to determine the terms of payment on the partial or staggered delivery of the Goods procured, provided such partial payment shall correspond to the value of the goods delivered and accepted in accordance with prevailing accounting and auditing rules and regulations. The terms of payment are indicated in the **SCC**.

3. Performance Security

Within ten (10) calendar days from receipt of the Notice of Award by the Bidder from the Procuring Entity but in no case later than prior to the signing of the Contract by both parties, the successful Bidder shall furnish the performance security in any of the forms prescribed in Section 39 of the 2016 revised IRR of RA No. 9184.

4. Inspection and Tests

The Procuring Entity or its representative shall have the right to inspect and/or to test the Goods to confirm their conformity to the Project specifications at no extra cost to the Procuring Entity in accordance with the Generic Procurement Manual. In addition to tests in the **SCC**, **Section IV** (**Technical Specifications**) shall specify what inspections and/or tests the Procuring Entity requires, and where they are to be conducted. The Procuring Entity shall notify the Supplier in writing, in a timely manner, of the identity of any representatives retained for these purposes.

All reasonable facilities and assistance for the inspection and testing of Goods, including access to drawings and production data, shall be provided by the Supplier to the authorized inspectors at no charge to the Procuring Entity.

5. Warranty

- 5.1 In order to assure that manufacturing defects shall be corrected by the Supplier, a warranty shall be required from the Supplier as provided under Section 62.1 of the 2016 revised IRR of RA No. 9184.
- 5.2 The Procuring Entity shall promptly notify the Supplier in writing of any claims arising under this warranty. Upon receipt of such notice, the Supplier shall, repair or replace the defective Goods or parts thereof without cost to the Procuring Entity, pursuant to the Generic Procurement Manual.

6. Liability of the Supplier

The Supplier's liability under this Contract shall be as provided by the laws of the Republic of the Philippines.

If the Supplier is a joint venture, all partners to the joint venture shall be jointly and severally liable to the Procuring Entity.

Section V. Special Conditions of Contract

GCC Clause	
1	Delivery and Documents –
	The Goods shall only be delivered by the supplier as indicated in Section VI. Schedule of Requirements. Moreover, the delivery schedule as indicated in Section VI. Schedule of Requirements may be modified at the option of the Procuring Entity, with prior due notice, written or verbal, to the Supplier.
2.2	Payment shall be made after formal acceptance of deliverables, and
	10% shall be retained until completion of contract.
3	No further instructions.
4	Inspections and Tests
	Complete Goods shall be inspected and/or tested by the End User based in Section VII. Technical Specifications.
5.1	One (1) year warranty on parts and services commencing after the final acceptance of Procuring Entity.
	After Sales Service and Support during the warranty period, all reported defects shall be completely/satisfactory repaired/replaced by the supplier/contractor within 72 hours after receipt of verbal and/or written notice from the Procuring Entity.
5.2	No further instructions.
6	No additional provision.

Section VI. Schedule of Requirements

Lot	Description	Location	Qty (unit/s)	Delivery Date
	Supply, Delivery, Installation, Testing and Commissioning of Standby Generator Sets with	Port of Subic	2	Supply, Delivery, Installation, Testing and Commissioning within ninety (90) calendar days
1	Accessories and Automatic Transfer Switch (ATS) at MICP, Port of Cagayan De Oro, Port of Davao and Port of Subic	Manila International Container Port	1	after receipt of Notice to Proceed to be delivered in Port of Subic and Manila International Airport
	Supply, Delivery, Installation, Testing and Commissioning of Standby Generator Sets with Accessories and	Port of Davao	1	Supply, Delivery, Installation, Testing and Commissioning within ninety (90) calendar days after receipt of Notice to
2	Automatic Transfer Switch (ATS) at MICP, Port of Cagayan De Oro, Port of Davao and Port of Subic	Port of Cagayan De Oro (Sub- Port of Tagoloan)	1	Proceed to be delivered in Port of Davao and Port of Cagayan De Oro (Sub-Port of Tagoloan)

I hereby commit to comply and deliver the above requirements.

Name of Company (in print)

Signature of Company Authorized Representative

Name & Designation (in print)

Date

Section VII. Technical Specifications

STATEMENT OF COMPLIANCE TO TECHNICAL SPECIFICATIONS

A. INSTRUCTION:

The bidder must state in the last column opposite each parameter and required specifications either "Comply" or "Not Comply". All pages shall be properly signed. Bidders must state here either "Comply" or "Not Comply" against each of the individual parameters of each Specification stating the corresponding performance parameter of the equipment offered. Statements of "Comply" or "Not Comply" must be supported by evidence in a Bidders Bid and cross-referenced to that evidence. Evidence shall be in the form of manufacturer's un-amended sales literature, unconditional statements of specification and compliance issued by the manufacturer, samples, independent test data etc., as appropriate. A statement that is not supported by evidence or is subsequently found to be contradicted by the evidence presented will render the Bid under evaluation liable for rejection. A statement either in the Bidders statement of compliance or the supporting evidence that is found to be false either during Bid evaluation, post-qualification or the execution of the Contract may be regarded as fraudulent and render the Bidder or supplier liable for prosecution subject to the provisions of ITB Clause above goods manufactured by us.

Lot	Description	Statement of Compliance
1	PORT OF SUBIC (75KVA)	
	• Standby Power Rating: 75KVA/60 KW	
	Rated AC Voltage: 230V	
	• Frequency: 60Hz	
	Rated Speed: 1800rpm	
	Power Factors: 0.8	
	Phases: Three Phase	
	• Type: Silent Type	
	• Engine Type: Diesel Fuel	
	• Noise Level: 75-85 db @ 1m	
	Fuel System: Manufacturer Standard	
	Electrical System: Manufacturer's Standard	
	Digital Controller:	
	Over & Under Speed	
	Low Oil Pressure	
	Under/Over Generator Voltage	
	Low & High Battery Voltage	
	Emergency Stop	
	Over Current	
	High Engine Temperature	
	Start/Stop Failure	
	Charge Fail	
	Other Accessories:	
	Set mounted tropical radiator	
	Set-mounted circuit breaker	
	Skid-base diesel tank	
	 Digital generator set controller with meter and 	
	alert	

	Free maintenance type battery	
Autor	matic Transfer Switch (ATS)	
٠	Ampere Rating: 200 Amps	
•	Voltage Rating: 230 Volts	
٠	Ampere Frame: 250AF	
٠	Interrupting Capacity: 25KAIC	
٠	Phase: Three Phase	
٠	Enclosure: Nema – 1	
٠	Accessories:	
	Phase Voltage Digital Meter (3 Phase)	
	Phase Current Digital Meter (3 Phase)	
	Normal and Emergency Signal/Indicator	
Instal	llation, Testing and Commissioning	
I.	Mobilization	
	The mobilization of the project shall consist of the	
	following:	
	a. Preparation of logistics of contractor's	
	equipment; and	
	b. Setting up of temporary facilities within the site.	
	Site.	
II.	Electrical Works	
	a. Walk around, Visual inspection, Gather data,	
	and information;	
	b. Securing and processing of necessary permits	
	and licenses for the permissible operation of	
	generator set (Mechanical permits from	
	respective LGU);	
	c. Marking and Positioning of Generator and	
	Automatic Transfer Switch (ATS);	
	d. Site coordination for power interruption during	
	transfer of normal to emergency;	
	e. Coordination to Electric Cooperative for	
	temporary shutdown;	
	f. Supply and Installation of new Generator with	
	accessories and ATS.	
	g. Supply and Installation of wiring system from	
	Generator to ATS and from ATS to existing	
	electrical main panelboard shall be overhead	
	installation. Color Coded (RYB) THHN wire	
	in IMC conduit pipe shall be used for installation;	
	h. Termination of existing cable wires to	
	delivered new Generator and ATS;	
	i. Installation of control wiring from ATS to	
	Generator panel;	
	j. Installation of three phase shall be in correct phase sequence to supply the power from	
	phase sequence to suppry the power non	

	1
emergency generator for the future electrical system arrangement;	
k. Load balancing shall be done for all three-	
phase supply;	
1. If any has been omitted for any items of work	
or materials usually furnished, which are	
necessary for the completion of entire work as	
outlined herein before, then such items must	
be and hereby included to complete the standard installation;	
m. Conduct Continuity Test and Insulation	
Resistance Test for installed feeder line and to	
submit test reports. n. All synch controllers and generators must be	
set to automatic mode;	
o. Supply of fuel in Generator for testing (1/4 of	
fuel tank capacity);	
p. Simulate operation of the ATS transfer from	
normal to emergency power;	
q. Testing and commissioning of new Generator and ATS with load;	
r. Return operation of the ATS emergency power	
to normal power	
s. Double check genset controller, synch	
controller, and ATS controller if it's in auto mode before demobilized;	
t. Submission of test reports (continuity and	
insulation resistance test) and service report;	
u. Submission of certificate of completion;	
v. Submission of signed and sealed as-built plan of	
electrical power distribution system to	
General Services Division (GSD) after	
completion of project and final acceptance;	
III. Civil Works	
a. Construction of elevated concrete pad (30cm	
from the highest elevated area) as per new	
Generator requirements;	
IV. Demobilization	
a. Sites clean up.	
b. Removal and hauling of tools and equipment	
from project site.	
Code and Standards	
Code and Standards a. PEC – Philippine Electrical Code	
b. NFPA 110 Standard for Emergency and Standby	
Power System	
c. UL 1008 - Standard for Automatic Transfer	
Switches	

	Other	Requirements	
	0	a. Original Equipment Manufacturer (OEM) Certificate (Engine, Alternator and Controller)	
		b. ISO Certificate	
		c. Load Bank Test Result/Certification	
		d. Operation and Maintenance Manual for Genset and	
		Automatic Transfer Switch	
		e. Brochure of Generator Set and Automatic Transfer	
		Switch	
1	MAN	ILA INTERNATIONAL CONTAINER PORT (800K)	VA)
	•	Standby Power Rating: 800KVA/640KW	
	•	Rated AC Voltage: 230V	
	•	Frequency: 60Hz	
	•	Rated Speed: 1800rpm	
	•	Power Factors: 0.8	
	•	Phases: Three Phase	
	•	Type: Open Type	
	•	Engine Type: Diesel Fuel	
	•	Fuel System: Manufacturer Standard	
	•	Electrical System: Manufacturer's Standard	
	•	Digital Controller:	
	•	 Øver & Under Speed 	
		 Low Oil Pressure 	
		 Under/Over Generator Voltage 	
		 Low & High Battery Voltage 	
		 Emergency Stop 	
		 Over Current 	
		 High Engine Temperature 	
		 Start/Stop Failure 	
		➢ Charge Fail	
	•	Other Accessories:	
		Set-mounted tropical radiator	
		Set-mounted circuit breaker	
		Skid-base diesel tank	
		Digital generator set controller with meter and	
		alert	
		Free maintenance type battery	
		natic Transfer Switch (ATS)	
	Ampe	ere Rating: 2000 Amps	
	•	Voltage Rating: 230 Volts	
	•	Ampere Frame: 2500AF	
	•	Interrupting Capacity: 85KAIC	
	•	Phase: Three Phase	
	•	Enclosure: Nema – 1	
	•	Accessories:	
		Phase Voltage Digital Meter (3 Phase)	
		Phase Current Digital Meter (3 Phase)	
		Normal and Emergency Signal/Indicator	
	Instal	lation, Testing and Commissioning	

I.	Mobilization The mobilization of the project shall consist of the	
	following: a. Preparation of logistics of contractor's	
	equipment; and	
	b. Setting up of temporary facilities within the	
	site.	
II.	Electrical Works	
	a. Walk around, visual inspection, gather data,	
	and information;	
	b. Securing and processing of necessary permits and licenses for the permissible operation of	
	generator set (Mechanical permit from	
	respective LGU);	
	c. Dismantling, hauling and rigging of existing	
	Generator, Automatic Transfer Switch	
	(ATS) and its accessories; d. Construction of concrete pad as per new	
	Generator requirements;	
	e. Marking and Positioning of new Generator and	
	Automatic Transfer Switch (ATS);	
	f. Supply and installation of exhaust and air duct system;	
	g. Site coordination for power interruption during	
	transfer of normal to emergency;	
	h. Coordination to Meralco/Electric Cooperative for temporary shutdown;	
	i. Supply and Installation of new Generator;	
	j. Installation of wiring system from Generator	
	to ATS and from ATS to existing electrical	
	main panelboard shall be overhead	
	installation. THHN wire in IMC conduit pipe shall be used for installation;	
	k. Termination of existing cable wires to	
	delivered new Generator and ATS;	
	l. Installation of control wiring from ATS to	
	Generator panel; m. Installation of three phase shall be in correct.	
	m. Installation of three phase shall be in correct phase sequence to supply the power from	
	emergency generator for the future electrical	
	system arrangement;	
	n. Load balancing shall be done for all three-	
	phase supply;	
	o. If any has been omitted for any items of work	
	or materials usually furnished, which are	
	necessary for the completion of entire work as	
	outlined herein before, then such items must	

Г	
	be and hereby included to complete the
	standard installation;
	p. Supply and installation of engine exhaust
	(exhaust system shall be minimum of three
	meters from the ground).
	q. All synch controllers and generators must be
	set to automatic mode;
	r. Supply of fuel of Generator for testing (1/4 of
	fuel tank capacity);
	s. Simulate operation of the ATS transfer from
	normal to emergency power;
	t. Testing and commissioning of new Generator
	and ATS with load;
	u. Return operation of the ATS emergency power
	to normal power;
	v. Double check genset controller, sync
	controller, and ATS controller if it is in auto
	mode before being demobilized;
	w. Submission of test reports (continuity and
	insulation resistance test) and service report;
	x. Submission of certificate of completion;
	y. Transfer to Warehouse 159 with provision of
	protective vinyl cover/sheet (Delgado Street corner
	16 th Street, South Harbor, Port Area, Manila) of
	Old Generator and Automatic Transfer Switch
	(ATS);
	z. Submission of signed and sealed as-built plan of
	electrical power distribution system to GSD
	after completion of project and final
	acceptance;
III. Civ	vil Works
	a. Construction of elevated concrete pad (30cm
	from the highest elevated area) as per new
	Generator requirements;
IV. De	emobilization
	a. Sites clean up;
	b. Hauling of debris materials from project site to
	appropriate disposal area; and
	c. Removal and hauling of tools and equipment
	from project site.
Code and S	
	PEC – Philippine Electrical Code
b.	NFPA 110 Standard for Emergency and Standby
	Power System
C.	UL 1008 - Standard for Automatic Transfer
	Switches
Other Deer	viromonts
Other Req	
a.	Original Equipment Manufacturer (OEM)

r	1		
		Certificate (Engine, Alternator and Controller)	
		b. ISO Certificate	
		c. Load Bank Test Result/Certification	
		d. Operation and Maintenance Manual for Genset and	
		Automatic Transfer Switch e. Brochure of Generator Set and Automatic Transfer	
		e. Brochure of Generator Set and Automatic Transfer Switch	
2	PORT	F OF DAVAO (200KVA)	
4	•	Standby Power Rating: 200KVA/160 KW	
	•	Rated AC Voltage: 230V	
	•	Frequency: 60Hz	
	•	Rated Speed: 1800rpm	
	•	Power Factors: 0.8	
	•	Phases: Three Phase	
	•	Type: Silent Type	
	•	Engine Type: Diesel Fuel	
	•	Noise Level: 75-85 db @ 1m	
	•	Fuel System: Manufacturer Standard	
	•	Electrical System: Manufacturer's Standard	
	•	Digital Controller:	
		Over & Under Speed	
		Low Oil Pressure	
		Under/Over Generator Voltage	
		Low & High Battery Voltage	
		Emergency Stop	
		> Over Current	
		High Engine Temperature	
		Start/Stop Failure	
		> Charge Fail	
	•	Other Accessories:	
		Set-mounted tropical radiator	
		 Set-mounted circuit breaker Skid-base diesel tank 	
		 Digital generator set controller with meter and 	
		alert	
		Free maintenance type battery	
	Autor	natic Transfer Switch (ATS)	
	Auton	Ampere Rating: 500 Amps	
	•	Voltage Rating: 230 Volts	
	•	Ampere Frame: 600AF	
	•	Interrupting Capacity: 44KAIC	
	•	Phase: Three Phase	
	•	Enclosure: Nema – 1	
	•	Accessories:	
	•		
		 Phase Voltage Digital Meter (3 Phase) Phase Current Digital Meter (3 Phase) 	
		 Phase Current Digital Meter (5 Phase) Normal and Emergency Signal/Indicator 	
	Instal	lation, Testing and Commissioning	
	I.	Mobilization	
	•		

 The mobilization of the project shall consist of the following: a. Preparation of logistics of contractor's equipment b. Setting up of temporary facilities within the site II. Electrical Works a. Walk around, Visual inspection, Gather data, and information; b. Securing and processing of necessary permits and licenses for the permissible operation of generator set (Mechanical permit from respective LGU); c. Marking and Positioning of Generator and Automatic Transfer Switch (ATS); d. Site coordination for power interruption during transfer of normal to emergency; e. Coordination to Electric Cooperative for temporary shutdown; f. Supply and Installation of new Generator with accessories and ATS; g. Supply and Installation of wiring system from Generator to ATS and from ATS to existing electrical main panelboard shall be overhead installation; h. Termination of existing cable wires to delivered new Generator and ATS; i. Installation of control wiring from ATS to Generator panel; j. Installation of three phase shall be in correct phase squence to supply the power from emergency generator for the future electrical system arrangement; k. Load balancing shall be done for all three-phase supply; i. If any has been omitted for any items of work or materials usually furnished, which are necessary for the completion of entire work as outlined herein before, then such items must be and hereby included to complete the standard installation; m. Conduct continuity test and insulation resistance test for installed feeder line and to submit test reports. a. All synch controllers and generators must be set to automatic mode; b. Supply of the lof Generator for testing (1/4 of fuel tank capacity): 		
 a. Preparation of logistics of contractor's equipment b. Setting up of temporary facilities within the site II. Electrical Works a. Walk around, Visual inspection, Gather data, and information; b. Securing and processing of necessary permits and licenses for the permissible operation of generator set (Mechanical permit from respective LGU); c. Marking and Positioning of Generator and Automatic Transfer Switch (ATS); d. Site coordination for power interruption during transfer of normal to emergency; e. Coordination to Electric Cooperative for temporary shutdown; f. Supply and Installation of wiring system from Generator to ATS and from ATS to existing electrical main panelboard shall be overhead installation; b. Termination of existing cable wires to delivered new Generator and ATS; i. Installation of control wiring from ATS to Generator panel; j. Installation of three phase shall be in correct phase sequence to supply the power from emergency generator for the future electrical system arrangement; k. Load balancing shall be done for all three-phase sequence; i. If any has been omitted for any items of work or materials usually furnished, which are necessary for the completion of entire work as outlined herein before, then such items must be and hereipy included to complete the standard installation; m. Conduct continuity test and insulation resistance test for installed feeder line and to submit test reports. 		The mobilization of the project shall consist of the following:
 b. Setting up of temporary facilities within the site II. Electrical Works a. Walk around, Visual inspection, Gather data, and information; b. Securing and processing of necessary permits and licenses for the permissible operation of generator set (Mechanical permit from respective LGU); c. Marking and Positioning of Generator and Automatic Transfer Switch (ATS); d. Site coordination for power interruption during transfer of normal to emergency; e. Coordination to Electric Cooperative for temporary shutdown; f. Supply and Installation of new Generator with accessories and ATS; g. Supply and Installation of wiring system from Generator to ATS and from ATS to existing electrical main panelboard shall be overhead installation; h. Termination of existing cable wires to delivered new Generator and ATS; i. Installation of control wiring from ATS to Generator panel; j. Installation of the phase shall be in correct phase sequence to supply the power from emergency generator for the future electrical system arrangement; k. Load balancing shall be done for all three-phase supply; l. If any has been omitted for any items of work or materials usually furnished, which are necessary for the completion of entire work as outlined herein before, then such items must be and hereby included to complete the standard installation; m. Conduct continuity test and insulation resistance test for installed feeder line and to submit test reports. 		a. Preparation of logistics of contractor's
 site II. Electrical Works a. Walk around, Visual inspection, Gather data, and information; b. Securing and processing of necessary permits and licenses for the permissible operation of generator set (Mechanical permit from respective LGU); c. Marking and Positioning of Generator and Automatic Transfer Switch (ATS); d. Site coordination for power interruption during transfer of normal to emergency; e. Coordination to Electric Cooperative for temporary shutdown; f. Supply and Installation of new Generator with accessories and ATS; g. Supply and Installation of wring system from Generator to ATS and from ATS to existing electrical main panelboard shall be overhead installation; h. Termination of existing cable wires to delivered new Generator and ATS; i. Installation of control wiring from ATS to Generator panel; j. Installation of cortrol wiring from ATS to Generator panel; j. Installation of the future electrical system arrangement; k. Load balancing shall be done for all three-phase supply; l. If any has been omitted for any items of work or materials usually furnished, which are necessary for the completion of entire work as outlined herein before, then such items must be and hereiby included to complete the standard installation; m. Conduct continuity test and insulation resistance test for installed feeder line and to submit test reports. a. All synch controllers and generators must be set to automatic mode; o. Supply of fuel of Generator for testing (1/4 of 		
 a. Walk around, Visual inspection, Gather data, and information; b. Securing and processing of necessary permits and licenses for the permissible operation of generator set (Mechanical permit from respective LGU); c. Marking and Positioning of Generator and Automatic Transfer Switch (ATS); d. Site coordination for power interruption during transfer of normal to emergency; e. Coordination to Electric Cooperative for temporary shutdown; f. Supply and Installation of new Generator with accessories and ATS; g. Supply and Installation of wiring system from Generator to ATS and from ATS to existing electrical main panelboard shall be overhead installation; h. Termination of existing cable wires to delivered new Generator and ATS; i. Installation of control wiring from ATS to Generator panel; j. Installation of the phase shall be in correct phase sequence to supply the power from emergency generator for the future electrical system arrangement; k. Load balancing shall be done for all three-phase supply; l. If any has been omitted for any items of work or materials usually furnished, which are necessary for the completion of entire work as outlined herein before, then such items must be and hereby included to complete the standard installation; m. Conduct continuity test and insulation resistance test for installed feeder line and to submit test reports. a. All synch controllers and generators must be set to automatic mode; o. Supply of fuel of Generator for testing (1/4 of 		
 a. Walk around, Visual inspection, Gather data, and information; b. Securing and processing of necessary permits and licenses for the permissible operation of generator set (Mechanical permit from respective LGU); c. Marking and Positioning of Generator and Automatic Transfer Switch (ATS); d. Site coordination for power interruption during transfer of normal to emergency; e. Coordination to Electric Cooperative for temporary shutdown; f. Supply and Installation of new Generator with accessories and ATS; g. Supply and Installation of wiring system from Generator to ATS and from ATS to existing electrical main panelboard shall be overhead installation; h. Termination of existing cable wires to delivered new Generator and ATS; i. Installation of control wiring from ATS to Generator panel; j. Installation of the phase shall be in correct phase sequence to supply the power from emergency generator for the future electrical system arrangement; k. Load balancing shall be done for all three-phase supply; l. If any has been omitted for any items of work or materials usually furnished, which are necessary for the completion of entire work as outlined herein before, then such items must be and hereby included to complete the standard installation; m. Conduct continuity test and insulation resistance test for installed feeder line and to submit test reports. a. All synch controllers and generators must be set to automatic mode; o. Supply of fuel of Generator for testing (1/4 of 	Ц	Electrical Works
 b. Securing and processing of necessary permits and licenses for the permissible operation of generator set (Mechanical permit from respective LGU); c. Marking and Positioning of Generator and Automatic Transfer Switch (ATS); d. Site coordination for power interruption during transfer of normal to emergency; e. Coordination to Electric Cooperative for temporary shutdown; f. Supply and Installation of new Generator with accessories and ATS; g. Supply and Installation of viring system from Generator to ATS and from ATS to existing electrical main panelboard shall be overhead installation. Color Coded (RYB) THHN wire in IMC conduit pipe shall be used for installation; h. Termination of existing cable wires to delivered new Generator and ATS; i. Installation of ontrol wiring from ATS to Generator panel; j. Installation of three phase shall be in correct phase sequence to supply the power from emergency generator for the future electrical system arrangement; k. Load balancing shall be done for all three-phase supply; l. If any has been omitted for any items of work or materials usually furnished, which are necessary for the completion of entire work as outlined herein before, then such items must be and hereiny included to complete the standard installation; m. Conduct continuity test and insulation resistance test for installed feeder line and to submit test reports. n. All synch controllers and generators must be set to automatic mode; o. Supply of fuel of Generator for testing (1/4 of 		a. Walk around, Visual inspection, Gather data,
 and licenses for the permissible operation of generator set (Mechanical permit from respective LGU); c. Marking and Positioning of Generator and Automatic Transfer Switch (ATS); d. Site coordination for power interruption during transfer of normal to emergency; e. Coordination to Electric Cooperative for temporary shutdown; f. Supply and Installation of new Generator with accessories and ATS; g. Supply and Installation of wiring system from Generator to ATS and from ATS to existing electrical main panelboard shall be overhead installation. Color Coded (RYB) THHN wire in IMC conduit pipe shall be used for installation. h. Termination of existing cable wires to delivered new Generator and ATS; i. Installation of control wiring from ATS to Generator panel; j. Installation of three phase shall be in correct phase sequence to supply the power from emergency generator for the future electrical system arrangement; k. Load balancing shall be done for all three-phase supply; l. If any has been omitted for any items of work or materials usually furnished, which are necessary for the completion of entire work as outlined herein before, then such items must be and hereby included to complete the standard installation; m. Conduct continuity test and insulation resistance test for installed feeder line and to submit test reports. n. All synch controllers and generators must be set to automatic mode; o. Supply of fuel of Generator for testing (1/4 of 		
 generator set (Mechanical permit from respective LGU); c. Marking and Positioning of Generator and Automatic Transfer Switch (ATS); d. Site coordination for power interruption during transfer of normal to emergency; e. Coordination to Electric Cooperative for temporary shutdown; f. Supply and Installation of new Generator with accessories and ATS; g. Supply and Installation of wiring system from Generator to ATS and from ATS to existing electrical main panelboard shall be overhead installation; h. Termination of existing cable wires to delivered new Generator and ATS; i. Installation of control wiring from ATS to Generator panel; j. Installation of three phase shall be in correct phase sequence to supply the power from emergency generator for the future electrical system arrangement; k. Load balancing shall be done for all three-phase supply; l. If any has been omitted for any items of work or materials usually furnished, which are necessary for the completion of entire work as outlined herein before, then such items must be and hereby included to complete the standard installation; m. Conduct continuity test and insulation resistance test for installed feeder line and to submit test reports. n. All synch controllers and generators must be set to automatic mode; o. Supply of fuel of Generator for testing (1/4 of 		
 c. Marking and Positioning of Generator and Automatic Transfer Switch (ATS); d. Site coordination for power interruption during transfer of normal to emergency; e. Coordination to Electric Cooperative for temporary shutdown; f. Supply and Installation of new Generator with accessories and ATS; g. Supply and Installation of wiring system from Generator to ATS and from ATS to existing electrical main panelboard shall be overhead installation. Color Coded (RYB) THHN wire in IMC conduit pipe shall be used for installation; h. Termination of existing cable wires to delivered new Generator and ATS; i. Installation of control wiring from ATS to Generator panel; j. Installation of three phase shall be in correct phase sequence to supply the power from emergency generator for the future electrical system arrangement; k. Load balancing shall be done for all three-phase supply; l. If any has been omitted for any items of work or materials usually furnished, which are necessary for the completion of entire work as outlined herein before, then such items must be and hereby included to complete the standard installation; m. Conduct continuity test and insulation resistance test for installed feeder line and to submit test reports. n. All synch controllers and generators must be set to automatic mode; o. Supply of fuel of Generator for testing (1/4 of 		generator set (Mechanical permit from
 Automatic Transfer Switch (ATS); d. Site coordination for power interruption during transfer of normal to emergency; e. Coordination to Electric Cooperative for temporary shutdown; f. Supply and Installation of new Generator with accessories and ATS; g. Supply and Installation of wiring system from Generator to ATS and from ATS to existing electrical main panelboard shall be overhead installation. Color Coded (RYB) THHN wire in IMC conduit pipe shall be used for installation; h. Termination of existing cable wires to delivered new Generator and ATS; i. Installation of control wiring from ATS to Generator panel; j. Installation of three phase shall be in correct phase sequence to supply the power from emergency generator for the future electrical system arrangement; k. Load balancing shall be done for all three-phase supply; l. If any has been omitted for any items of work or materials usually furnished, which are necessary for the completion of entire work as outlined herein before, then such items must be and hereby included to complete the standard installation; m. Conduct continuity test and insulation resistance test for installed feeder line and to submit test reports. n. All synch controllers and generators must be set to automatic mode; o. Supply of fuel of Generator for testing (1/4 of 		•
 d. Site coordination for power interruption during transfer of normal to emergency; e. Coordination to Electric Cooperative for temporary shutdown; f. Supply and Installation of new Generator with accessories and ATS; g. Supply and Installation of wiring system from Generator to ATS and from ATS to existing electrical main panelboard shall be overhead installation. Color Coded (RYB) THHN wire in IMC conduit pipe shall be used for installation; h. Termination of existing cable wires to delivered new Generator and ATS; i. Installation of control wiring from ATS to Generator panel; j. Installation of three phase shall be in correct phase sequence to supply the power from emergency generator for the future electrical system arrangement; k. Load balancing shall be done for all three-phase supply; l. If any has been omitted for any items of work or materials usually furnished, which are necessary for the completion of entire work as outlined herein before, then such items must be and hereby included to complete the standard installation; m. Conduct continuity test and insulation resistance test for installed feeder line and to submit test reports. n. All synch controllers and generators must be set to automatic mode; o. Supply of fuel of Generator for testing (1/4 of 		
 transfer of normal to emergency; e. Coordination to Electric Cooperative for temporary shutdown; f. Supply and Installation of new Generator with accessories and ATS; g. Supply and Installation of wiring system from Generator to ATS and from ATS to existing electrical main panelboard shall be overhead installation. Color Coded (RYB) THHN wire in IMC conduit pipe shall be used for installation; h. Termination of existing cable wires to delivered new Generator and ATS; i. Installation of control wiring from ATS to Generator panel; j. Installation of three phase shall be in correct phase sequence to supply the power from emergency generator for the future electrical system arrangement; k. Load balancing shall be done for all three-phase supply; l. If any has been omitted for any items of work or materials usually furnished, which are necessary for the completion of entire work as outlined herein before, then such items must be and hereby included to complete the standard installation; m. Conduct continuity test and insulation resistance test for installed feeder line and to submit test reports. n. All synch controllers and generators must be set to automatic mode; o. Supply of fuel of Generator for testing (1/4 of 		
 e. Coordination to Electric Cooperative for temporary shutdown; f. Supply and Installation of new Generator with accessories and ATS; g. Supply and Installation of wiring system from Generator to ATS and from ATS to existing electrical main panelboard shall be overhead installation. Color Coded (RYB) THHN wire in IMC conduit pipe shall be used for installation; h. Termination of existing cable wires to delivered new Generator and ATS; i. Installation of control wiring from ATS to Generator panel; j. Installation of three phase shall be in correct phase sequence to supply the power from emergency generator for the future electrical system arrangement; k. Load balancing shall be done for all three-phase supply; l. If any has been omitted for any items of work or materials usually furnished, which are necessary for the completion of entire work as outlined herein before, then such items must be and hereby included to complete the standard installation; m. Conduct continuity test and insulation resistance test for installed feeder line and to submit test reports. n. All synch controllers and generators must be set to automatic mode; o. Supply of fuel of Generator for testing (1/4 of 		
 temporary shutdown; f. Supply and Installation of new Generator with accessories and ATS; g. Supply and Installation of wiring system from Generator to ATS and from ATS to existing electrical main panelboard shall be overhead installation. Color Coded (RYB) THHN wire in IMC conduit pipe shall be used for installation; h. Termination of existing cable wires to delivered new Generator and ATS; i. Installation of control wiring from ATS to Generator panel; j. Installation of three phase shall be in correct phase sequence to supply the power from emergency generator for the future electrical system arrangement; k. Load balancing shall be done for all three-phase supply; l. If any has been omitted for any items of work or materials usually furnished, which are necessary for the completion of entire work as outlined herein before, then such items must be and hereby included to complete the standard installation; m. Conduct continuity test and insulation resistance test for installed feeder line and to submit test reports. n. All synch controllers and generators must be set to automatic mode; o. Supply of fuel of Generator for testing (1/4 of 		
 f. Supply and Installation of new Generator with accessories and ATS; g. Supply and Installation of wiring system from Generator to ATS and from ATS to existing electrical main panelboard shall be overhead installation. Color Coded (RYB) THHN wire in IMC conduit pipe shall be used for installation; h. Termination of existing cable wires to delivered new Generator and ATS; i. Installation of control wiring from ATS to Generator panel; j. Installation of three phase shall be in correct phase sequence to supply the power from emergency generator for the future electrical system arrangement; k. Load balancing shall be done for all three-phase supply; l. If any has been omitted for any items of work or materials usually furnished, which are necessary for the completion of entire work as outlined herein before, then such items must be and hereby included to complete the standard installation; m. Conduct continuity test and insulation resistance test for installed feeder line and to submit test reports. n. All synch controllers and generators must be set to automatic mode; o. Supply of fuel of Generator for testing (1/4 of 		-
 g. Supply and Installation of wiring system from Generator to ATS and from ATS to existing electrical main panelboard shall be overhead installation. Color Coded (RYB) THHN wire in IMC conduit pipe shall be used for installation; h. Termination of existing cable wires to delivered new Generator and ATS; i. Installation of control wiring from ATS to Generator panel; j. Installation of three phase shall be in correct phase sequence to supply the power from emergency generator for the future electrical system arrangement; k. Load balancing shall be done for all three- phase supply; l. If any has been omitted for any items of work or materials usually furnished, which are necessary for the completion of entire work as outlined herein before, then such items must be and hereby included to complete the standard installation; m. Conduct continuity test and insulation resistance test for installed feeder line and to submit test reports. n. All synch controllers and generators must be set to automatic mode; o. Supply of fuel of Generator for testing (1/4 of 		
 Generator to ATS and from ATS to existing electrical main panelboard shall be overhead installation. Color Coded (RYB) THHN wire in IMC conduit pipe shall be used for installation; h. Termination of existing cable wires to delivered new Generator and ATS; i. Installation of control wiring from ATS to Generator panel; j. Installation of three phase shall be in correct phase sequence to supply the power from emergency generator for the future electrical system arrangement; k. Load balancing shall be done for all three-phase supply; l. If any has been omitted for any items of work or materials usually furnished, which are necessary for the completion of entire work as outlined herein before, then such items must be and hereby included to complete the standard installation; m. Conduct continuity test and insulation resistance test for installed feeder line and to submit test reports. n. All synch controllers and generators must be set to automatic mode; o. Supply of fuel of Generator for testing (1/4 of 		accessories and ATS;
 electrical main panelboard shall be overhead installation. Color Coded (RYB) THHN wire in IMC conduit pipe shall be used for installation; h. Termination of existing cable wires to delivered new Generator and ATS; i. Installation of control wiring from ATS to Generator panel; j. Installation of three phase shall be in correct phase sequence to supply the power from emergency generator for the future electrical system arrangement; k. Load balancing shall be done for all three-phase supply; l. If any has been omitted for any items of work or materials usually furnished, which are necessary for the completion of entire work as outlined herein before, then such items must be and hereby included to complete the standard installation; m. Conduct continuity test and insulation resistance test for installed feeder line and to submit test reports. n. All synch controllers and generators must be set to automatic mode; o. Supply of fuel of Generator for testing (1/4 of 		
 installation. Color Coded (RYB) THHN wire in IMC conduit pipe shall be used for installation; h. Termination of existing cable wires to delivered new Generator and ATS; i. Installation of control wiring from ATS to Generator panel; j. Installation of three phase shall be in correct phase sequence to supply the power from emergency generator for the future electrical system arrangement; k. Load balancing shall be done for all three- phase supply; l. If any has been omitted for any items of work or materials usually furnished, which are necessary for the completion of entire work as outlined herein before, then such items must be and hereby included to complete the standard installation; m. Conduct continuity test and insulation resistance test for installed feeder line and to submit test reports. n. All synch controllers and generators must be set to automatic mode; o. Supply of fuel of Generator for testing (1/4 of 		0
 in IMC conduit pipe shall be used for installation; h. Termination of existing cable wires to delivered new Generator and ATS; i. Installation of control wiring from ATS to Generator panel; j. Installation of three phase shall be in correct phase sequence to supply the power from emergency generator for the future electrical system arrangement; k. Load balancing shall be done for all three-phase supply; l. If any has been omitted for any items of work or materials usually furnished, which are necessary for the completion of entire work as outlined herein before, then such items must be and hereby included to complete the standard installation; m. Conduct continuity test and insulation resistance test for installed feeder line and to submit test reports. n. All synch controllers and generators must be set to automatic mode; o. Supply of fuel of Generator for testing (1/4 of 		
 installation; h. Termination of existing cable wires to delivered new Generator and ATS; i. Installation of control wiring from ATS to Generator panel; j. Installation of three phase shall be in correct phase sequence to supply the power from emergency generator for the future electrical system arrangement; k. Load balancing shall be done for all three-phase supply; l. If any has been omitted for any items of work or materials usually furnished, which are necessary for the completion of entire work as outlined herein before, then such items must be and hereby included to complete the standard installation; m. Conduct continuity test and insulation resistance test for installed feeder line and to submit test reports. n. All synch controllers and generators must be set to automatic mode; o. Supply of fuel of Generator for testing (1/4 of 		
 h. Termination of existing cable wires to delivered new Generator and ATS; i. Installation of control wiring from ATS to Generator panel; j. Installation of three phase shall be in correct phase sequence to supply the power from emergency generator for the future electrical system arrangement; k. Load balancing shall be done for all three-phase supply; l. If any has been omitted for any items of work or materials usually furnished, which are necessary for the completion of entire work as outlined herein before, then such items must be and hereby included to complete the standard installation; m. Conduct continuity test and insulation resistance test for installed feeder line and to submit test reports. n. All synch controllers and generators must be set to automatic mode; o. Supply of fuel of Generator for testing (1/4 of 		••
 i. Installation of control wiring from ATS to Generator panel; j. Installation of three phase shall be in correct phase sequence to supply the power from emergency generator for the future electrical system arrangement; k. Load balancing shall be done for all three- phase supply; l. If any has been omitted for any items of work or materials usually furnished, which are necessary for the completion of entire work as outlined herein before, then such items must be and hereby included to complete the standard installation; m. Conduct continuity test and insulation resistance test for installed feeder line and to submit test reports. n. All synch controllers and generators must be set to automatic mode; o. Supply of fuel of Generator for testing (1/4 of 		h. Termination of existing cable wires to
 Generator panel; j. Installation of three phase shall be in correct phase sequence to supply the power from emergency generator for the future electrical system arrangement; k. Load balancing shall be done for all three-phase supply; l. If any has been omitted for any items of work or materials usually furnished, which are necessary for the completion of entire work as outlined herein before, then such items must be and hereby included to complete the standard installation; m. Conduct continuity test and insulation resistance test for installed feeder line and to submit test reports. n. All synch controllers and generators must be set to automatic mode; o. Supply of fuel of Generator for testing (1/4 of 		
 phase sequence to supply the power from emergency generator for the future electrical system arrangement; k. Load balancing shall be done for all three-phase supply; l. If any has been omitted for any items of work or materials usually furnished, which are necessary for the completion of entire work as outlined herein before, then such items must be and hereby included to complete the standard installation; m. Conduct continuity test and insulation resistance test for installed feeder line and to submit test reports. n. All synch controllers and generators must be set to automatic mode; o. Supply of fuel of Generator for testing (1/4 of 		
 emergency generator for the future electrical system arrangement; k. Load balancing shall be done for all three-phase supply; l. If any has been omitted for any items of work or materials usually furnished, which are necessary for the completion of entire work as outlined herein before, then such items must be and hereby included to complete the standard installation; m. Conduct continuity test and insulation resistance test for installed feeder line and to submit test reports. n. All synch controllers and generators must be set to automatic mode; o. Supply of fuel of Generator for testing (1/4 of 		
 system arrangement; k. Load balancing shall be done for all three-phase supply; l. If any has been omitted for any items of work or materials usually furnished, which are necessary for the completion of entire work as outlined herein before, then such items must be and hereby included to complete the standard installation; m. Conduct continuity test and insulation resistance test for installed feeder line and to submit test reports. n. All synch controllers and generators must be set to automatic mode; o. Supply of fuel of Generator for testing (1/4 of 		
 k. Load balancing shall be done for all three-phase supply; l. If any has been omitted for any items of work or materials usually furnished, which are necessary for the completion of entire work as outlined herein before, then such items must be and hereby included to complete the standard installation; m. Conduct continuity test and insulation resistance test for installed feeder line and to submit test reports. n. All synch controllers and generators must be set to automatic mode; o. Supply of fuel of Generator for testing (1/4 of 		
 phase supply; If any has been omitted for any items of work or materials usually furnished, which are necessary for the completion of entire work as outlined herein before, then such items must be and hereby included to complete the standard installation; m. Conduct continuity test and insulation resistance test for installed feeder line and to submit test reports. n. All synch controllers and generators must be set to automatic mode; o. Supply of fuel of Generator for testing (1/4 of 		
 If any has been omitted for any items of work or materials usually furnished, which are necessary for the completion of entire work as outlined herein before, then such items must be and hereby included to complete the standard installation; m. Conduct continuity test and insulation resistance test for installed feeder line and to submit test reports. n. All synch controllers and generators must be set to automatic mode; o. Supply of fuel of Generator for testing (1/4 of 		•
 necessary for the completion of entire work as outlined herein before, then such items must be and hereby included to complete the standard installation; m. Conduct continuity test and insulation resistance test for installed feeder line and to submit test reports. n. All synch controllers and generators must be set to automatic mode; o. Supply of fuel of Generator for testing (1/4 of 		
 outlined herein before, then such items must be and hereby included to complete the standard installation; m. Conduct continuity test and insulation resistance test for installed feeder line and to submit test reports. n. All synch controllers and generators must be set to automatic mode; o. Supply of fuel of Generator for testing (1/4 of 		•
 be and hereby included to complete the standard installation; m. Conduct continuity test and insulation resistance test for installed feeder line and to submit test reports. n. All synch controllers and generators must be set to automatic mode; o. Supply of fuel of Generator for testing (1/4 of 		
standard installation; m. Conduct continuity test and insulation resistance test for installed feeder line and to submit test reports. n. All synch controllers and generators must be set to automatic mode; o. Supply of fuel of Generator for testing (1/4 of		
 m. Conduct continuity test and insulation resistance test for installed feeder line and to submit test reports. n. All synch controllers and generators must be set to automatic mode; o. Supply of fuel of Generator for testing (1/4 of 		•
 resistance test for installed feeder line and to submit test reports. n. All synch controllers and generators must be set to automatic mode; o. Supply of fuel of Generator for testing (1/4 of 		,
 submit test reports. n. All synch controllers and generators must be set to automatic mode; o. Supply of fuel of Generator for testing (1/4 of 		
set to automatic mode; o. Supply of fuel of Generator for testing (1/4 of		
o. Supply of fuel of Generator for testing (1/4 of		
tuel tank capacity);		
		tuel tank capacity);

	p. Simulate operation of the ATS transfer from
	normal to emergency power;
	q. Testing and commissioning of new Generator
	and ATS with load;
	r. Return operation of the ATS emergency power to normal power
	s. Double check genset controller, synch
	controller, and ATS controller if it's in auto
	mode before demobilized;
	t. Submission of test reports (continuity and
	insulation resistance test) and service report;
	u. Submission of certificate of completion;v. Submission of signed and sealed as-built plan of
	electrical power distribution system to GSD
	after completion of project and final
	acceptance;
	III. Civil Works
	a. Construction of concrete pad (30cm from the highest elevated area) as per new Generator
	requirements;
	IV. Construction of Genset and Automatic Transfer
	Switch (ATS) enclosed shed.
	V. Demobilization
	a. Sites clean up;
	b. Removal and hauling of tools and equipment
	from project site;
•	PORT OF CAGAYAN DE ORO (Sub-Port of Tagoloan) (200KVA)
2	Standby Power Rating: 200KVA/160 KW
	Rated AC Voltage: 230V
	• Frequency: 60Hz
	Rated Speed: 1800rpm
	Power Factors: 0.8
	Phases: Three Phase
	• Type: Silent Type
	Engine Type: Diesel Fuel
	• Noise Level: 75-85 db @ 1m
	Fuel System: Manufacturer Standard
	Electrical System: Manufacturer's Standard Digital Controllogy
	 Digital Controller: > Over & Under Speed
	 Low Oil Pressure
	 Under/Over Generator Voltage
	Low & High Battery Voltage
	Emergency Stop
	Over Current

 High Engine Temperature Start/Stop Failure Charge Fail Other Accessories: Set-mounted tropical radiator Set-mounted circuit breaker Skid-base diesel tank Digital generator set controller with meter and alert Free maintenance type battery Automatic Transfer Switch (ATS) Ampere Rating: 500 Amps Voltage Rating: 230 Volts Ampere Frame: 600AF Interrupting Capacity: 44KAIC Phase: Three Phase Enclosure: Nema – 1 Accessories: 	
 Charge Fail Other Accessories: Set-mounted tropical radiator Set-mounted circuit breaker Skid-base diesel tank Digital generator set controller with meter and alert Free maintenance type battery Automatic Transfer Switch (ATS) Ampere Rating: 500 Amps Voltage Rating: 230 Volts Ampere Frame: 600AF Interrupting Capacity: 44KAIC Phase: Three Phase Enclosure: Nema – 1 	
 Other Accessories: Set-mounted tropical radiator Set-mounted circuit breaker Skid-base diesel tank Digital generator set controller with meter and alert Free maintenance type battery Automatic Transfer Switch (ATS) Ampere Rating: 500 Amps Voltage Rating: 230 Volts Ampere Frame: 600AF Interrupting Capacity: 44KAIC Phase: Three Phase Enclosure: Nema – 1 	
 Set-mounted tropical radiator Set-mounted circuit breaker Skid-base diesel tank Digital generator set controller with meter and alert Free maintenance type battery Automatic Transfer Switch (ATS) Ampere Rating: 500 Amps Voltage Rating: 230 Volts Ampere Frame: 600AF Interrupting Capacity: 44KAIC Phase: Three Phase Enclosure: Nema – 1 	
 Set-mounted circuit breaker Skid-base diesel tank Digital generator set controller with meter and alert Free maintenance type battery Automatic Transfer Switch (ATS) Ampere Rating: 500 Amps Voltage Rating: 230 Volts Ampere Frame: 600AF Interrupting Capacity: 44KAIC Phase: Three Phase Enclosure: Nema – 1 	
 Skid-base diesel tank Digital generator set controller with meter and alert Free maintenance type battery Automatic Transfer Switch (ATS) Ampere Rating: 500 Amps Voltage Rating: 230 Volts Ampere Frame: 600AF Interrupting Capacity: 44KAIC Phase: Three Phase Enclosure: Nema – 1 	
 Digital generator set controller with meter and alert Free maintenance type battery Automatic Transfer Switch (ATS) Ampere Rating: 500 Amps Voltage Rating: 230 Volts Ampere Frame: 600AF Interrupting Capacity: 44KAIC Phase: Three Phase Enclosure: Nema – 1 	
alert > > Free maintenance type battery Automatic Transfer Switch (ATS) • Ampere Rating: 500 Amps • Voltage Rating: 230 Volts • Ampere Frame: 600AF • Interrupting Capacity: 44KAIC • Phase: Three Phase • Enclosure: Nema – 1	
alert > > Free maintenance type battery Automatic Transfer Switch (ATS) • Ampere Rating: 500 Amps • Voltage Rating: 230 Volts • Ampere Frame: 600AF • Interrupting Capacity: 44KAIC • Phase: Three Phase • Enclosure: Nema – 1	
Automatic Transfer Switch (ATS) • Ampere Rating: 500 Amps • Voltage Rating: 230 Volts • Ampere Frame: 600AF • Interrupting Capacity: 44KAIC • Phase: Three Phase • Enclosure: Nema – 1	
Automatic Transfer Switch (ATS) • Ampere Rating: 500 Amps • Voltage Rating: 230 Volts • Ampere Frame: 600AF • Interrupting Capacity: 44KAIC • Phase: Three Phase • Enclosure: Nema – 1	
 Ampere Rating: 500 Amps Voltage Rating: 230 Volts Ampere Frame: 600AF Interrupting Capacity: 44KAIC Phase: Three Phase Enclosure: Nema – 1 	
 Voltage Rating: 230 Volts Ampere Frame: 600AF Interrupting Capacity: 44KAIC Phase: Three Phase Enclosure: Nema – 1 	
Ampere Frame: 600AF Interrupting Capacity: 44KAIC Phase: Three Phase Enclosure: Nema – 1	
 Interrupting Capacity: 44KAIC Phase: Three Phase Enclosure: Nema – 1 	
 Phase: Three Phase Enclosure: Nema – 1 	
• Enclosure: Nema – 1	
	1
 Phase Voltage Digital Meter (3 Phase) Phase Current Digital Meter (3 Phase) 	
e e e	
 Normal and Emergency Signal/Indicator Installation, Testing and Commissioning 	
Instanation, resting and Commissioning	
I. Mobilization	
The mobilization of the project shall consist of the	
following:	
a. Preparation of logistics of contractor's	
equipment	
b. Setting up of temporary facilities within the site	
II. Electrical Works	
a. Walk around, Visual inspection, Gather data,	
and information;	
a. Securing and processing of necessary	
permits and licenses for the permissible	
operation of generator set (Mechanical permit	
from respective LGU);	
b. Marking and Positioning of Generator and	
Automatic Transfer Switch (ATS);	
c. Site coordination for power interruption during	
transfer of normal to emergency;	
d. Coordination to Electric Cooperative for	
temporary shutdown;	
e. Supply and Installation of new Generator with	
accessories and ATS.	
f. Supply and Installation of wiring system from	
Generator to ATS and from ATS to existing	
electrical main panelboard shall be overhead	
installation. Color Coded (RYB) THHN wire	
in IMC conduit pipe shall be used for	
installation;	

 r		
	g. Termination of existing cable wires to	
	delivered new Generator and ATS;	
	h. Installation of control wiring from ATS to	
	Generator panel; i. Installation of three phase shall be in correct	
	phase sequence to supply the power from	
	emergency generator for the future electrical	
	system arrangement;	
	j. Load balancing shall be done for all three-	
	phase supply;	
	k. If any has been omitted for any items of work	
	or materials usually furnished, which are	
	necessary for the completion of entire work as	
	outlined herein before, then such items must	
	be and hereby included to complete the	
	standard installation; 1. Conduct continuity test and insulation	
	resistance test for installed feeder line and to	
	submit test reports.	
	m. All synch controllers and generators must be	
	set to automatic mode;	
	b. Supply of fuel in Generator for testing (1/4 of	
	fuel tank capacity);	
	n. Simulate operation of the ATS transfer from	
	normal to emergency power;	
	o. Testing and commissioning of new Generator	
	and ATS with load;	
	p. Return operation of the ATS emergency power	
	to normal power	
	q. Double check genset controller, synch	
	controller, and ATS controller if it's in auto mode before demobilized;	
	r. Submission of test reports (continuity and	
	insulation resistance test) and service report;	
	s. Submission of certificate of completion;	
	t. Submission of signed and sealed as-built plan of	
	electrical power distribution system to GSD	
	after completion of project and final	
	acceptance;	
III.	Civil Works	
	a. Construction of elevated concrete (30cm from	
	the highest elevated area) pad as per new	
	Generator requirements;	
IV.	Demobilization	
	a. Sites clean up;	
	b. Removal and hauling of tools and equipment	
	from project site	

Code and S	standards	
a.	PEC – Philippine Electrical Code	
b.	NFPA 110 Standard for Emergency and Standby	
	Power System	
c.	UL 1008 - Standard for Automatic Transfer Switches	
Other Req	urements	
a.	Original Equipment Manufacturer (OEM)	
	Certificate (Engine, Alternator and Controller)	
b. 1	SO Certificate	
c.]	Load Bank Test Result/Certification	
	Operation and Maintenance Manual for Genset and Automatic Transfer Switch	
	Brochure of Generator Set and Automatic Transfer Switch	

I hereby commit to comply and deliver the above requirements.

Name of Company (in print)

Signature of Company Authorized Representative

Name & Designation (in print)

Date

Section VIII. Checklist of Technical and Financial Documents

Checklist of Technical and Financial Documents

I. TECHNICAL COMPONENT ENVELOPE

Class "A" Documents

Legal Documents

(a) Valid PhilGEPS Registration Certificate (Platinum Membership) (all pages) in accordance with Section 8.5.2 of the IRR;

Technical Documents

- (b) Statement of the prospective bidder of all its ongoing government and private contracts, including contracts awarded but not yet started, if any, whether similar or not similar in nature and complexity to the contract to be bid; **and**
- (c) Statement of the bidder's Single Largest Completed Contract (SLCC) similar to the contract to be bid, except under conditions provided for in Sections 23.4.1.3 and 23.4.2.4 of the 2016 revised IRR of RA No. 9184, within the relevant period as provided in the Bidding Documents; **and**
- (d) Original copy of Bid Security. If in the form of a Surety Bond, submit also a certification issued by the Insurance Commission <u>or</u> Original copy of Notarized Bid Securing Declaration; <u>and</u>
- (e) Conformity with the Schedule of Requirements, Technical Specifications, which may include production/delivery schedule, manpower requirements, and/or after-sales/parts, if applicable; **and**
- (f) Original duly signed Omnibus Sworn Statement (OSS) <u>and</u> if applicable, Original Notarized Secretary's Certificate in case of a corporation, partnership, or cooperative; or Original Special Power of Attorney of all members of the joint venture giving full power and authority to its officer to sign the OSS and do acts to represent the Bidder.

Financial Documents

(g) The prospective bidder's computation of Net Financial Contracting Capacity (NFCC) <u>or</u> A committed Line of Credit from a Universal or Commercial Bank in lieu of its NFCC computation.

Class "B" Documents

(h) If applicable, a duly signed joint venture agreement (JVA) in case the joint venture is already in existence <u>or</u> duly notarized statements from all the potential joint venture partners stating that they will enter into and abide by the provisions of the JVA in the instance that the bid is successful.

II. FINANCIAL COMPONENT ENVELOPE

(i) Original of duly signed and accomplished Financial Bid Form; and

(j) Original of duly signed and accomplished Price Schedule(s).

Other documentary requirements under RA No. 9184 (as applicable)

- (k) [For foreign bidders claiming by reason of their country's extension of reciprocal rights to Filipinos] Certification from the relevant government office of their country stating that Filipinos are allowed to participate in government procurement activities for the same item or product.
- (1) Certification from the DTI if the Bidder claims preference as a Domestic Bidder or Domestic Entity.

Date: ______ Invitation to Bid³ N^o: _____

To: [name and address of Procuring Entity]

Gentlemen and/or Ladies:

Having examined the Bidding Documents including Bid Bulletin Numbers [insert numbers], the receipt of which is hereby duly acknowledged, we, the undersigned, offer to the BOC, our services for the project, "Supply, Delivery, Installation, Testing and Commissioning of Standby Generator Sets with Accessories and Automatic Transfer Switch (ATS) at MICP, Port of Cagayan De Oro, Port of Davao and Port of Subic" in conformity with the said Bidding Documents for the sum of [total Bid amount in words and figures] or such other sums as may be ascertained in accordance with the Schedule of Prices attached herewith and made part of this Bid.

LOT	DESCRIPTION	LOCATION	QTY	UNIT COST	TOTAL COST
NO.					
	Supply, Delivery, Installation, Testing and Commissioning of Standby Generator Sets with	Port of Subic	2		
1	Sets withAccessories andAutomaticTransfer Switch(ATS) at MICP,Port of CagayanDe Oro, Port ofDavao and Port ofSubic	Manila International Container Port	1		

We undertake, if our Bid is accepted, to deliver the goods in accordance with the delivery schedule specified in the Schedule of Requirements.

If our Bid is accepted, we undertake to provide a performance security in the form, amounts, and within the times specified in the Bidding Documents.

We agree to abide by this Bid for the Bid Validity Period specified in <u>BDS</u> provision for **ITB** Clause 14.2 and it shall remain binding upon us and may be accepted at any time before the expiration of that period.

Commissions or gratuities, if any, paid or to be paid by us to agents relating to this Bid, and to contract execution if we are awarded the contract, are listed below:⁴

³ If ADB, JICA and WB funded projects, use IFB.

⁴ Applicable only if the Funding Source is the ADB, JICA or WB.

Name and address of agent	Amount and Currency	Purpose of Commission or gratuity
(if none, state "None	")	

Until a formal Contract is prepared and executed, this Bid, together with your written acceptance thereof and your Notice of Award, shall be binding upon us.

We understand that you are not bound to accept the Lowest Calculated Bid or any Bid you may receive.

We certify/confirm that we comply with the eligibility requirements as per **ITB** Clause 10 of the Bidding Documents.

We likewise certify/confirm that the undersigned, [for sole proprietorships, insert: as the owner and sole proprietor or authorized representative of <u>Name of Bidder</u>, has the full power and authority to participate, submit the bid, and to sign and execute the ensuing contract, on the latter's behalf for the <u>Name of Project</u> of the <u>Name of the Procuring Entity</u>] [for partnerships, corporations, cooperatives, or joint ventures, insert: is granted full power and authority by the <u>Name of Bidder</u>, to participate, submit the bid, and to sign and execute the ensuing contract on the latter's behalf for <u>Name of Project</u> of the <u>Name of the Procuring Entity</u>].

We acknowledge that failure to sign each and every page of this Bid Form, including the attached Schedule of Prices, shall be a ground for the rejection of our bid.

Dated this _____ day of _____ 20____.

[signature]

[in the capacity of]

Duly authorized to sign Bid for and on behalf of _____

Date: _____ Invitation to Bid⁵ N°:

To: [name and address of Procuring Entity]

Gentlemen and/or Ladies:

Having examined the Bidding Documents including Bid Bulletin Numbers [insert numbers], the receipt of which is hereby duly acknowledged, we, the undersigned, offer to the BOC, our services for the project, "Supply, Delivery, Installation, Testing and Commissioning of Standby Generator Sets with Accessories and Automatic Transfer Switch (ATS) at MICP, Port of Cagayan De Oro, Port of Davao and Port of Subic" in conformity with the said Bidding Documents for the sum of [total Bid amount in words and figures] or such other sums as may be ascertained in accordance with the Schedule of Prices attached herewith and made part of this Bid.

LOT	DESCRIPTION	LOCATION	QTY	UNIT COST	TOTAL COST
NO.					
2	Supply, Delivery, Installation, Testing and Commissioning of Standby Generator Sets with	Port of Davao	1		
	Accessories and Automatic Transfer Switch (ATS) at MICP, Port of Cagayan De Oro, Port of Davao and Port of Subic	Port of Cagayan De Oro (Sub- Port of Tagoloan)	1		

We undertake, if our Bid is accepted, to deliver the goods in accordance with the delivery schedule specified in the Schedule of Requirements.

If our Bid is accepted, we undertake to provide a performance security in the form, amounts, and within the times specified in the Bidding Documents.

We agree to abide by this Bid for the Bid Validity Period specified in <u>BDS</u> provision for **ITB** Clause 14.2 and it shall remain binding upon us and may be accepted at any time before the expiration of that period.

Commissions or gratuities, if any, paid or to be paid by us to agents relating to this Bid, and to contract execution if we are awarded the contract, are listed below:⁶

⁵ If ADB, JICA and WB funded projects, use IFB.

⁶ Applicable only if the Funding Source is the ADB, JICA or WB.

Name and address of agent	Amount and Currency	Purpose of Commission or gratuity
(if none, state "None	")	

Until a formal Contract is prepared and executed, this Bid, together with your written acceptance thereof and your Notice of Award, shall be binding upon us.

We understand that you are not bound to accept the Lowest Calculated Bid or any Bid you may receive.

We certify/confirm that we comply with the eligibility requirements as per **ITB** Clause 10 of the Bidding Documents.

We likewise certify/confirm that the undersigned, [for sole proprietorships, insert: as the owner and sole proprietor or authorized representative of <u>Name of Bidder</u>, has the full power and authority to participate, submit the bid, and to sign and execute the ensuing contract, on the latter's behalf for the <u>Name of Project</u> of the <u>Name of the Procuring Entity</u>] [for partnerships, corporations, cooperatives, or joint ventures, insert: is granted full power and authority by the <u>Name of Bidder</u>, to participate, submit the bid, and to sign and execute the ensuing contract on the latter's behalf for <u>Name of Project</u> of the <u>Name of the Procuring Entity</u>].

We acknowledge that failure to sign each and every page of this Bid Form, including the attached Schedule of Prices, shall be a ground for the rejection of our bid.

Dated this _____ day of _____ 20____.

[signature]

[in the capacity of]

Duly authorized to sign Bid for and on behalf of _____

Price Schedule for Goods Offered from Within the Philippines

Name	e of Bidder		Project ID No 1					Page	_of
1	2	3	4	5	6	7	8	9	10
Item	Description	Country of origin	Quantity	Unit price EXW per item	Transportation and all other costs incidental to delivery, per item	Sales and other taxes payable if Contract is awarded, per item	Cost of Incidental Services, if applicable, per item	Total Price, per unit (col 5+6+7+8)	Total Price delivered Final Destination (col 9) x (col 4)

For Goods Offered from Within the Philippines

Name: ______
Legal Capacity: ______

Signature: _____

Duly authorized to sign the Bid for and behalf of: _____

Price Schedule for Goods Offered from Abroad

For Goods Offered from Abroad

Name of Bidder _____ Project ID No.____ Page ___ of ____

1	2	3	4	5	6	7	8	9
Item	Description	Country of origin	Quantity	Unit price CIF port of entry (specify port) or CIP named place (specify border point or place of destination)	Total CIF or CIP price per item (col. 4 x 5)	Unit Price Delivered Duty Unpaid (DDU)	Unit price Delivered Duty Paid (DDP)	Total Price delivered DDP (col 4 x 8)

Name:		
Legal Capacity:		

Signature: _____

Duly authorized to sign the Bid for and behalf of: _____

Statement of Single Largest Completed Contract which is similar in nature

Business Name:	
Business Address:_	

Name of Contract (including the name of procuring entity)	Date of the Contract	Kinds of Goods	Amount of Contract	Date of Delivery	End User's Acceptance or Official Receipt(s) Issued for the Contract

Submitted by	:
	(Printed Name & Signature)
Designation	:
Date	:

List of all Ongoing Government & Private Contracts including

Contracts awarded but not yet started

Business Name:	
Business Address:_	

Name of Contract (including the name of procuring entity)	Date of the Contract	Kinds of Goods	Value of Outstanding Contracts	Date of Delivery
<u>Government</u>				
<u>Private</u>				

Submitted by	:
	(Printed Name & Signature)
Designation	:
e	
Date	:

Instructions:

- i. State all ongoing contracts including those awarded but not yet started within five (5) years (government and private contracts, which may be similar or not similar to the project being bidded) prior to opening of bids.
- ii. If there is no ongoing contract including awarded but not yet started as of the aforementioned period, state none or equivalent term.
- iii. The total amount of the ongoing and awarded but not yet started contracts should be consistent with those used in the Net Financial Contracting Capacity (NFCC) in case an NFCC is submitted as an eligibility document

CONTRACT AGREEMENT

THIS AGREEMENT made the _____ day of _____ 20____ between [name of PROCURING ENTITY] of the Philippines (hereinafter called "the Entity") of the one part and [name of Supplier] of [city and country of Supplier] (hereinafter called "the Supplier") of the other part;

WHEREAS, the Entity invited Bids for certain goods and ancillary services, particularly [brief description of goods and services] and has accepted a Bid by the Supplier for the supply of those goods and services in the sum of [contract price in words and figures in specified currency] (hereinafter called "the Contract Price").

NOW THIS AGREEMENT WITNESSETH AS FOLLOWS:

- 1. In this Agreement words and expressions shall have the same meanings as are respectively assigned to them in the Conditions of Contract referred to.
- 2. The following documents as required by the 2016 revised Implementing Rules and Regulations of Republic Act No. 9184 shall be deemed to form and be read and construed as integral part of this Agreement, *viz*.:
 - i. Philippine Bidding Documents (PBDs);
 - i. Schedule of Requirements;
 - ii. Technical Specifications;
 - iii. General and Special Conditions of Contract; and
 - iv. Supplemental or Bid Bulletins, if any
 - ii. Winning bidder's bid, including the Eligibility requirements, Technical and Financial Proposals, and all other documents or statements submitted;

Bid form, including all the documents/statements contained in the Bidder's bidding envelopes, as annexes, and all other documents submitted (*e.g.*, Bidder's response to request for clarifications on the bid), including corrections to the bid, if any, resulting from the Procuring Entity's bid evaluation;

- iii. Performance Security;
- iv. Notice of Award of Contract; and the Bidder's conforme thereto; and
- v. Other contract documents that may be required by existing laws and/or the Procuring Entity concerned in the PBDs. <u>Winning bidder agrees that</u> <u>additional contract documents or information prescribed by the GPPB</u> <u>that are subsequently required for submission after the contract</u> <u>execution, such as the Notice to Proceed, Variation Orders, and</u> <u>Warranty Security, shall likewise form part of the Contract.</u>

- 3. In consideration for the sum of *[total contract price in words and figures]* or such other sums as may be ascertained, *[Named of the bidder]* agrees to *[state the object of the contract]* in accordance with his/her/its Bid.
- 4. The *[Name of the procuring entity]* agrees to pay the above-mentioned sum in accordance with the terms of the Bidding.

IN WITNESS whereof the parties hereto have caused this Agreement to be executed in accordance with the laws of the Republic of the Philippines on the day and year first above written.

[Insert Name and Signature]	[Insert Name and Signature]	
[Insert Signatory's Legal Capacity]	[Insert Signatory's Legal Capacity]	
for:	for:	
[Insert Procuring Entity]	[Insert Name of Supplier]	

Acknowledgment

[Format shall be based on the latest Rules on Notarial Practice

REPUBLIC OF THE PHILIPPINES) CITY/MUNICIPALITY OF _____) S.S.

AFFIDAVIT

I, [Name of Affiant], of legal age, [Civil Status], [Nationality], and residing at [Address of Affiant], after having been duly sworn in accordance with law, do hereby depose and state that:

1. [Select one, delete the other:]

[*If a sole proprietorship:*] I am the sole proprietor or authorized representative of [Name of Bidder] with office address at [address of Bidder];

[*If a partnership, corporation, cooperative, or joint venture:*] I am the duly authorized and designated representative of [Name of Bidder] with office address at [address of Bidder];

2. [Select one, delete the other:]

[*If a sole proprietorship:*] As the owner and sole proprietor, or authorized representative of [Name of Bidder], I have full power and authority to do, execute and perform any and all acts necessary to participate, submit the bid, and to sign and execute the ensuing contract for [Name of the Project] of the [Name of the Procuring Entity], as shown in the attached duly notarized Special Power of Attorney;

[If a partnership, corporation, cooperative, or joint venture:] I am granted full power and authority to do, execute and perform any and all acts necessary to participate, submit the bid, and to sign and execute the ensuing contract for [Name of the Project] of the [Name of the Procuring Entity], as shown in the attached [state title of attached document showing proof of authorization (e.g., duly notarized Secretary's Certificate, Board/Partnership Resolution, or Special Power of Attorney, whichever is applicable;)];

- 3. [Name of Bidder] is not "blacklisted" or barred from bidding by the Government of the Philippines or any of its agencies, offices, corporations, or Local Government Units, foreign government/foreign or international financing institution whose blacklisting rules have been recognized by the Government Procurement Policy Board, <u>by itself or by relation, membership, association, affiliation, or controlling interest with another blacklisted person or entity as defined and provided for in the Uniform Guidelines on Blacklisting;</u>
- 4. Each of the documents submitted in satisfaction of the bidding requirements is an authentic copy of the original, complete, and all statements and information provided therein are true and correct;
- 5. [Name of Bidder] is authorizing the Head of the Procuring Entity or its duly authorized representative(s) to verify all the documents submitted;
- 6. [Select one, delete the rest:]

[*If a sole proprietorship:*] The owner or sole proprietor is not related to the Head of the Procuring Entity, members of the Bids and Awards Committee (BAC), the Technical Working Group, and the BAC Secretariat, the head of the Project Management Office or the end-user unit, and the project consultants by consanguinity or affinity up to the third civil degree;

[*If a partnership or cooperative:*] None of the officers and members of [*Name of Bidder*] is related to the Head of the Procuring Entity, members of the Bids and Awards Committee (BAC), the Technical Working Group, and the BAC Secretariat, the head of the Project Management Office or the end-user unit, and the project consultants by consanguinity or affinity up to the third civil degree;

[If a corporation or joint venture:] None of the officers, directors, and controlling stockholders of *[Name of Bidder]* is related to the Head of the Procuring Entity, members of the Bids and Awards Committee (BAC), the Technical Working Group, and the BAC Secretariat, the head of the Project Management Office or the end-user unit, and the project consultants by consanguinity or affinity up to the third civil degree;

- 7. [Name of Bidder] complies with existing labor laws and standards; and
- 8. *[Name of Bidder]* is aware of and has undertaken the responsibilities as a Bidder in compliance with the Philippine Bidding Documents, which includes:
 - a. Carefully examining all of the Bidding Documents;
 - b. Acknowledging all conditions, local or otherwise, affecting the implementation of the Contract;
 - c. Making an estimate of the facilities available and needed for the contract to be bid, if any; and
 - d. Inquiring or securing Supplemental/Bid Bulletin(s) issued for the [Name of the Project].
- 9. *[Name of Bidder]* did not give or pay directly or indirectly, any commission, amount, fee, or any form of consideration, pecuniary or otherwise, to any person or official, personnel or representative of the government in relation to any procurement project or activity.
- 10. <u>In case advance payment was made or given, failure to perform or deliver any of the obligations and undertakings in the contract shall be sufficient grounds to constitute criminal liability for Swindling (Estafa) or the commission of fraud with unfaithfulness or abuse of confidence through misappropriating or converting any payment received by a person or entity under an obligation involving the duty to deliver certain goods or services, to the prejudice of the public and the government of the Philippines pursuant to Article 315 of Act No. 3815 s. 1930, as amended, or the Revised Penal Code.</u>

IN WITNESS WHEREOF, I have hereunto set my hand this ____ day of ____, 20___ at _____, Philippines.

[Insert NAME OF BIDDER OR ITS AUTHORIZED REPRESENTATIVE] [Insert signatory's legal capacity] Affiant

[Jurat] [Format shall be based on the latest Rules on Notarial Practice]

REPUBLIC OF THE PHILIPPINES) CITY OF ______) S.S.

BID SECURING DECLARATION Project Identification No.: *[Insert number]*

To: [Insert name and address of the Procuring Entity]

I/We, the undersigned, declare that:

- 1. I/We understand that, according to your conditions, bids must be supported by a Bid Security, which may be in the form of a Bid Securing Declaration.
- 2. I/We accept that: (a) I/we will be automatically disqualified from bidding for any procurement contract with any procuring entity for a period of two (2) years upon receipt of your Blacklisting Order; and, (b) I/we will pay the applicable fine provided under Section 6 of the Guidelines on the Use of Bid Securing Declaration, within fifteen (15) days from receipt of the written demand by the procuring entity for the commission of acts resulting to the enforcement of the bid securing declaration under Sections 23.1(b), 34.2, 40.1 and 69.1, except 69.1(f), of the IRR of RA No. 9184; without prejudice to other legal action the government may undertake.
- 3. I/We understand that this Bid Securing Declaration shall cease to be valid on the following circumstances:
 - a. Upon expiration of the bid validity period, or any extension thereof pursuant to your request;
 - b. I am/we are declared ineligible or post-disqualified upon receipt of your notice to such effect, and (i) I/we failed to timely file a request for reconsideration or (ii) I/we filed a waiver to avail of said right; and
 - c. I am/we are declared the bidder with the Lowest Calculated Responsive Bid, and I/we have furnished the performance security and signed the Contract.

IN WITNESS WHEREOF, I/We have hereunto set my/our hand/s this _____ day of [month] [year] at [place of execution].

[Insert NAME OF BIDDER OR ITS AUTHORIZED REPRESENTATIVE] [Insert signatory's legal capacity] Affiant

[Jurat]

[Format shall be based on the latest Rules on Notarial Practice]

